

RC-Pier LRFD T-Pier Example

1203 Jefferson
223' x 40' PPCB Bridge
(Three Spans: 70.75' – 91.5' – 60.75')
32 deg LA Skew
T-Piers on Pile Footings
Integral Abutments

Office Example
10-10-2010

Table of Contents

Title Page	1
Table of Contents	2
RC-Pier Version	3
Notes & Issues	4
General RC-Pier Layout Geometry	5 to 6
Assemble Program Input	7 to 88
Superstructure Dead Load	7 to 13
Live Load	14 to 59
Methods to Calculate Pier Live Loads	14 to 15
Controlling Live Load Pier Reactions	16
Software Problem Logs for QConBridge	17 to 18
QConBridge Screen Captures	19 to 20
QConBridge Run 1 for Maximum Live Load Pier Reaction	21 to 31
QConBridge Run 2 for Truck Portion	32 to 42
QConBridge Run 3 for Lane Portion	43 to 53
Spreadsheet Results for Distribution of Live Load to Beams	54 to 59
Geometrical Considerations for Various Loadings	60
Temperature Forces	61 to 65
Braking Forces	66 to 69
Water Elevations: Case 1-3 Loadings	70 to 72
Stream Flow, Buoyancy, and Ice Forces	73 to 78
Wind Forces	79 to 88
Cap and Column Design	89 to 146
Case 1 Loading	90 to 137
RC-Pier Input Screen Captures for Case 1 Loading	90 to 110
RC-Pier Cap Design	111 to 117
Spreadsheet for Cap Design	118 to 123
RC-Pier Column Design	124 to 130
spColumn	131 to 135
Column Moment Magnification	136 to 137
RC-Pier Input Screen Captures for Case 2 Loading	138 to 141
RC-Pier Input Screen Captures for Case 3 Loading	142 to 146
Footing Design	147 to 176
Case 1 Loading	147 to 167
RC-Pier Input Screen Captures for Case 1 Loading	148 to 154
RC-Pier Footing Design	155 to 164
Spreadsheet for Cap Design	165 to 167
RC-Pier Input Screen Captures for Case 2 Loading	168 to 171
RC-Pier Input Screen Captures for Case 3 Loading	172 to 176
1203 Jefferson Plan Set	177 to 222

About LEAP® RC-PIER® V8i (SELECTseries1)



LEAP® RC-PIER® V8i (SELECTseries1)

Version 09.00.03.01
Copyright © 1999-2010

Example is based on
this version of RC-Pier

This product is licensed to:

mnop
IOWA DOT

SELECT Server Name: selectserver.bentlev.com



Development Team...

Copyright © 2010 Bentley Systems, Incorporated. All Rights Reserved.

Including software, file formats, and audio-visual displays; may be used pursuant to applicable software license agreement; contains confidential and proprietary information of Bentley Systems and/or third parties which is protected by copyright and trade secret law and may not be provided or otherwise made available without proper authorization.

Trademark Notice

Bentley, the "B" Bentley logo, and MicroStation are registered or non-registered trademarks of Bentley Systems, Inc. or Bentley Software, Inc. All other marks are the property of their respective owners.

Disclaimer

Although this program has been written and tested by Bentley Systems Inc., no warranty, expressed or implied, is made as to the accuracy or functioning of the program and related program material. In no event will Bentley Systems Inc. be liable for any damages, including, without limitation, incidental and consequential damages and damages for lost data or profits, arising out of the use of or inability to use the licensed

System Info

Operating System: Windows XP Service Pack 3
Processor: GenuineIntel, x86 Family 15 Model 4 Stepping 1, Speed 3,590 MHz
Physical Memory: 1,022 Mb Available Memory: 408 Mb
Available Disk Space: 30,856 Mb on Drive W:

OK

Legal Notices...

Notes and Issues

- 1.) The primary intent of this example is to illustrate the use of RC-Pier, not to show every aspect of a pier design.
- 2.) Pier No. 1 of the west bound bridge from 1203 Jefferson forms the basis of this example. In general pier dimensions and reinforcement will not deviate from the existing plans (which are not based on an LRFD design) unless necessary to better illustrate some aspect of RC-Pier or LRFD.
- 3.) Bridge Office preference is to establish column fixity at the base of the column for the cap and column design and then establish fixity at the base of the footing for the footing and pile design. This policy has a few implications as stated below:
 - Foundation springs due to pile flexibility may be incorporated into both models.
 - For the footing/pile analysis designers may extend the column in RC-Pier to the bottom of the footing, but designers will not be required to increase the column inertia over the depth of the footing in order to model the footing's properties.
 - In general, the idea is that the applied loads will not have to be adjusted in RC-Pier due to the column height change between the two models. The loads that would typically be affected for a T-pier by the change in model geometry are column self-weight, column buoyancy, stream flow loading, ice loading, and wind on substructure. Because a number of loads are affected for T-piers it is usually a good idea to adjust the loads.
 - The designer should determine superstructure temperature loads based on pier fixity at the bottom of the column (with foundations springs if desired).
- 4.) The Bridge Office typically bases wind loading forces on the requirements for "usual girder and slab bridges" from AASHTO LRFD Articles 3.8.1.2.2 and 3.8.1.3 when BDM requirements are met. Iowa allows the use of these provisions for span lengths up to 155' (this is meant to include bridges using Iowa's longest prestressed beam, BTE155) and for top of railing elevations not exceeding 100'. Substructure wind loading is then assumed to be 40 psf in the longitudinal and transverse directions simultaneously. In RC-Pier it is recommended the designer both apply and exclude the wind uplift force from all load combinations since it is conservative and requires less bookkeeping.
- 5.) There are various issues with RC-Pier version V8i (09.00.03.01). These issues are addressed as they come up in this example.
- 6.) The Iowa DOT Bridge Design Manual shall be consulted for the most up-to-date DOT policies.

General RC-Pier Layout Geometry

(Figures on this page and the next are taken from the RC-Pier User Manual)




Figure TH-4 Bridge Pier Looking Upstation

Notes

- 1.) Recommend Upstation View over Downstation View.
- 2.) Generally Iowa uses only one bearing line in RC-Pier for typical steel and prestressed beam bridges.




Figure TH-5 Bridge Pier Details in Upstation View

Skew Angle (in degrees)

The skew angle is defined as the angle between the normal to the centerline of the bridge and the centerline of the pier cap (in positive X-direction). It is positive if measured in counterclockwise direction, as shown in [Figure TH-9](#). Note that the skew angle is used only for auto load generation.




Figure TH-9 Bridge with Piers at Skew
(Modified Coordinate System)

Notes

- 1.) Redrew coordinate system to make it consistent with Upstation View.
- 2.) In RC-Pier the global coordinate system rotates with the skew.
- 3.) Right ahead skews are positive. Left ahead skews are negative.
- 4.) Face the pier looking in the negative Z-axis direction.

Dead Load: DC1, DC2, and DW

- 1.) RC-Pier can auto-generate these loads, but there are some drawbacks with doing it this way. Typically the DC1 loads are underestimated because the haunch, intermediate diaphragm, pier diaphragm, and the slab thickening on the overhang are not included. The distribution to the various beams is also based on tributary deck width which doesn't always correlate with Bridge Design Manual policy. So, in general, it is typically better to calculate these apart from RC-Pier and input them manually.
- 2.) The spreadsheet on the following pages can be used to generate loads for typical prestressed beam bridges. Hand calculations have also been provided as a check.

Pier Dead Load Beam Reactions for Interior and Exterior P/S Beams

Pier beam reactions consider only unfactored superstructure DC and DW loads.

Number of Spans	3	Can be 2 to 6 spans.
Beam Type	D	Beam type must be the same for each span. The bridge being checked has the "old" LXD beams which are quite similar to the current D beams.
Span 1 Beam Size	D70	
Span 2 Beam Size	D90	
Span 3 Beam Size	D60	
Span 4 Beam Size	---	
Span 5 Beam Size	---	
Span 6 Beam Size	---	
Pier Number of Interest	1	Can be 1, 2, 3, 4, or 5 depending on number of spans.

Default Override	Description	Units	Default	Input/Override	Value Used
<input type="checkbox"/> Default Override	Span 1 Beam Length, end to end	ft	71.000		71.000
<input type="checkbox"/> Default Override	Span 2 Beam Length, end to end	ft	91.000		91.000
<input type="checkbox"/> Default Override	Span 3 Beam Length, end to end	ft	61.000		61.000
<input type="checkbox"/> Default Override	Span 4 Beam Length, end to end	ft	5.000		5.000
<input type="checkbox"/> Default Override	Span 5 Beam Length, end to end	ft	5.000		5.000
<input type="checkbox"/> Default Override	Span 6 Beam Length, end to end	ft	5.000		5.000
<input type="checkbox"/> Default Override	Span 1 Beam Length, c.l. to c.l. bearing	ft	70.000		70.000
<input type="checkbox"/> Default Override	Span 2 Beam Length, c.l. to c.l. bearing	ft	90.000		90.000
<input type="checkbox"/> Default Override	Span 3 Beam Length, c.l. to c.l. bearing	ft	60.000		60.000
<input type="checkbox"/> Default Override	Span 4 Beam Length, c.l. to c.l. bearing	ft	5.000		5.000
<input type="checkbox"/> Default Override	Span 5 Beam Length, c.l. to c.l. bearing	ft	5.000		5.000
<input type="checkbox"/> Default Override	Span 6 Beam Length, c.l. to c.l. bearing	ft	5.000		5.000
<input type="checkbox"/> Default Override	Distance bt. Beam Ends on Pier 1	in	6.000		6.000
<input type="checkbox"/> Default Override	Distance bt. Beam Ends on Pier 2	in	6.000		6.000
<input type="checkbox"/> Default Override	Distance bt. Beam Ends on Pier 3	in	5.000		5.000
<input type="checkbox"/> Default Override	Distance bt. Beam Ends on Pier 4	in	5.000		5.000
<input type="checkbox"/> Default Override	Distance bt. Beam Ends on Pier 5	in	5.000		5.000

Distance bt. Centerline Bearings on Pier 1	ft	1.500		1.500
--	----	-------	--	-------

Roadway Width (Gutter to Gutter)	ft		40.000	40.000
Number of Beams in Cross-Section			6.000	6.000

FWS Load	ksf		0.020	0.020
SBC Load - Includes Both Rails	klf		0.852	0.852

<input type="checkbox"/> Default Override	FWS Distribution Factor for Exterior Beam (*)		0.167	0.167
<input type="checkbox"/> Default Override	FWS Distribution Factor for Interior Beam (*)		0.167	0.167
<input type="checkbox"/> Default Override	SBC Distribution Factor for Exterior Beam (*)		0.167	0.167
<input type="checkbox"/> Default Override	SBC Distribution Factor for Interior Beam (*)		0.167	0.167

* Default is an equal distribution of the FWS and SBC loads among all the beams in the cross-section.

<input type="checkbox"/> Default Override	Pier 1 Reaction Due to 1.00 klf Distributed Load (**)	kips	91.868	91.868
---	---	------	--------	--------

** The pier rxn is used as a ratio to distribute FWS and SBC loads to the pier. It is based on span continuity and a 1.00 klf distr. load.

<input type="checkbox"/> Default Override	Exterior Beam Reaction for FWS	kips	12.249	12.249
<input type="checkbox"/> Default Override	Interior Beam Reaction for FWS	kips	12.249	12.249
<input type="checkbox"/> Default Override	Exterior Beam Reaction for SBC	kips	13.045	13.045
<input type="checkbox"/> Default Override	Interior Beam Reaction for SBC	kips	13.045	13.045

Bearing Pad Height at Pier 1 (+)	in		4.000	4.000
Beam Height at Pier 1	ft	4.500		4.500
Average Haunch Thickness for Spans 1 and 2	in		1.000	1.000
Max Haunch Thickness at Pier 1	in		2.000	2.000
Slab Thickness	in		8.000	8.000
Slab Cantilever Min. Thickness at Slab Edge	in		8.750	8.750
Slab Cantilever Max. Thickness at Flange Edge	in		10.250	10.250

+ Bearing pad height is only used in the calculation of pier diaphragm weight for fixed piers.

Top Flange Width	in	20.000		20.000
Beam Area	in^2	638.750		638.750

Beam Spacing Perpendicular to Roadway (++)	ft		7.401	7.401
Slab Cantilever Length (++)	ft		3.083	3.083

++ Beam spacing, slab cantilever length, number of beams, and roadway width should all be consistent.

	Skew, Always Positive	deg		32.000	32.000
<input type="checkbox"/> Default Override	No. of Intermediate Diaphragms in Span 1		1		1.000
	Enter: 1 = Steel Diaphragm, 2 = Concrete Diaphragm			1	1.000
<input type="checkbox"/> Default Override	Weight of One Intermediate Diaphragm in Span 1	kips	0.281		0.281
<input type="checkbox"/> Default Override	No. of Intermediate Diaphragms in Span 2		1		1.000
	Enter: 1 = Steel Diaphragm, 2 = Concrete Diaphragm			1	1.000
<input type="checkbox"/> Default Override	Weight of One Intermediate Diaphragm in Span 2	kips	0.281		0.281

Perpendicular Thickness of Pier Diaphragm	ft		2.667	2.667
Perp. Extension of Pier Diaph. Past C.L. Ext. Beam (#)	ft		1.583	1.583
Enter: 1 = Fixed Pier, 2 = Expansion Pier			2	2.000

If the pier diaphragm is flush with the exterior side of the exterior beam then enter 0.

Pier 1 Component	Load Type	Unfactored Beam Reactions (includes both spans)	
		Interior Beam kips	Exterior Beam kips
Beam	DC1	53.895	53.895
Slab	DC1	60.318	58.723
Haunch	DC1	1.688	1.688
Intermediate Diaphragms	DC1	0.281	0.141
Pier Diaphragm	DC1	14.423	9.213
SBC	DC2	13.045	13.045
Total (##)	DC Total	143.649	136.704

FWS	DW	12.249	12.249
-----	----	--------	--------

Some designers include pier cap step weight in the beam reactions. That weight is not included here.

	Interior	Exterior
DC1 Pier Cap Step Weight	2.615 k	0.000 k
	<u>143.649 k</u>	<u>136.704 k</u>
Total DC	146.264 k	136.704 k
Total DW	12.249 k	12.249 k

See hand calculations on following sheets for more information.

Pier cap step weight is not included here.


These loads will be used in RC-Pier for the general T-Pier design. The loads for the pier cap overhang will be different.

Hand Calculations for Superstructure Beam Dead Load Reactions

1.) Beam - DC1

Interior & Exterior Beams

$$(0.5) * (71 \text{ ft} + 91 \text{ ft}) * [(638.75 \text{ in}^2) / (144 \text{ in}^2/\text{ft}^2)] * (0.150 \text{ kcf}) = \underline{53.895 \text{ k}}$$




2.) Slab - DC1

Interior Beam

$$(7.401') * [(8'') / (12 \text{ in}^2/\text{ft}^2)] * [(0.5) * (70' + 90') + 1.5'] * (0.150 \text{ kcf}) = \underline{60.318 \text{ k}}$$

Exterior Beam

$$\begin{aligned} & \{ [(0.5) * (7.401') + 3.083'] * [(8'') / (12 \text{ in}^2/\text{ft}^2)] + \\ & [3.083' - (0.5) * (20'') / (12 \text{ in}^2/\text{ft}^2)] * [0.75'' + (0.5) * (1.5'')] / (12 \text{ in}^2/\text{ft}^2) \} * \\ & [(0.5) * (70') + (0.5) * (90') + 1.5'] * (0.150 \text{ kcf}) = \underline{58.723 \text{ k}} \end{aligned}$$



3.) Haunch - DC1

Interior & Exterior Beams

$$[(1'') * (20'') / (144 \text{ in}^2/\text{ft}^2)] [(0.5) * (70') + (0.5) * (90') + 1'] * (0.150 \text{ kcf}) = \underline{1.688 \text{ k}}$$

4.) Intermediate Steel Diaphragm – DC1

(One steel diaphragm per span; based on LXD beam data in plan set the diaphragm weighs 0.285 k for 7.5' beam spacing)


Interior Beam

$$\{(0.285 \text{ k}) \cdot (7.401' / 7.5') = \underline{0.281 \text{ k}}\}$$

Exterior Beam


$$(0.5) \cdot (0.281 \text{ k}) = \underline{0.141 \text{ k}}$$

5.) Pier Diaphragm – DC1



Interior Beam

$$\begin{aligned} &\{(7.401') \cdot [(2.667') / (\cos(32 \text{ deg}))] \cdot [4.5' + (2'') / (12 \text{ in/ft})] - \\ &[(638.75 \text{ in}^2 + (2'') \cdot (20'')) / (144 \text{ in}^2/\text{ft}^2)] \cdot [(2.667') / (\cos(32 \text{ deg})) - 0.5']\} \cdot \\ &(0.150 \text{ kcf}) = \underline{14.423 \text{ k}} \end{aligned}$$



Exterior Beam

$$\begin{aligned} &(0.5) \cdot (14.423 \text{ k}) + [4.5' + (2'') / (12 \text{ in/ft})] \cdot (1.583') \cdot [(2.667') / (\cos(32 \text{ deg})) - \\ &(0.5) \cdot (1.583') \cdot (\tan(32 \text{ deg}))] - (0.5) \cdot [(638.75 \text{ in}^2 + (2'') \cdot (20'')) / (144 \text{ in}^2/\text{ft}^2)] \cdot \\ &[(2.667') / (\cos(32 \text{ deg})) - 0.5'] \cdot (0.150 \text{ kcf}) = \underline{9.213 \text{ k}} \end{aligned}$$

5.) Pier Diaphragm – DC1

For simplicity we generally assume the pier step load acts through the interior beams.

Interior Only

Average Step Height = 4.88” average of all six beam seat elevations

Pier Cap Width = 3.5’

Average Total Step Length Along Pier Cap = 49’ approximately

$$[(4.88'')/(12 \text{ in/ft})]*(3.5')*(49')*(0.150 \text{ kcf})/(4 \text{ Int. Beams}) = \underline{2.615 \text{ k}}$$

6.) SBC – DC2

Interior & Exterior Beams

Area of One SBC = 2.84 ft²

Reaction from QConBridge Due to 1.00 k/ft Uniform Dead Load = 91.868 k

$$(2 \text{ SBC})*(2.84 \text{ ft}^2)*(0.150 \text{ kcf})*[(91.868 \text{ k})/(1.00 \text{ k/ft})]/(6 \text{ Beams}) = \underline{13.045 \text{ k}}$$

7.) FWS – DW

Interior & Exterior Beams

$$(0.020 \text{ ksf})*(40')*[(91.868 \text{ k})/(1.00 \text{ k/ft})]/(6 \text{ Beams}) = \underline{12.249 \text{ k}}$$

Total Dead Load

DC Load

		<u>Interior</u>	<u>Exterior</u>
DC1	Beam	53.895 k	53.895 k
	Slab	60.318 k	58.723 k
	Haunch	1.688 k	1.688 k
	Intern. Diaph.	0.281 k	0.141 k
	Pier Diaph.	14.423 k	9.213 k
	Pier Steps	2.615 k	0.000 k
DC2	SBC	<u>13.045 k</u>	<u>13.045 k</u>
Total DC		146.264 k	136.704 k

DW Load

	<u>Interior</u>	<u>Exterior</u>
FWS	12.249 k	12.249 k

Live Load: LL

There are a number of ways live load can be done in RC-Pier.

- 1.) Use QConBridge to get the live load pier reaction. Move the live load(s) transversely back and forth across the deck width and determine the beam reactions for those arrangements that maximize force effects in the pier. Typically placement of live load for maximum force effects can be done intuitively. The spreadsheet on the following pages facilitates this method and consequently is used for this example.
- 2.) Another method is to use RC-Pier's auto-generation feature for determination of live loads. The program is capable of determining the pier live load reaction for a continuous bridge with a constant moment of inertia. (For this example I checked the live load reaction QConBridge came up with against RC-Pier's value and the two compared quite well.) The user can use RC-Pier's live load reaction, import it from Conspan, or enter their own. Once RC-Pier has this determined there are basically two ways to obtain the actual live load cases.
 - a.) Variable spacing
 - b.) Constant spacing

Auto Load generation: Live Load

Longitudinal Reaction

Compute Simple Span Reaction

Available:

- Design Truck
- Design Truck + Lane Load
- Design Tandem + Lane Load
- Two Design Trucks + Lane Load
- Two Design Tandem + Lane Load
- Fatigue Truck
- [FV]P-5 Truck
- [FV]P-7 Truck

Selected:

- Design Truck + Lane Load
- Design Tandem + Lane Load
- Two Design Trucks + Lane Load

Compute Continuous Beam Reaction

Input Already Computed Reaction

Import Conspan Reaction

Normal pier

Max Truck Load: 0 kips

Max Lane Load: 0 kips

Normal pier

Max Truck Load: 0 kips

Max Lane Load: 0 kips

Integral pier

	Max Load,	Moment, k-ft	Load, kips	Max. Moment,
Truck:				
Lane:				

Reaction distribution among bearing lines

	Bearing Line 1	Bearing Line 2
Truck Case A:	1	0
Lane Case A:	1	0
Truck Case B:	0	0
Lane Case B:	0	0

Generate Reverse Cases also

Transverse Positioning

Loaded Lanes: All combinations

Live Load Positions

Variable spacing

Minimum spacing between positions: 0 ft

Constant spacing

Minimum distance from curb: 2 ft

Center to center spacing: 10 ft

Longitudinal Force

Generate Longitudinal Load Cases also

Auto Compute Manual input

Truck Load: 0 kips

Lane Load: 0 kips

Centrifugal Force

Generate Centrifugal Load Cases also

Auto Compute Manual input

Truck Load: 0 kips

Radius of curve: 0 ft

Design speed: 0 ft/s

Direction of centrifugal force: +[X] -[X]

Generate **Cancel**

RC-Pier's manual explains how the two methods work. Essentially each method follows an algorithm for determining how many different live load positions are possible. The program then seeks to maximize forces for each member and keeps only the live load arrangements that do this. In general the variable spacing method is going to check more possibilities and thus produce more live load cases (especially with 0' as the "Minimum spacing between positions"). This in turn will increase the number of load combinations and computing time. However, for the settings shown above the variable spacing method and constant spacing method both come up with 5 different live load cases.

Note:

When live loads are auto-generated in RC-Pier the user can review some of the processes RC-Pier went through in order to determine the live load cases. There is a "LL details" button on the Loads tab screen that brings this information up. One shortcoming of RC-Pier is that the information for the truck positions in these details is based on a downstation view of the pier even when the user is working in the upstation view mode. I've contacted the developers and they are already aware of the inconsistency and it is on their list of things to fix.

Live Load

QConBridge Runs are on the following pages.

Run 1:

This was done to determine what live load controls for the pier reaction. The dual truck train with lane controlled.

Max. LL + I = 168.615 k	Dual Truck Train + Lane
	Impact
	Axle Load
	Unfactored

Run 2:

This was done to determine the truck portion of the controlling live load since RC-Pier entry requires the truck and lane to be separated in order to track impact application for the various pier components.

Dual Truck Rxn = 85.662 k	No Lane
	No Impact
	Axle Load
	Unfactored

Run 3:

This was done to determine the lane portion of the controlling live load since RC-Pier entry requires the truck and lane to be separated in order to track application for the various pier components.

Dual Lane Rxn = 54.683 k	No Truck
	No Impact
	Axle Load
	Unfactored

Check: $(85.662 \text{ k}) \cdot (1.33) + 54.683 \text{ k} = 168.613 \text{ k}$

Note: The dual truck train + lane often controls the pier reaction. It needs to be remembered that the truck and lane weights are reduced to 90% and that this reduction is already included in the reactions above.

The next page details how the reactions for the truck and lane can be obtained separately in QConBridge.

QConBridge Version 1.3

Getting Truck Load and Lane Load Separately for HL-93 Loading.

This description is taken directly from the Washington DOT website:

<http://www.wsdot.wa.gov/eesc/bridge/software/>

Q2 How can I get the truck load and lane load results separately?

A2 The HL93 Live Load model consists of the truck and lane applied simultaneously, along with appropriate dynamic load allowance (impact) factors. This is how QConBridge approaches the problem, so there is no direct way to separate the truck and lane response.

However, there is a "trick" that you can use to "turn off" either the truck or lane load. The trick is to use a dynamic load allowance of -100% for the load component you want to turn off. Truck and lane responses are scaled by $(1.0 + IM/100)$ where IM is the applicable dynamic load allowance factor. Using a factor of -100% the response is scaled by $(1.0 + -100/100) = 0.0$, which, in effect, "turns off" the response.


To modify the dynamic load allowance, select Loads | Dynamic Load Allowance... Enter a value of -100% for **either** Truck or Lane. Press the OK button and run the analysis.

Thanks to Dr. Harry Cole from the Mississippi State University for sharing this tip. (Go Bulldogs)

QConBridge Version 1.3


Minimum Number of Analysis Points

Use a minimum of 10 analysis points for any QConBridge run. QConBridge uses a finer influence line as more analysis points are used. Every axle on every truck is placed at every analysis point. If you decrease the number of points from 10 your results will likely be off by a significant percentage. In order to get reasonable results the minimum default value of 10 analysis points should be used. You can also use more than 10 analysis points, but this isn't typically necessary and as you increase the number of analysis points you increase the time of execution which can be substantial for bridges with a large number of spans.




Load Factors

Typically we are only interested in unfactored LL pier reactions from QConBridge. However, it is worth noting that changing the load factors in QConBridge Version 1.3 does show the change in the load factors in the output's echo of the input, but the results for the limit states are not affected. The default load factors always seem to be used in the factored results.



QConBridge - QCon01.qcb

File Edit Span/Support Loads Bridge Options View Window Help


MVTR

Editor

HScale: 25. ft/inch - VScale: 0.0 ft/inch

DC Dead Load	DW Dead Load	Self Weight : Disabled
Traffic Barrier : 1.000e+03 lbs/ft	Utility : Disabled	Overlay : Disabled
Pedestrian Ld : 0.000e+00 lbs/ft		

1 2 3 4
 ← ← ← ←
 1 2 3 4
 70.750 ft 91.500 ft 60.750 ft

Modified

Standard Dead Loads

DC Loads | DW Loads

Generate Self Weight Dead Load

Traffic Barrier 1000.000 lbs/ft

OK Cancel Help

Get pier reaction for a 1.00 k/ft loading on the continuous structure.

Live Load Generation Parameters

Dual Truck Train | Dual Tandem Train | Fatigue Truck

Design Tandem | Design Truck

Disable Load Generator

OK Cancel Help

Live Load Generation Parameters

Dual Truck Train | Dual Tandem Train | Fatigue Truck

Design Tandem | Design Truck


Disable Load Generator

Enter number of rear axle spacings to be used for live load generation

17

OK Cancel Help

This is probably quite a few more increments than needed to get the maximum pier reaction and, consequently, may cause QConBridge to run for quite awhile. To save time the user could decrease the number of increments or use a larger number of increments for a shorter headway spacing in Range 1 and then use less increments with larger headway spacing in Ranges 2 and 3.



Live Load Generation Parameters

Design Tandem | Design Truck

Dual Truck Train | Dual Tandem Train | Fatigue Truck

Disable Load Generator

Variable Headway Spacing Parameters

Range 1 50. feet To 223. feet Using 173. Increments

Range 2 49. feet To 49. feet Using 1. Increments

Range 3 49. feet To 49. feet Using 1. Increments

OK Cancel Help

Live Load Generation Parameters

Design Tandem | Design Truck

Dual Truck Train | Dual Tandem Train | Fatigue Truck

Disable Load Generator

Variable Headway Spacing Parameters

Range 1 26. feet To 39. feet Using 1. Increments

Range 2 26. feet To 39. feet Using 1. Increments

Range 3 26. feet To 39. feet Using 1. Increments

OK Cancel Help

Normally we do not consider the Dual Tandem Train and we may ignore the Fatigue Truck for typical pier designs.

Dynamic Load Allowance

Truck 33.000 %

Lane 0.000 %

Fatigue 15.000 %

OK Cancel Help

Total Bridge Length

$(223'-50')/1' = 173$

Values shown are for Run 1. These will be adjusted for Runs 2 and 3.

Washington State Department of Transportation
Bridge and Structures Office
QConBridge Version 1.0

QConBridge

Run 1 Output

Max LL+I Rxn = 168.615 k

Dual Truck Train +
Lane Controls

Rxn Due to 1.00 k/ft Uniform Load = 91.868 k

Code: LRFD First Edition 1994

Span Data

Span 1 Length: 70.750 ft

Section Properties

Location (ft)	Ax (in ²)	Iz (in ⁴)	Mod. E (psi)	Unit Wgt (pcf)
0.000	1.000e+00	999.999e-03	1.000e+03	999.997e-03

Live Load Distribution Factors

Location (ft)	Str/Serv gM	Limit States gV	Fatigue Limit gM	State gV
0.000	1.000	1.000	1.000	1.000

Strength Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Service Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Span 2 Length: 91.500 ft

Section Properties

Location (ft)	Ax (in ²)	Iz (in ⁴)	Mod. E (psi)	Unit Wgt (pcf)
0.000	1.000e+00	999.999e-03	1.000e+03	999.997e-03

Live Load Distribution Factors

Location (ft)	Str/Serv gM	Limit States gV	Fatigue Limit gM	State gV
0.000	1.000	1.000	1.000	1.000

Strength Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Service Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Span 3 Length: 60.750 ft

Section Properties

Location (ft)	Ax (in ²)	Iz (in ⁴)	Mod. E (psi)	Unit Wgt (pcf)
0.000	1.000e+00	999.999e-03	1.000e+03	999.997e-03

Live Load Distribution Factors

Location (ft)	Str/Serv gM	Limit States gV	Fatigue Limit gM	State gV
0.000	1.000	1.000	1.000	1.000

Strength Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Service Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Support Data

Support 1 Roller

Support 2 Pinned

Support 3 Pinned

Support 4 Roller

Loading Data

DC Loads

Self Weight Generation Disabled
Traffic Barrier Load 1.000e+03 plf

DW Loads

Utility Load Disabled
Wearing Surface Load Disabled


Live Load Data

Live Load Generation Parameters

Design Tandem : Enabled
Design Truck : 17 rear axle spacing increments
Dual Truck Train : Headway Spacing varies from 50.000 ft to 223.000 ft using 173 increments
Dual Tandem Train: Disabled
Fatigue Truck : Disabled

Live Load Impact

Truck Loads 33.000%
Lane Loads 0.000%
Fatigue Truck 15.000%



Pedestrian Live Load 0.000e+00 plf

Load Factors

	DC min	DC max	DW min	DW max	LL	
Strength I	0.900	1.250	0.650	1.500	1.750	
Service I	1.000	1.000	1.000	1.000		
Service II	1.000	1.000	1.000	1.300		
Service III	1.000	1.000	1.000	0.800		
Fatigue	0.000	0.000	0.000	0.750		

Analysis Results

DC Dead Load

Span	Point	Shear (lbs)	Moment (ft-lbs)
1	0	25.587e+03	0.000e+00
1	1	18.512e+03	156.005e+03
1	2	11.437e+03	261.956e+03
1	3	4.362e+03	317.850e+03
1	4	-2.712e+03	323.689e+03
1	5	-9.787e+03	279.473e+03
1	6	-16.862e+03	185.200e+03
1	7	-23.937e+03	40.872e+03
1	8	-31.012e+03	-153.510e+03
1	9	-38.087e+03	-397.949e+03
1	10	-45.162e+03	-692.444e+03
2	0	46.706e+03	-692.444e+03
2	1	37.556e+03	-306.943e+03
2	2	28.406e+03	-5.165e+03

2	3	19.256e+03	212.890e+03
2	4	10.106e+03	347.223e+03
2	5	956.236e+00	397.834e+03
2	6	-8.193e+03	364.722e+03
2	7	-17.343e+03	247.888e+03
2	8	-26.493e+03	47.331e+03
2	9	-35.643e+03	-236.947e+03
2	10	-44.793e+03	-604.948e+03
3	0	40.333e+03	-604.948e+03
3	1	34.258e+03	-378.378e+03
3	2	28.183e+03	-188.714e+03
3	3	22.108e+03	-35.955e+03
3	4	16.033e+03	79.898e+03
3	5	9.958e+03	158.845e+03
3	6	3.883e+03	200.887e+03
3	7	-2.191e+03	206.024e+03
3	8	-8.266e+03	174.255e+03
3	9	-14.341e+03	105.580e+03
3	10	-20.416e+03	0.000e+00

DC Dead Load

Pier	Fx (lbs)	Fy (lbs)	Mz (ft-lbs)
1	0.000e+00	25.587e+03	0.000e+00
2	0.000e+00	91.868e+03	0.000e+00
3	0.000e+00	85.126e+03	0.000e+00
4	0.000e+00	20.416e+03	0.000e+00

DW Dead Load

Span	Point	Shear (lbs)	Moment (ft-lbs)
1	0	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00
1	2	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00
1	9	0.000e+00	0.000e+00
1	10	0.000e+00	0.000e+00
2	0	0.000e+00	0.000e+00
2	1	0.000e+00	0.000e+00
2	2	0.000e+00	0.000e+00
2	3	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00
2	10	0.000e+00	0.000e+00
3	0	0.000e+00	0.000e+00
3	1	0.000e+00	0.000e+00
3	2	0.000e+00	0.000e+00
3	3	0.000e+00	0.000e+00
3	4	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00

DW Dead Load

Pier	Fx (lbs)	Fy (lbs)	Mz (ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00

Live Load Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	-14.367e+03	101.931e+03	0.000e+00	0.000e+00
1	1	-14.646e+03	86.026e+03	-101.651e+03	622.614e+03
1	2	-19.062e+03	70.997e+03	-203.303e+03	1.052e+06
1	3	-28.338e+03	56.973e+03	-304.954e+03	1.300e+06
1	4	-39.927e+03	44.078e+03	-406.606e+03	1.414e+06
1	5	-53.540e+03	32.427e+03	-508.258e+03	1.393e+06
1	6	-67.118e+03	22.129e+03	-609.909e+03	1.261e+06
1	7	-80.487e+03	14.442e+03	-711.561e+03	991.720e+03
1	8	-93.469e+03	8.392e+03	-813.213e+03	611.706e+03
1	9	-105.873e+03	3.453e+03	-1.032e+06	257.017e+03
1	10	-117.504e+03	2.274e+03	-1.573e+06	160.896e+03
2	0	-7.994e+03	117.918e+03	-1.573e+06	160.896e+03
2	1	-8.207e+03	106.088e+03	-901.750e+03	299.239e+03
2	2	-12.263e+03	90.862e+03	-571.975e+03	726.934e+03
2	3	-20.753e+03	75.328e+03	-483.464e+03	1.170e+06
2	4	-32.672e+03	60.032e+03	-399.425e+03	1.435e+06
2	5	-46.236e+03	45.485e+03	-315.385e+03	1.504e+06
2	6	-60.924e+03	32.197e+03	-319.357e+03	1.415e+06
2	7	-76.243e+03	20.618e+03	-368.032e+03	1.130e+06
2	8	-91.667e+03	12.489e+03	-428.013e+03	682.182e+03
2	9	-106.646e+03	11.161e+03	-805.037e+03	286.061e+03
2	10	-120.622e+03	10.963e+03	-1.452e+06	231.796e+03
3	0	-3.815e+03	110.822e+03	-1.452e+06	231.796e+03
3	1	-3.936e+03	101.262e+03	-1.025e+06	252.624e+03
3	2	-8.877e+03	89.149e+03	-887.211e+03	554.894e+03
3	3	-14.939e+03	76.561e+03	-776.310e+03	854.724e+03
3	4	-21.946e+03	63.624e+03	-665.408e+03	1.061e+06
3	5	-31.409e+03	50.501e+03	-554.507e+03	1.153e+06
3	6	-42.577e+03	38.165e+03	-443.605e+03	1.164e+06
3	7	-54.915e+03	28.371e+03	-332.704e+03	1.068e+06
3	8	-68.250e+03	19.412e+03	-221.803e+03	864.870e+03
3	9	-82.513e+03	18.490e+03	-110.901e+03	511.596e+03
3	10	-97.557e+03	18.255e+03	0.000e+00	0.000e+00

Unfactored Max
LL+I Rxn based
on all live loads:
Dual Truck Train
+ Lane Controls

Live Load Envelopes (Per Lane)

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	-14.367e+03	101.931e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-10.268e+03	168.615e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-14.779e+03	161.430e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-18.255e+03	97.557e+03	0.000e+00	0.000e+00

Design Tandem + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	-11.394e+03	83.906e+03	0.000e+00	0.000e+00
1	1	-11.673e+03	71.573e+03	-80.616e+03	520.357e+03
1	2	-19.062e+03	59.914e+03	-161.233e+03	895.860e+03
1	3	-28.338e+03	49.013e+03	-241.850e+03	1.131e+06
1	4	-37.886e+03	38.949e+03	-322.466e+03	1.233e+06
1	5	-47.591e+03	29.793e+03	-403.083e+03	1.219e+06
1	6	-57.328e+03	21.610e+03	-483.700e+03	1.102e+06
1	7	-66.968e+03	14.442e+03	-564.317e+03	883.849e+03

1	8	-76.398e+03	8.392e+03	-644.933e+03	578.388e+03
1	9	-85.410e+03	3.453e+03	-773.378e+03	257.017e+03
1	10	-93.919e+03	1.829e+03	-994.370e+03	129.405e+03
2	0	-6.429e+03	93.536e+03	-994.370e+03	129.405e+03
2	1	-6.643e+03	85.577e+03	-610.091e+03	299.239e+03
2	2	-12.263e+03	74.175e+03	-453.401e+03	673.313e+03
2	3	-20.337e+03	62.483e+03	-385.731e+03	1.024e+06
2	4	-29.741e+03	50.903e+03	-322.533e+03	1.240e+06
2	5	-40.185e+03	39.795e+03	-259.335e+03	1.304e+06
2	6	-51.356e+03	29.496e+03	-264.945e+03	1.224e+06
2	7	-62.913e+03	20.310e+03	-299.303e+03	992.989e+03
2	8	-74.485e+03	12.489e+03	-344.966e+03	639.750e+03
2	9	-85.696e+03	8.883e+03	-495.957e+03	286.061e+03
2	10	-96.049e+03	8.686e+03	-1.006e+06	183.640e+03
3	0	-3.022e+03	89.565e+03	-1.006e+06	183.640e+03
3	1	-3.841e+03	82.890e+03	-818.560e+03	252.624e+03
3	2	-8.877e+03	74.283e+03	-703.382e+03	529.003e+03
3	3	-14.939e+03	65.339e+03	-615.459e+03	774.302e+03
3	4	-21.946e+03	56.135e+03	-527.537e+03	948.056e+03
3	5	-29.936e+03	46.839e+03	-439.614e+03	1.035e+06
3	6	-38.763e+03	37.548e+03	-351.691e+03	1.039e+06
3	7	-48.392e+03	28.371e+03	-263.768e+03	949.468e+03
3	8	-58.755e+03	19.412e+03	-175.845e+03	749.513e+03
3	9	-69.779e+03	14.708e+03	-87.922e+03	434.238e+03
3	10	-81.384e+03	14.472e+03	0.000e+00	0.000e+00

Design Tandem + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	-11.394e+03	83.906e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-8.258e+03	126.299e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-11.708e+03	123.741e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-14.472e+03	81.384e+03	0.000e+00	0.000e+00

Design Truck + Lane Envelopes (Per Lane)

Span	Point	Min Shear(lbs)	Max Shear(lbs)	Min Moment(ft-lbs)	Max Moment(ft-lbs)
1	0	-14.367e+03	101.931e+03	0.000e+00	0.000e+00
1	1	-14.646e+03	86.026e+03	-101.651e+03	622.614e+03
1	2	-15.819e+03	70.997e+03	-203.303e+03	1.052e+06
1	3	-27.725e+03	56.973e+03	-304.954e+03	1.300e+06
1	4	-39.927e+03	44.078e+03	-406.606e+03	1.414e+06
1	5	-53.540e+03	32.427e+03	-508.258e+03	1.393e+06
1	6	-67.118e+03	22.129e+03	-609.909e+03	1.261e+06
1	7	-80.487e+03	13.755e+03	-711.561e+03	991.720e+03
1	8	-93.469e+03	6.781e+03	-813.213e+03	611.706e+03
1	9	-105.873e+03	3.209e+03	-962.692e+03	217.821e+03
1	10	-117.504e+03	2.274e+03	-1.204e+06	160.896e+03
2	0	-7.994e+03	117.918e+03	-1.204e+06	160.896e+03
2	1	-8.207e+03	106.088e+03	-749.507e+03	245.825e+03
2	2	-11.313e+03	90.862e+03	-571.975e+03	726.934e+03
2	3	-20.753e+03	75.328e+03	-483.464e+03	1.170e+06
2	4	-32.672e+03	60.032e+03	-399.425e+03	1.435e+06
2	5	-46.236e+03	45.485e+03	-315.385e+03	1.504e+06
2	6	-60.924e+03	32.197e+03	-319.357e+03	1.415e+06
2	7	-76.243e+03	20.618e+03	-368.032e+03	1.130e+06
2	8	-91.667e+03	11.808e+03	-428.013e+03	682.182e+03
2	9	-106.646e+03	11.161e+03	-593.322e+03	242.639e+03
2	10	-120.622e+03	10.963e+03	-1.236e+06	231.796e+03
3	0	-3.815e+03	110.822e+03	-1.236e+06	231.796e+03
3	1	-3.936e+03	101.262e+03	-1.025e+06	227.420e+03
3	2	-7.388e+03	89.149e+03	-887.211e+03	554.894e+03
3	3	-13.610e+03	76.561e+03	-776.310e+03	854.724e+03
3	4	-21.796e+03	63.624e+03	-665.408e+03	1.061e+06

3	5	-31.409e+03	50.501e+03	-554.507e+03	1.153e+06
3	6	-42.577e+03	38.165e+03	-443.605e+03	1.164e+06
3	7	-54.915e+03	26.390e+03	-332.704e+03	1.068e+06
3	8	-68.250e+03	19.194e+03	-221.803e+03	864.870e+03
3	9	-82.513e+03	18.490e+03	-110.901e+03	511.596e+03
3	10	-97.557e+03	18.255e+03	0.000e+00	0.000e+00

Design Truck + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	-14.367e+03	101.931e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-10.268e+03	155.520e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-14.779e+03	153.137e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-18.255e+03	97.557e+03	0.000e+00	0.000e+00

Dual Truck Train + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00	-731.891e+03	0.000e+00
1	9	0.000e+00	0.000e+00	-1.032e+06	0.000e+00
1	10	0.000e+00	0.000e+00	-1.573e+06	0.000e+00
2	0	0.000e+00	0.000e+00	-1.573e+06	0.000e+00
2	1	0.000e+00	0.000e+00	-901.750e+03	0.000e+00
2	2	0.000e+00	0.000e+00	-521.373e+03	0.000e+00
2	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00	-805.037e+03	0.000e+00
2	10	0.000e+00	0.000e+00	-1.452e+06	0.000e+00
3	0	0.000e+00	0.000e+00	-1.452e+06	0.000e+00
3	1	0.000e+00	0.000e+00	-1.025e+06	0.000e+00
3	2	0.000e+00	0.000e+00	-798.490e+03	0.000e+00
3	3	0.000e+00	0.000e+00	-698.679e+03	0.000e+00
3	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Dual Truck Train + Lane Controls

Dual Truck Train + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-9.241e+03	168.615e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-13.301e+03	161.430e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Dual Tandem Train + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00

1	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Dual Tandem Train + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Fatigue Truck Envelopes (Per Lane)

Span	Point	Min Shear(lbs)	Max Shear(lbs)	Min Moment(ft-lbs)	Max Moment(ft-lbs)
1	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00

2	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Fatigue Truck Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Strength I Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	-2.114e+03	210.364e+03	0.000e+00	0.000e+00
1	1	-8.969e+03	173.687e+03	-37.485e+03	1.284e+06
1	2	-23.064e+03	138.542e+03	-120.020e+03	2.169e+06
1	3	-45.665e+03	105.157e+03	-247.605e+03	2.672e+06
1	4	-73.263e+03	74.695e+03	-420.240e+03	2.880e+06
1	5	-105.929e+03	47.938e+03	-637.926e+03	2.787e+06
1	6	-138.534e+03	23.551e+03	-900.661e+03	2.439e+06
1	7	-170.774e+03	3.730e+03	-1.208e+06	1.786e+06
1	8	-202.336e+03	-13.224e+03	-1.615e+06	932.325e+03
1	9	-232.886e+03	-28.234e+03	-2.304e+06	91.626e+03
1	10	-262.084e+03	-36.666e+03	-3.619e+06	-341.630e+03
2	0	28.045e+03	264.739e+03	-3.619e+06	-341.630e+03
2	1	19.436e+03	232.600e+03	-1.961e+06	247.420e+03
2	2	4.104e+03	194.516e+03	-1.007e+06	1.267e+06
2	3	-18.988e+03	155.895e+03	-654.460e+03	2.313e+06
2	4	-48.080e+03	117.689e+03	-386.492e+03	2.946e+06
2	5	-80.053e+03	80.795e+03	-193.874e+03	3.130e+06
2	6	-116.860e+03	48.971e+03	-230.625e+03	2.933e+06
2	7	-155.106e+03	20.472e+03	-420.957e+03	2.288e+06
2	8	-193.536e+03	-1.986e+03	-706.425e+03	1.252e+06
2	9	-231.185e+03	-12.547e+03	-1.704e+06	287.354e+03
2	10	-267.081e+03	-21.127e+03	-3.297e+06	-138.810e+03
3	0	29.622e+03	244.355e+03	-3.297e+06	-138.810e+03
3	1	23.942e+03	220.032e+03	-2.267e+06	101.552e+03
3	2	9.828e+03	191.239e+03	-1.788e+06	801.222e+03
3	3	-6.246e+03	161.617e+03	-1.403e+06	1.463e+06
3	4	-23.977e+03	131.384e+03	-1.092e+06	1.957e+06
3	5	-46.004e+03	100.825e+03	-827.426e+03	2.216e+06
3	6	-71.015e+03	71.643e+03	-595.511e+03	2.289e+06
3	7	-98.841e+03	47.678e+03	-396.810e+03	2.127e+06
3	8	-129.771e+03	26.532e+03	-231.325e+03	1.731e+06
3	9	-162.325e+03	19.450e+03	-99.055e+03	1.027e+06
3	10	-196.247e+03	13.571e+03	0.000e+00	0.000e+00

Strength I Limit State Envelopes

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	-2.114e+03	210.364e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	64.711e+03	409.911e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	50.750e+03	388.912e+03	0.000e+00	0.000e+00

4 0.000e+00 0.000e+00 -13.571e+03 196.247e+03 0.000e+00 0.000e+00

Service I Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	11.220e+03	127.519e+03	0.000e+00	0.000e+00
1	1	3.866e+03	104.539e+03	54.354e+03	778.620e+03
1	2	-7.624e+03	82.435e+03	58.652e+03	1.314e+06
1	3	-23.975e+03	61.336e+03	12.895e+03	1.617e+06
1	4	-42.639e+03	41.365e+03	-82.916e+03	1.738e+06
1	5	-63.327e+03	22.639e+03	-228.785e+03	1.672e+06
1	6	-83.980e+03	5.267e+03	-424.709e+03	1.447e+06
1	7	-104.424e+03	-9.494e+03	-670.688e+03	1.032e+06
1	8	-124.481e+03	-22.619e+03	-966.723e+03	458.195e+03
1	9	-143.960e+03	-34.633e+03	-1.430e+06	-140.931e+03
1	10	-162.666e+03	-42.888e+03	-2.266e+06	-531.547e+03
2	0	38.711e+03	164.624e+03	-2.266e+06	-531.547e+03
2	1	29.348e+03	143.644e+03	-1.208e+06	-7.703e+03
2	2	16.142e+03	119.268e+03	-577.141e+03	721.769e+03
2	3	-1.497e+03	94.584e+03	-270.573e+03	1.382e+06
2	4	-22.565e+03	70.138e+03	-52.201e+03	1.783e+06
2	5	-45.280e+03	46.442e+03	82.448e+03	1.902e+06
2	6	-69.118e+03	24.003e+03	45.365e+03	1.780e+06
2	7	-93.587e+03	3.274e+03	-120.144e+03	1.378e+06
2	8	-118.161e+03	-14.003e+03	-380.681e+03	729.514e+03
2	9	-142.289e+03	-24.482e+03	-1.041e+06	49.114e+03
2	10	-165.416e+03	-33.830e+03	-2.057e+06	-373.152e+03
3	0	36.517e+03	151.155e+03	-2.057e+06	-373.152e+03
3	1	30.321e+03	135.520e+03	-1.403e+06	-125.754e+03
3	2	19.305e+03	117.332e+03	-1.075e+06	366.180e+03
3	3	7.168e+03	98.669e+03	-812.265e+03	818.769e+03
3	4	-5.913e+03	79.657e+03	-585.510e+03	1.141e+06
3	5	-21.451e+03	60.459e+03	-395.661e+03	1.312e+06
3	6	-38.694e+03	42.048e+03	-242.718e+03	1.365e+06
3	7	-57.107e+03	26.179e+03	-126.680e+03	1.274e+06
3	8	-76.517e+03	11.145e+03	-47.547e+03	1.039e+06
3	9	-96.855e+03	4.148e+03	-5.321e+03	617.177e+03
3	10	-117.974e+03	-2.161e+03	0.000e+00	0.000e+00

Service I Limit State Envelopes

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	11.220e+03	127.519e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	81.599e+03	260.483e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	70.347e+03	246.557e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	2.161e+03	117.974e+03	0.000e+00	0.000e+00

Service II Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	6.909e+03	158.098e+03	0.000e+00	0.000e+00
1	1	-527.412e+00	130.347e+03	23.858e+03	965.404e+03
1	2	-13.342e+03	103.734e+03	-2.338e+03	1.630e+06
1	3	-32.477e+03	78.428e+03	-78.590e+03	2.007e+06
1	4	-54.617e+03	54.589e+03	-204.898e+03	2.162e+06
1	5	-79.389e+03	32.367e+03	-381.262e+03	2.090e+06
1	6	-104.116e+03	11.906e+03	-607.682e+03	1.825e+06
1	7	-128.571e+03	-5.161e+03	-884.157e+03	1.330e+06
1	8	-152.522e+03	-20.102e+03	-1.210e+06	641.707e+03
1	9	-175.722e+03	-33.597e+03	-1.740e+06	-63.826e+03
1	10	-197.917e+03	-42.205e+03	-2.738e+06	-483.278e+03
2	0	36.313e+03	199.999e+03	-2.738e+06	-483.278e+03
2	1	26.885e+03	175.471e+03	-1.479e+06	82.067e+03
2	2	12.463e+03	146.527e+03	-748.733e+03	939.849e+03
2	3	-7.723e+03	117.183e+03	-415.613e+03	1.733e+06

2	4	-32.367e+03	88.148e+03	-172.028e+03	2.213e+06
2	5	-59.151e+03	60.088e+03	-12.167e+03	2.353e+06
2	6	-87.395e+03	33.663e+03	-50.442e+03	2.205e+06
2	7	-116.460e+03	9.459e+03	-230.554e+03	1.717e+06
2	8	-145.662e+03	-10.256e+03	-509.086e+03	934.169e+03
2	9	-174.283e+03	-21.134e+03	-1.283e+06	134.932e+03
2	10	-201.602e+03	-30.540e+03	-2.493e+06	-303.613e+03
3	0	35.372e+03	184.402e+03	-2.493e+06	-303.613e+03
3	1	29.139e+03	165.899e+03	-1.711e+06	-49.966e+03
3	2	16.641e+03	144.076e+03	-1.342e+06	532.648e+03
3	3	2.687e+03	121.638e+03	-1.045e+06	1.075e+06
3	4	-12.497e+03	98.744e+03	-785.133e+03	1.460e+06
3	5	-30.874e+03	75.609e+03	-562.013e+03	1.658e+06
3	6	-51.467e+03	53.498e+03	-375.799e+03	1.715e+06
3	7	-73.581e+03	34.691e+03	-226.491e+03	1.594e+06
3	8	-96.992e+03	16.969e+03	-114.088e+03	1.298e+06
3	9	-121.609e+03	9.695e+03	-38.591e+03	770.656e+03
3	10	-147.241e+03	3.315e+03	0.000e+00	0.000e+00

Service II Limit State Envelopes

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	6.909e+03	158.098e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	78.519e+03	311.067e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	65.913e+03	294.986e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-3.315e+03	147.241e+03	0.000e+00	0.000e+00

Service III Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	14.093e+03	107.132e+03	0.000e+00	0.000e+00
1	1	6.795e+03	87.333e+03	74.684e+03	654.097e+03
1	2	-3.811e+03	68.235e+03	99.313e+03	1.104e+06
1	3	-18.307e+03	49.941e+03	73.886e+03	1.357e+06
1	4	-34.654e+03	32.550e+03	-1.595e+03	1.455e+06
1	5	-52.619e+03	16.154e+03	-127.133e+03	1.394e+06
1	6	-70.556e+03	841.625e+00	-302.727e+03	1.194e+06
1	7	-88.327e+03	-12.383e+03	-528.376e+03	834.249e+03
1	8	-105.787e+03	-24.298e+03	-804.081e+03	335.854e+03
1	9	-122.785e+03	-35.324e+03	-1.224e+06	-192.335e+03
1	10	-139.165e+03	-43.342e+03	-1.951e+06	-563.727e+03
2	0	40.310e+03	141.040e+03	-1.951e+06	-563.727e+03
2	1	30.989e+03	122.426e+03	-1.028e+06	-67.551e+03
2	2	18.595e+03	101.096e+03	-462.745e+03	576.382e+03
2	3	2.653e+03	79.519e+03	-173.880e+03	1.148e+06
2	4	-16.031e+03	58.132e+03	27.683e+03	1.495e+06
2	5	-36.032e+03	37.345e+03	145.525e+03	1.601e+06
2	6	-56.933e+03	17.564e+03	109.236e+03	1.497e+06
2	7	-78.338e+03	-849.258e+00	-46.537e+03	1.152e+06
2	8	-99.828e+03	-16.501e+03	-295.079e+03	593.077e+03
2	9	-120.960e+03	-26.714e+03	-880.976e+03	-8.098e+03
2	10	-141.291e+03	-36.022e+03	-1.766e+06	-419.511e+03
3	0	37.280e+03	128.991e+03	-1.766e+06	-419.511e+03
3	1	31.108e+03	115.268e+03	-1.198e+06	-176.279e+03
3	2	21.080e+03	99.502e+03	-898.483e+03	255.201e+03
3	3	10.156e+03	83.357e+03	-657.003e+03	647.824e+03
3	4	-1.524e+03	66.932e+03	-452.429e+03	929.248e+03
3	5	-15.169e+03	50.359e+03	-284.760e+03	1.081e+06
3	6	-30.178e+03	34.415e+03	-153.996e+03	1.132e+06
3	7	-46.124e+03	20.505e+03	-60.139e+03	1.060e+06
3	8	-62.867e+03	7.263e+03	-3.187e+03	866.151e+03
3	9	-80.352e+03	450.586e+00	16.859e+03	514.858e+03
3	10	-98.463e+03	-5.812e+03	0.000e+00	0.000e+00

Washington State Department of Transportation
 Bridge and Structures Office
 QConBridge Version 1.0

QConBridge
Run 2 Output

Dual Truck Axle Rxn = 85.662 No Impact
No Lane

Code: LRFD First Edition 1994

Span Data

Span 1 Length: 70.750 ft

Section Properties

Location	Ax	Iz	Mod. E	Unit Wgt
(ft)	(in ²)	(in ⁴)	(psi)	(pcf)
0.000	1.000e+00	999.999e-03	1.000e+03	999.997e-03

Live Load Distribution Factors

Location	Str/Serv	Limit States	Fatigue Limit	State
(ft)	gM	gV	gM	gV
0.000	1.000	1.000	1.000	1.000

Strength Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00
 Service Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Span 2 Length: 91.500 ft

Section Properties

Location	Ax	Iz	Mod. E	Unit Wgt
(ft)	(in ²)	(in ⁴)	(psi)	(pcf)
0.000	1.000e+00	999.999e-03	1.000e+03	999.997e-03

Live Load Distribution Factors

Location	Str/Serv	Limit States	Fatigue Limit	State
(ft)	gM	gV	gM	gV
0.000	1.000	1.000	1.000	1.000

Strength Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00
 Service Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Span 3 Length: 60.750 ft

Section Properties

Location	Ax	Iz	Mod. E	Unit Wgt
(ft)	(in ²)	(in ⁴)	(psi)	(pcf)
0.000	1.000e+00	999.999e-03	1.000e+03	999.997e-03

Live Load Distribution Factors

Location	Str/Serv	Limit States	Fatigue Limit	State
(ft)	gM	gV	gM	gV
0.000	1.000	1.000	1.000	1.000

Strength Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00
 Service Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Support Data

Support 1 Roller

Support 2 Pinned

Support 3 Pinned

Support 4 Roller

Loading Data

DC Loads

Self Weight Generation Disabled
Traffic Barrier Load 1.000e+03 plf

DW Loads

Utility Load Disabled
Wearing Surface Load Disabled


Live Load Data

Live Load Generation Parameters

Design Tandem : Enabled
Design Truck : 17 rear axle spacing increments
Dual Truck Train : Headway Spacing varies from 50.000 ft to 223.000 ft using 173 increments
Dual Tandem Train: Disabled
Fatigue Truck : Disabled

Live Load Impact

Truck Loads 0.000%
Lane Loads -100.000%
Fatigue Truck 15.000%



Pedestrian Live Load 0.000e+00 plf

Load Factors

Strength I	DC min	0.900	DC max	1.250	DW min	0.650	DW max	1.500	LL	1.750
Service I	DC	1.000	DW	1.000	LL	1.000				
Service II	DC	1.000	DW	1.000	LL	1.300				
Service III	DC	1.000	DW	1.000	LL	0.800				
Fatigue	DC	0.000	DW	0.000	LL	0.750				

Analysis Results

DC Dead Load

Span	Point	Shear (lbs)	Moment (ft-lbs)
1	0	25.587e+03	0.000e+00
1	1	18.512e+03	156.005e+03
1	2	11.437e+03	261.956e+03
1	3	4.362e+03	317.850e+03
1	4	-2.712e+03	323.689e+03
1	5	-9.787e+03	279.473e+03
1	6	-16.862e+03	185.200e+03
1	7	-23.937e+03	40.872e+03
1	8	-31.012e+03	-153.510e+03
1	9	-38.087e+03	-397.949e+03
1	10	-45.162e+03	-692.444e+03
2	0	46.706e+03	-692.444e+03
2	1	37.556e+03	-306.943e+03
2	2	28.406e+03	-5.165e+03

2	3	19.256e+03	212.890e+03
2	4	10.106e+03	347.223e+03
2	5	956.236e+00	397.834e+03
2	6	-8.193e+03	364.722e+03
2	7	-17.343e+03	247.888e+03
2	8	-26.493e+03	47.331e+03
2	9	-35.643e+03	-236.947e+03
2	10	-44.793e+03	-604.948e+03
3	0	40.333e+03	-604.948e+03
3	1	34.258e+03	-378.378e+03
3	2	28.183e+03	-188.714e+03
3	3	22.108e+03	-35.955e+03
3	4	16.033e+03	79.898e+03
3	5	9.958e+03	158.845e+03
3	6	3.883e+03	200.887e+03
3	7	-2.191e+03	206.024e+03
3	8	-8.266e+03	174.255e+03
3	9	-14.341e+03	105.580e+03
3	10	-20.416e+03	0.000e+00

DC Dead Load

Pier	Fx (lbs)	Fy (lbs)	Mz (ft-lbs)
1	0.000e+00	25.587e+03	0.000e+00
2	0.000e+00	91.868e+03	0.000e+00
3	0.000e+00	85.126e+03	0.000e+00
4	0.000e+00	20.416e+03	0.000e+00

DW Dead Load

Span	Point	Shear (lbs)	Moment (ft-lbs)
1	0	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00
1	2	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00
1	9	0.000e+00	0.000e+00
1	10	0.000e+00	0.000e+00
2	0	0.000e+00	0.000e+00
2	1	0.000e+00	0.000e+00
2	2	0.000e+00	0.000e+00
2	3	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00
2	10	0.000e+00	0.000e+00
3	0	0.000e+00	0.000e+00
3	1	0.000e+00	0.000e+00
3	2	0.000e+00	0.000e+00
3	3	0.000e+00	0.000e+00
3	4	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00

DW Dead Load

Pier	Fx (lbs)	Fy (lbs)	Mz (ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00

Live Load Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	-7.778e+03	61.310e+03	0.000e+00	0.000e+00
1	1	-7.778e+03	52.531e+03	-55.033e+03	371.663e+03
1	2	-10.472e+03	43.995e+03	-110.066e+03	622.542e+03
1	3	-16.412e+03	35.806e+03	-165.100e+03	759.993e+03
1	4	-23.693e+03	28.068e+03	-220.133e+03	821.639e+03
1	5	-32.115e+03	20.885e+03	-275.167e+03	805.080e+03
1	6	-40.154e+03	14.361e+03	-330.200e+03	729.700e+03
1	7	-47.703e+03	9.469e+03	-385.234e+03	574.036e+03
1	8	-54.660e+03	5.505e+03	-440.267e+03	359.727e+03
1	9	-60.919e+03	2.115e+03	-570.770e+03	152.485e+03
1	10	-66.375e+03	1.329e+03	-863.315e+03	94.052e+03
2	0	-4.673e+03	64.950e+03	-863.315e+03	94.052e+03
2	1	-4.673e+03	60.279e+03	-514.137e+03	186.812e+03
2	2	-7.199e+03	52.692e+03	-324.435e+03	440.312e+03
2	3	-12.624e+03	44.438e+03	-267.411e+03	678.592e+03
2	4	-20.140e+03	35.876e+03	-210.386e+03	820.243e+03
2	5	-28.377e+03	27.361e+03	-153.361e+03	853.929e+03
2	6	-36.933e+03	19.267e+03	-162.510e+03	809.383e+03
2	7	-45.453e+03	11.946e+03	-205.271e+03	656.943e+03
2	8	-53.575e+03	6.744e+03	-248.031e+03	413.707e+03
2	9	-60.940e+03	6.232e+03	-465.507e+03	170.608e+03
2	10	-67.213e+03	6.232e+03	-795.284e+03	131.761e+03
3	0	-2.168e+03	63.343e+03	-795.284e+03	131.761e+03
3	1	-2.168e+03	58.975e+03	-562.807e+03	137.535e+03
3	2	-5.592e+03	52.486e+03	-479.664e+03	318.116e+03
3	3	-9.627e+03	45.410e+03	-419.706e+03	494.050e+03
3	4	-14.113e+03	37.811e+03	-359.748e+03	617.842e+03
3	5	-20.159e+03	29.786e+03	-299.790e+03	672.543e+03
3	6	-27.180e+03	22.046e+03	-239.832e+03	684.799e+03
3	7	-34.758e+03	15.894e+03	-179.874e+03	633.478e+03
3	8	-42.749e+03	10.034e+03	-119.916e+03	519.406e+03
3	9	-51.091e+03	9.869e+03	-59.958e+03	310.382e+03
3	10	-59.669e+03	9.869e+03	0.000e+00	0.000e+00

Not interested in the overall envelope.

Live Load Envelopes (Per Lane)

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	-7.778e+03	61.310e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-6.002e+03	85.662e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-8.401e+03	82.260e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-9.869e+03	59.669e+03	0.000e+00	0.000e+00

Design Tandem + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	-5.543e+03	47.757e+03	0.000e+00	0.000e+00
1	1	-5.543e+03	41.664e+03	-39.217e+03	294.778e+03
1	2	-10.472e+03	35.662e+03	-78.435e+03	504.627e+03
1	3	-16.412e+03	29.821e+03	-117.653e+03	632.964e+03
1	4	-22.159e+03	24.212e+03	-156.870e+03	685.207e+03
1	5	-27.643e+03	18.905e+03	-196.088e+03	674.342e+03
1	6	-32.793e+03	13.971e+03	-235.306e+03	610.058e+03
1	7	-37.538e+03	9.469e+03	-274.524e+03	492.929e+03

1	8	-41.824e+03	5.505e+03	-313.741e+03	334.677e+03
1	9	-45.534e+03	2.115e+03	-352.959e+03	152.485e+03
1	10	-48.642e+03	994.701e+00	-392.177e+03	70.375e+03
2	0	-3.496e+03	46.618e+03	-392.177e+03	70.375e+03
2	1	-3.496e+03	44.858e+03	-276.636e+03	186.812e+03
2	2	-7.199e+03	40.145e+03	-235.282e+03	399.995e+03
2	3	-12.311e+03	34.780e+03	-193.927e+03	568.964e+03
2	4	-17.937e+03	29.012e+03	-152.573e+03	673.478e+03
2	5	-23.827e+03	23.083e+03	-111.218e+03	703.322e+03
2	6	-29.739e+03	17.236e+03	-121.599e+03	665.101e+03
2	7	-35.430e+03	11.715e+03	-153.594e+03	553.581e+03
2	8	-40.656e+03	6.744e+03	-185.590e+03	381.803e+03
2	9	-45.188e+03	4.519e+03	-217.586e+03	170.608e+03
2	10	-48.737e+03	4.519e+03	-426.808e+03	95.554e+03
3	0	-1.572e+03	47.360e+03	-426.808e+03	95.554e+03
3	1	-2.097e+03	45.161e+03	-384.127e+03	137.535e+03
3	2	-5.592e+03	41.309e+03	-341.446e+03	298.650e+03
3	3	-9.627e+03	36.972e+03	-298.765e+03	433.582e+03
3	4	-14.113e+03	32.180e+03	-256.085e+03	532.404e+03
3	5	-19.052e+03	27.032e+03	-213.404e+03	583.803e+03
3	6	-24.313e+03	21.582e+03	-170.723e+03	590.821e+03
3	7	-29.854e+03	15.894e+03	-128.042e+03	544.103e+03
3	8	-35.610e+03	10.034e+03	-85.361e+03	432.672e+03
3	9	-41.517e+03	7.025e+03	-42.680e+03	252.218e+03
3	10	-47.509e+03	7.025e+03	0.000e+00	0.000e+00

Design Tandem + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	-5.543e+03	47.757e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-4.491e+03	49.278e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-6.092e+03	49.576e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-7.025e+03	47.509e+03	0.000e+00	0.000e+00

Design Truck + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	-7.778e+03	61.310e+03	0.000e+00	0.000e+00
1	1	-7.778e+03	52.531e+03	-55.033e+03	371.663e+03
1	2	-8.034e+03	43.995e+03	-110.066e+03	622.542e+03
1	3	-15.951e+03	35.806e+03	-165.100e+03	759.993e+03
1	4	-23.693e+03	28.068e+03	-220.133e+03	821.639e+03
1	5	-32.115e+03	20.885e+03	-275.167e+03	805.080e+03
1	6	-40.154e+03	14.361e+03	-330.200e+03	729.700e+03
1	7	-47.703e+03	8.953e+03	-385.234e+03	574.036e+03
1	8	-54.660e+03	4.294e+03	-440.267e+03	359.727e+03
1	9	-60.919e+03	1.931e+03	-495.301e+03	123.014e+03
1	10	-66.375e+03	1.329e+03	-550.334e+03	94.052e+03
2	0	-4.673e+03	64.950e+03	-550.334e+03	94.052e+03
2	1	-4.673e+03	60.279e+03	-381.460e+03	146.651e+03
2	2	-6.484e+03	52.692e+03	-324.435e+03	440.312e+03
2	3	-12.624e+03	44.438e+03	-267.411e+03	678.592e+03
2	4	-20.140e+03	35.876e+03	-210.386e+03	820.243e+03
2	5	-28.377e+03	27.361e+03	-153.361e+03	853.929e+03
2	6	-36.933e+03	19.267e+03	-162.510e+03	809.383e+03
2	7	-45.453e+03	11.946e+03	-205.271e+03	656.943e+03
2	8	-53.575e+03	6.232e+03	-248.031e+03	413.707e+03
2	9	-60.940e+03	6.232e+03	-290.792e+03	137.961e+03
2	10	-67.213e+03	6.232e+03	-599.580e+03	131.761e+03
3	0	-2.168e+03	63.343e+03	-599.580e+03	131.761e+03
3	1	-2.168e+03	58.975e+03	-539.622e+03	118.585e+03
3	2	-4.473e+03	52.486e+03	-479.664e+03	318.116e+03
3	3	-8.628e+03	45.410e+03	-419.706e+03	494.050e+03
3	4	-14.000e+03	37.811e+03	-359.748e+03	617.842e+03

3	5	-20.159e+03	29.786e+03	-299.790e+03	672.543e+03
3	6	-27.180e+03	22.046e+03	-239.832e+03	684.799e+03
3	7	-34.758e+03	14.405e+03	-179.874e+03	633.478e+03
3	8	-42.749e+03	9.869e+03	-119.916e+03	519.406e+03
3	9	-51.091e+03	9.869e+03	-59.958e+03	310.382e+03
3	10	-59.669e+03	9.869e+03	0.000e+00	0.000e+00

Design Truck + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	-7.778e+03	61.310e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-6.002e+03	71.249e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-8.401e+03	71.679e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-9.869e+03	59.669e+03	0.000e+00	0.000e+00

Dual Truck Train + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00	-396.240e+03	0.000e+00
1	9	0.000e+00	0.000e+00	-570.770e+03	0.000e+00
1	10	0.000e+00	0.000e+00	-863.315e+03	0.000e+00
2	0	0.000e+00	0.000e+00	-863.315e+03	0.000e+00
2	1	0.000e+00	0.000e+00	-514.137e+03	0.000e+00
2	2	0.000e+00	0.000e+00	-296.951e+03	0.000e+00
2	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00	-465.507e+03	0.000e+00
2	10	0.000e+00	0.000e+00	-795.284e+03	0.000e+00
3	0	0.000e+00	0.000e+00	-795.284e+03	0.000e+00
3	1	0.000e+00	0.000e+00	-562.807e+03	0.000e+00
3	2	0.000e+00	0.000e+00	-431.697e+03	0.000e+00
3	3	0.000e+00	0.000e+00	-377.735e+03	0.000e+00
3	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Dual Truck Axle
Rxn – No Impact
and No Lane

Dual Truck Train + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-5.402e+03	85.662e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-7.561e+03	82.260e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Dual Tandem Train + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00

1	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Dual Tandem Train + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Fatigue Truck Envelopes (Per Lane)

Span	Point	Min Shear(lbs)	Max Shear(lbs)	Min Moment(ft-lbs)	Max Moment(ft-lbs)
1	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00

2	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Fatigue Truck Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Strength I Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	9.416e+03	139.277e+03	0.000e+00	0.000e+00
1	1	3.049e+03	115.071e+03	44.096e+03	845.418e+03
1	2	-8.033e+03	91.290e+03	43.143e+03	1.416e+06
1	3	-24.794e+03	68.114e+03	-2.859e+03	1.727e+06
1	4	-44.853e+03	46.678e+03	-93.913e+03	1.842e+06
1	5	-68.436e+03	27.740e+03	-230.016e+03	1.758e+06
1	6	-91.347e+03	9.957e+03	-411.170e+03	1.508e+06
1	7	-113.403e+03	-4.972e+03	-637.374e+03	1.055e+06
1	8	-134.420e+03	-18.275e+03	-962.356e+03	491.364e+03
1	9	-154.218e+03	-30.576e+03	-1.496e+06	-91.305e+03
1	10	-172.609e+03	-38.319e+03	-2.376e+06	-458.608e+03
2	0	33.857e+03	172.045e+03	-2.376e+06	-458.608e+03
2	1	25.622e+03	152.434e+03	-1.283e+06	50.673e+03
2	2	12.966e+03	127.719e+03	-574.219e+03	765.897e+03
2	3	-4.763e+03	101.838e+03	-276.368e+03	1.453e+06
2	4	-26.150e+03	75.417e+03	-55.675e+03	1.869e+06
2	5	-48.799e+03	49.077e+03	89.667e+03	1.991e+06
2	6	-74.876e+03	26.342e+03	43.856e+03	1.872e+06
2	7	-101.223e+03	5.296e+03	-136.125e+03	1.459e+06
2	8	-126.874e+03	-12.041e+03	-391.457e+03	783.152e+03
2	9	-151.200e+03	-21.173e+03	-1.110e+06	85.313e+03
2	10	-173.615e+03	-29.408e+03	-2.147e+06	-313.871e+03
3	0	32.504e+03	161.267e+03	-2.147e+06	-313.871e+03
3	1	27.036e+03	146.029e+03	-1.457e+06	-99.853e+03
3	2	15.577e+03	127.080e+03	-1.075e+06	386.861e+03
3	3	3.049e+03	107.103e+03	-779.429e+03	832.228e+03
3	4	-10.269e+03	86.211e+03	-557.650e+03	1.181e+06
3	5	-26.317e+03	64.573e+03	-381.671e+03	1.375e+06
3	6	-44.071e+03	43.435e+03	-238.907e+03	1.449e+06
3	7	-63.567e+03	25.843e+03	-129.357e+03	1.366e+06
3	8	-85.145e+03	10.119e+03	-53.023e+03	1.126e+06
3	9	-107.338e+03	4.364e+03	-9.904e+03	675.144e+03
3	10	-129.942e+03	-1.103e+03	0.000e+00	0.000e+00

Strength I Limit State Envelopes

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	9.416e+03	139.277e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	72.176e+03	264.745e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	61.912e+03	250.364e+03	0.000e+00	0.000e+00

4 0.000e+00 0.000e+00 1.103e+03 129.942e+03 0.000e+00 0.000e+00

Service I Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	17.809e+03	86.897e+03	0.000e+00	0.000e+00
1	1	10.734e+03	71.044e+03	100.972e+03	527.669e+03
1	2	965.105e+00	55.433e+03	151.889e+03	884.498e+03
1	3	-12.049e+03	40.169e+03	152.750e+03	1.077e+06
1	4	-26.405e+03	25.355e+03	103.555e+03	1.145e+06
1	5	-41.903e+03	11.098e+03	4.305e+03	1.084e+06
1	6	-57.016e+03	-2.500e+03	-144.999e+03	914.901e+03
1	7	-71.640e+03	-14.467e+03	-344.361e+03	614.908e+03
1	8	-85.672e+03	-25.506e+03	-593.778e+03	206.217e+03
1	9	-99.006e+03	-35.971e+03	-968.720e+03	-245.464e+03
1	10	-111.537e+03	-43.832e+03	-1.555e+06	-598.391e+03
2	0	42.032e+03	111.656e+03	-1.555e+06	-598.391e+03
2	1	32.882e+03	97.835e+03	-821.080e+03	-120.131e+03
2	2	21.206e+03	81.098e+03	-329.601e+03	435.146e+03
2	3	6.631e+03	63.695e+03	-54.520e+03	891.482e+03
2	4	-10.034e+03	45.982e+03	136.837e+03	1.167e+06
2	5	-27.420e+03	28.317e+03	244.472e+03	1.251e+06
2	6	-45.127e+03	11.073e+03	202.212e+03	1.174e+06
2	7	-62.797e+03	-5.397e+03	42.617e+03	904.832e+03
2	8	-80.069e+03	-19.749e+03	-200.699e+03	461.039e+03
2	9	-96.584e+03	-29.411e+03	-702.455e+03	-66.338e+03
2	10	-112.007e+03	-38.561e+03	-1.400e+06	-473.187e+03
3	0	38.164e+03	103.676e+03	-1.400e+06	-473.187e+03
3	1	32.089e+03	93.233e+03	-941.186e+03	-240.842e+03
3	2	22.590e+03	80.669e+03	-668.378e+03	129.402e+03
3	3	12.480e+03	67.518e+03	-455.661e+03	458.094e+03
3	4	1.919e+03	53.844e+03	-279.850e+03	697.740e+03
3	5	-10.201e+03	39.744e+03	-140.944e+03	831.388e+03
3	6	-23.297e+03	25.929e+03	-38.944e+03	885.687e+03
3	7	-36.950e+03	13.702e+03	26.150e+03	839.503e+03
3	8	-51.016e+03	1.767e+03	54.339e+03	693.662e+03
3	9	-65.433e+03	-4.472e+03	45.622e+03	415.962e+03
3	10	-80.086e+03	-10.547e+03	0.000e+00	0.000e+00

Service I Limit State Envelopes

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	17.809e+03	86.897e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	85.865e+03	177.531e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	76.725e+03	167.387e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	10.547e+03	80.086e+03	0.000e+00	0.000e+00

Service II Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	15.475e+03	105.291e+03	0.000e+00	0.000e+00
1	1	8.400e+03	86.804e+03	84.462e+03	639.168e+03
1	2	-2.176e+03	68.632e+03	118.869e+03	1.071e+06
1	3	-16.972e+03	50.911e+03	103.220e+03	1.305e+06
1	4	-33.513e+03	33.776e+03	37.515e+03	1.391e+06
1	5	-51.537e+03	17.363e+03	-78.244e+03	1.326e+06
1	6	-69.062e+03	1.808e+03	-244.060e+03	1.133e+06
1	7	-85.952e+03	-11.627e+03	-459.931e+03	787.119e+03
1	8	-102.070e+03	-23.854e+03	-725.858e+03	314.135e+03
1	9	-117.282e+03	-35.336e+03	-1.139e+06	-199.719e+03
1	10	-131.449e+03	-43.434e+03	-1.814e+06	-570.176e+03
2	0	40.630e+03	131.141e+03	-1.814e+06	-570.176e+03
2	1	31.480e+03	115.919e+03	-975.322e+03	-64.087e+03
2	2	19.046e+03	96.906e+03	-426.932e+03	567.240e+03
2	3	2.843e+03	77.026e+03	-134.744e+03	1.095e+06

2	4	-16.076e+03	56.745e+03	73.721e+03	1.413e+06
2	5	-35.934e+03	36.525e+03	198.464e+03	1.507e+06
2	6	-56.207e+03	16.853e+03	153.458e+03	1.416e+06
2	7	-76.433e+03	-1.813e+03	-18.964e+03	1.101e+06
2	8	-96.142e+03	-17.726e+03	-275.109e+03	585.151e+03
2	9	-114.866e+03	-27.541e+03	-842.107e+03	-15.155e+03
2	10	-132.171e+03	-36.691e+03	-1.638e+06	-433.658e+03
3	0	37.513e+03	122.679e+03	-1.638e+06	-433.658e+03
3	1	31.438e+03	110.925e+03	-1.110e+06	-199.582e+03
3	2	20.912e+03	96.416e+03	-812.277e+03	224.837e+03
3	3	9.592e+03	81.141e+03	-581.573e+03	606.309e+03
3	4	-2.314e+03	65.188e+03	-387.774e+03	883.093e+03
3	5	-16.249e+03	48.680e+03	-230.881e+03	1.033e+06
3	6	-31.451e+03	32.543e+03	-110.893e+03	1.091e+06
3	7	-47.378e+03	18.471e+03	-27.811e+03	1.029e+06
3	8	-63.841e+03	4.777e+03	18.364e+03	849.484e+03
3	9	-80.761e+03	-1.511e+03	27.634e+03	509.077e+03
3	10	-97.987e+03	-7.586e+03	0.000e+00	0.000e+00

Service II Limit State Envelopes

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	15.475e+03	105.291e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	84.064e+03	203.230e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	74.205e+03	192.065e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	7.586e+03	97.987e+03	0.000e+00	0.000e+00

Service III Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	19.364e+03	74.635e+03	0.000e+00	0.000e+00
1	1	12.289e+03	60.538e+03	111.979e+03	453.336e+03
1	2	3.059e+03	46.634e+03	173.902e+03	759.990e+03
1	3	-8.766e+03	33.008e+03	185.770e+03	925.845e+03
1	4	-21.666e+03	19.742e+03	147.582e+03	981.001e+03
1	5	-35.479e+03	6.920e+03	59.339e+03	923.537e+03
1	6	-48.985e+03	-5.372e+03	-78.959e+03	768.961e+03
1	7	-62.100e+03	-16.361e+03	-267.314e+03	500.101e+03
1	8	-74.740e+03	-26.607e+03	-505.724e+03	134.271e+03
1	9	-86.822e+03	-36.394e+03	-854.566e+03	-275.961e+03
1	10	-98.262e+03	-44.098e+03	-1.383e+06	-617.202e+03
2	0	42.967e+03	98.666e+03	-1.383e+06	-617.202e+03
2	1	33.817e+03	85.779e+03	-718.253e+03	-157.493e+03
2	2	22.646e+03	70.560e+03	-264.714e+03	347.084e+03
2	3	9.156e+03	54.807e+03	-1.038e+03	755.764e+03
2	4	-6.006e+03	38.807e+03	178.914e+03	1.003e+06
2	5	-21.745e+03	22.845e+03	275.145e+03	1.080e+06
2	6	-37.740e+03	7.219e+03	234.714e+03	1.012e+06
2	7	-53.706e+03	-7.786e+03	83.671e+03	773.443e+03
2	8	-69.354e+03	-21.098e+03	-151.093e+03	378.297e+03
2	9	-84.396e+03	-30.658e+03	-609.353e+03	-100.460e+03
2	10	-98.564e+03	-39.808e+03	-1.241e+06	-499.539e+03
3	0	38.597e+03	91.007e+03	-1.241e+06	-499.539e+03
3	1	32.522e+03	81.438e+03	-828.624e+03	-268.350e+03
3	2	23.708e+03	70.172e+03	-572.445e+03	65.779e+03
3	3	14.406e+03	58.436e+03	-371.720e+03	359.284e+03
3	4	4.741e+03	46.282e+03	-207.900e+03	574.171e+03
3	5	-6.169e+03	33.787e+03	-80.986e+03	696.880e+03
3	6	-17.861e+03	21.520e+03	9.022e+03	748.727e+03
3	7	-29.999e+03	10.523e+03	62.125e+03	712.807e+03
3	8	-42.466e+03	-239.789e+00	78.322e+03	589.780e+03
3	9	-55.215e+03	-6.446e+03	57.614e+03	353.886e+03
3	10	-68.152e+03	-12.521e+03	0.000e+00	0.000e+00

Washington State Department of Transportation
Bridge and Structures Office
QConBridge Version 1.0

QConBridge
Run 3 Output

Dual Lane Axle Rxn = 54.683 k No Impact
No Truck

Code: LRFD First Edition 1994

Span Data

Span 1 Length: 70.750 ft

Section Properties

Location (ft)	Ax (in ²)	Iz (in ⁴)	Mod. E (psi)	Unit Wgt (pcf)
0.000	1.000e+00	999.999e-03	1.000e+03	999.997e-03

Live Load Distribution Factors

Location (ft)	Str/Serv gM	Limit States gV	Fatigue Limit gM	State gV
0.000	1.000	1.000	1.000	1.000

Strength Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00
Service Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Span 2 Length: 91.500 ft

Section Properties

Location (ft)	Ax (in ²)	Iz (in ⁴)	Mod. E (psi)	Unit Wgt (pcf)
0.000	1.000e+00	999.999e-03	1.000e+03	999.997e-03

Live Load Distribution Factors

Location (ft)	Str/Serv gM	Limit States gV	Fatigue Limit gM	State gV
0.000	1.000	1.000	1.000	1.000

Strength Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00
Service Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Span 3 Length: 60.750 ft

Section Properties

Location (ft)	Ax (in ²)	Iz (in ⁴)	Mod. E (psi)	Unit Wgt (pcf)
0.000	1.000e+00	999.999e-03	1.000e+03	999.997e-03

Live Load Distribution Factors

Location (ft)	Str/Serv gM	Limit States gV	Fatigue Limit gM	State gV
0.000	1.000	1.000	1.000	1.000

Strength Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00
Service Limit State Factors: Ductility 1.00 Redundancy 1.00 Importance 1.00

Support Data

Support 1 Roller

Support 2 Pinned

Support 3 Pinned

Support 4 Roller

Loading Data

DC Loads

Self Weight Generation Disabled
Traffic Barrier Load 1.000e+03 plf

DW Loads

Utility Load Disabled
Wearing Surface Load Disabled


Live Load Data

Live Load Generation Parameters

Design Tandem : Enabled
Design Truck : 17 rear axle spacing increments
Dual Truck Train : Headway Spacing varies from 50.000 ft to 223.000 ft using 173 increments
Dual Tandem Train: Disabled
Fatigue Truck : Disabled

Live Load Impact

Truck Loads -100.000%
Lane Loads 0.000%
Fatigue Truck 15.000%



Pedestrian Live Load 0.000e+00 plf

Load Factors

Strength I	DC min	0.900	DC max	1.250	DW min	0.650	DW max	1.500	LL	1.750
Service I	DC	1.000	DW	1.000	LL	1.000				
Service II	DC	1.000	DW	1.000	LL	1.300				
Service III	DC	1.000	DW	1.000	LL	0.800				
Fatigue	DC	0.000	DW	0.000	LL	0.750				

Analysis Results

DC Dead Load

Span	Point	Shear (lbs)	Moment (ft-lbs)
1	0	25.587e+03	0.000e+00
1	1	18.512e+03	156.005e+03
1	2	11.437e+03	261.956e+03
1	3	4.362e+03	317.850e+03
1	4	-2.712e+03	323.689e+03
1	5	-9.787e+03	279.473e+03
1	6	-16.862e+03	185.200e+03
1	7	-23.937e+03	40.872e+03
1	8	-31.012e+03	-153.510e+03
1	9	-38.087e+03	-397.949e+03
1	10	-45.162e+03	-692.444e+03
2	0	46.706e+03	-692.444e+03
2	1	37.556e+03	-306.943e+03
2	2	28.406e+03	-5.165e+03

2	3	19.256e+03	212.890e+03
2	4	10.106e+03	347.223e+03
2	5	956.236e+00	397.834e+03
2	6	-8.193e+03	364.722e+03
2	7	-17.343e+03	247.888e+03
2	8	-26.493e+03	47.331e+03
2	9	-35.643e+03	-236.947e+03
2	10	-44.793e+03	-604.948e+03
3	0	40.333e+03	-604.948e+03
3	1	34.258e+03	-378.378e+03
3	2	28.183e+03	-188.714e+03
3	3	22.108e+03	-35.955e+03
3	4	16.033e+03	79.898e+03
3	5	9.958e+03	158.845e+03
3	6	3.883e+03	200.887e+03
3	7	-2.191e+03	206.024e+03
3	8	-8.266e+03	174.255e+03
3	9	-14.341e+03	105.580e+03
3	10	-20.416e+03	0.000e+00

DC Dead Load

Pier	Fx (lbs)	Fy (lbs)	Mz (ft-lbs)
1	0.000e+00	25.587e+03	0.000e+00
2	0.000e+00	91.868e+03	0.000e+00
3	0.000e+00	85.126e+03	0.000e+00
4	0.000e+00	20.416e+03	0.000e+00

DW Dead Load

Span	Point	Shear (lbs)	Moment (ft-lbs)
1	0	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00
1	2	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00
1	9	0.000e+00	0.000e+00
1	10	0.000e+00	0.000e+00
2	0	0.000e+00	0.000e+00
2	1	0.000e+00	0.000e+00
2	2	0.000e+00	0.000e+00
2	3	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00
2	10	0.000e+00	0.000e+00
3	0	0.000e+00	0.000e+00
3	1	0.000e+00	0.000e+00
3	2	0.000e+00	0.000e+00
3	3	0.000e+00	0.000e+00
3	4	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00

DW Dead Load

Pier	Fx (lbs)	Fy (lbs)	Mz (ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00

Live Load Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	-4.022e+03	20.388e+03	0.000e+00	0.000e+00
1	1	-4.300e+03	16.158e+03	-28.457e+03	128.301e+03
1	2	-5.133e+03	12.482e+03	-56.914e+03	224.705e+03
1	3	-6.510e+03	9.351e+03	-85.371e+03	289.210e+03
1	4	-8.415e+03	6.747e+03	-113.828e+03	321.818e+03
1	5	-10.825e+03	4.649e+03	-142.285e+03	322.527e+03
1	6	-13.713e+03	3.028e+03	-170.743e+03	291.339e+03
1	7	-17.041e+03	1.848e+03	-199.200e+03	228.252e+03
1	8	-20.771e+03	1.069e+03	-227.657e+03	133.267e+03
1	9	-24.850e+03	639.704e+00	-303.942e+03	54.212e+03
1	10	-29.225e+03	506.102e+00	-472.774e+03	35.806e+03
2	0	-1.779e+03	31.534e+03	-472.774e+03	35.806e+03
2	1	-1.992e+03	25.916e+03	-242.164e+03	50.778e+03
2	2	-2.688e+03	20.781e+03	-140.475e+03	141.319e+03
2	3	-3.962e+03	16.224e+03	-127.807e+03	267.527e+03
2	4	-5.885e+03	12.316e+03	-119.610e+03	344.856e+03
2	5	-8.494e+03	9.095e+03	-111.414e+03	368.832e+03
2	6	-11.802e+03	6.572e+03	-103.218e+03	339.455e+03
2	7	-15.790e+03	4.729e+03	-95.022e+03	256.727e+03
2	8	-20.412e+03	3.520e+03	-98.131e+03	131.951e+03
2	9	-25.595e+03	2.872e+03	-206.568e+03	59.151e+03
2	10	-31.228e+03	2.674e+03	-438.560e+03	56.553e+03
3	0	-930.922e+00	26.575e+03	-438.560e+03	56.553e+03
3	1	-1.052e+03	22.825e+03	-307.670e+03	69.701e+03
3	2	-1.439e+03	19.341e+03	-249.258e+03	131.798e+03
3	3	-2.135e+03	16.165e+03	-218.101e+03	197.637e+03
3	4	-3.175e+03	13.335e+03	-186.943e+03	239.958e+03
3	5	-4.597e+03	10.885e+03	-155.786e+03	258.760e+03
3	6	-6.426e+03	8.843e+03	-124.629e+03	254.045e+03
3	7	-8.686e+03	7.231e+03	-93.471e+03	225.811e+03
3	8	-11.393e+03	6.067e+03	-62.314e+03	174.058e+03
3	9	-14.561e+03	5.364e+03	-31.157e+03	98.788e+03
3	10	-18.197e+03	5.128e+03	0.000e+00	0.000e+00

Not interested in the overall envelope.

Live Load Envelopes (Per Lane)

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	-4.022e+03	20.388e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-2.285e+03	60.759e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-3.605e+03	57.804e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-5.128e+03	18.197e+03	0.000e+00	0.000e+00

Design Tandem + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	-4.022e+03	20.388e+03	0.000e+00	0.000e+00
1	1	-4.300e+03	16.158e+03	-28.457e+03	128.301e+03
1	2	-5.133e+03	12.482e+03	-56.914e+03	224.705e+03
1	3	-6.510e+03	9.351e+03	-85.371e+03	289.210e+03
1	4	-8.415e+03	6.747e+03	-113.828e+03	321.818e+03
1	5	-10.825e+03	4.649e+03	-142.285e+03	322.527e+03
1	6	-13.713e+03	3.028e+03	-170.743e+03	291.339e+03
1	7	-17.041e+03	1.848e+03	-199.200e+03	228.252e+03

1	8	-20.771e+03	1.069e+03	-227.657e+03	133.267e+03
1	9	-24.850e+03	639.704e+00	-303.942e+03	54.212e+03
1	10	-29.225e+03	506.102e+00	-472.774e+03	35.806e+03
2	0	-1.779e+03	31.534e+03	-472.774e+03	35.806e+03
2	1	-1.992e+03	25.916e+03	-242.164e+03	50.778e+03
2	2	-2.688e+03	20.781e+03	-140.475e+03	141.319e+03
2	3	-3.962e+03	16.224e+03	-127.807e+03	267.527e+03
2	4	-5.885e+03	12.316e+03	-119.610e+03	344.856e+03
2	5	-8.494e+03	9.095e+03	-111.414e+03	368.832e+03
2	6	-11.802e+03	6.572e+03	-103.218e+03	339.455e+03
2	7	-15.790e+03	4.729e+03	-95.022e+03	256.727e+03
2	8	-20.412e+03	3.520e+03	-98.131e+03	131.951e+03
2	9	-25.595e+03	2.872e+03	-206.568e+03	59.151e+03
2	10	-31.228e+03	2.674e+03	-438.560e+03	56.553e+03
3	0	-930.922e+00	26.575e+03	-438.560e+03	56.553e+03
3	1	-1.052e+03	22.825e+03	-307.670e+03	69.701e+03
3	2	-1.439e+03	19.341e+03	-249.258e+03	131.798e+03
3	3	-2.135e+03	16.165e+03	-218.101e+03	197.637e+03
3	4	-3.175e+03	13.335e+03	-186.943e+03	239.958e+03
3	5	-4.597e+03	10.885e+03	-155.786e+03	258.760e+03
3	6	-6.426e+03	8.843e+03	-124.629e+03	254.045e+03
3	7	-8.686e+03	7.231e+03	-93.471e+03	225.811e+03
3	8	-11.393e+03	6.067e+03	-62.314e+03	174.058e+03
3	9	-14.561e+03	5.364e+03	-31.157e+03	98.788e+03
3	10	-18.197e+03	5.128e+03	0.000e+00	0.000e+00

Design Tandem + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	-4.022e+03	20.388e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-2.285e+03	60.759e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-3.605e+03	57.804e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-5.128e+03	18.197e+03	0.000e+00	0.000e+00

Design Truck + Lane Envelopes (Per Lane)

Span	Point	Min Shear(lbs)	Max Shear(lbs)	Min Moment(ft-lbs)	Max Moment(ft-lbs)
1	0	-4.022e+03	20.388e+03	0.000e+00	0.000e+00
1	1	-4.300e+03	16.158e+03	-28.457e+03	128.301e+03
1	2	-5.133e+03	12.482e+03	-56.914e+03	224.705e+03
1	3	-6.510e+03	9.351e+03	-85.371e+03	289.210e+03
1	4	-8.415e+03	6.747e+03	-113.828e+03	321.818e+03
1	5	-10.825e+03	4.649e+03	-142.285e+03	322.527e+03
1	6	-13.713e+03	3.028e+03	-170.743e+03	291.339e+03
1	7	-17.041e+03	1.848e+03	-199.200e+03	228.252e+03
1	8	-20.771e+03	1.069e+03	-227.657e+03	133.267e+03
1	9	-24.850e+03	639.704e+00	-303.942e+03	54.212e+03
1	10	-29.225e+03	506.102e+00	-472.774e+03	35.806e+03
2	0	-1.779e+03	31.534e+03	-472.774e+03	35.806e+03
2	1	-1.992e+03	25.916e+03	-242.164e+03	50.778e+03
2	2	-2.688e+03	20.781e+03	-140.475e+03	141.319e+03
2	3	-3.962e+03	16.224e+03	-127.807e+03	267.527e+03
2	4	-5.885e+03	12.316e+03	-119.610e+03	344.856e+03
2	5	-8.494e+03	9.095e+03	-111.414e+03	368.832e+03
2	6	-11.802e+03	6.572e+03	-103.218e+03	339.455e+03
2	7	-15.790e+03	4.729e+03	-95.022e+03	256.727e+03
2	8	-20.412e+03	3.520e+03	-98.131e+03	131.951e+03
2	9	-25.595e+03	2.872e+03	-206.568e+03	59.151e+03
2	10	-31.228e+03	2.674e+03	-438.560e+03	56.553e+03
3	0	-930.922e+00	26.575e+03	-438.560e+03	56.553e+03
3	1	-1.052e+03	22.825e+03	-307.670e+03	69.701e+03
3	2	-1.439e+03	19.341e+03	-249.258e+03	131.798e+03
3	3	-2.135e+03	16.165e+03	-218.101e+03	197.637e+03
3	4	-3.175e+03	13.335e+03	-186.943e+03	239.958e+03

3	5	-4.597e+03	10.885e+03	-155.786e+03	258.760e+03
3	6	-6.426e+03	8.843e+03	-124.629e+03	254.045e+03
3	7	-8.686e+03	7.231e+03	-93.471e+03	225.811e+03
3	8	-11.393e+03	6.067e+03	-62.314e+03	174.058e+03
3	9	-14.561e+03	5.364e+03	-31.157e+03	98.788e+03
3	10	-18.197e+03	5.128e+03	0.000e+00	0.000e+00

Design Truck + Lane Envelopes (Per Lane)

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	-4.022e+03	20.388e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-2.285e+03	60.759e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-3.605e+03	57.804e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	-5.128e+03	18.197e+03	0.000e+00	0.000e+00

Dual Truck Train + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00	-204.891e+03	0.000e+00
1	9	0.000e+00	0.000e+00	-273.547e+03	0.000e+00
1	10	0.000e+00	0.000e+00	-425.496e+03	0.000e+00
2	0	0.000e+00	0.000e+00	-425.496e+03	0.000e+00
2	1	0.000e+00	0.000e+00	-217.948e+03	0.000e+00
2	2	0.000e+00	0.000e+00	-126.428e+03	0.000e+00
2	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00	-185.911e+03	0.000e+00
2	10	0.000e+00	0.000e+00	-394.704e+03	0.000e+00
3	0	0.000e+00	0.000e+00	-394.704e+03	0.000e+00
3	1	0.000e+00	0.000e+00	-276.903e+03	0.000e+00
3	2	0.000e+00	0.000e+00	-224.332e+03	0.000e+00
3	3	0.000e+00	0.000e+00	-196.291e+03	0.000e+00
3	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Dual Lane Axle
Rxn – No Impact
and No Truck

Dual Truck Train + Lane Envelopes (Per Lane)

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	-2.056e+03	54.683e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	-3.245e+03	52.023e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Dual Tandem Train + Lane Envelopes (Per Lane)

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00

1	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Dual Tandem Train + Lane Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Fatigue Truck Envelopes (Per Lane)

Span	Point	Min Shear(lbs)	Max Shear(lbs)	Min Moment(ft-lbs)	Max Moment(ft-lbs)
1	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
1	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00

2	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	1	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	2	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	3	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	4	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	5	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	6	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	7	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	8	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	9	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	10	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Fatigue Truck Envelopes (Per Lane)

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00	0.000e+00

Strength I Limit State Envelopes

Span	Point	Min Shear(lbs)	Max Shear(lbs)	Min Moment(ft-lbs)	Max Moment(ft-lbs)
1	0	15.990e+03	67.665e+03	0.000e+00	0.000e+00
1	1	9.135e+03	51.418e+03	90.605e+03	419.535e+03
1	2	1.310e+03	36.142e+03	136.160e+03	720.679e+03
1	3	-7.466e+03	21.817e+03	136.665e+03	903.432e+03
1	4	-18.116e+03	9.367e+03	92.120e+03	967.794e+03
1	5	-31.179e+03	-671.576e+00	2.525e+03	913.765e+03
1	6	-45.075e+03	-9.876e+03	-132.119e+03	741.344e+03
1	7	-59.744e+03	-18.308e+03	-311.814e+03	450.533e+03
1	8	-75.115e+03	-26.039e+03	-590.288e+03	95.059e+03
1	9	-91.096e+03	-33.159e+03	-1.029e+06	-263.282e+03
1	10	-107.596e+03	-39.760e+03	-1.692e+06	-560.538e+03
2	0	38.922e+03	113.567e+03	-1.692e+06	-560.538e+03
2	1	30.313e+03	92.299e+03	-807.467e+03	-187.386e+03
2	2	20.861e+03	71.874e+03	-252.289e+03	242.660e+03
2	3	10.396e+03	52.463e+03	-32.061e+03	734.286e+03
2	4	-1.203e+03	34.186e+03	103.182e+03	1.037e+06
2	5	-14.005e+03	17.112e+03	163.075e+03	1.142e+06
2	6	-30.896e+03	4.127e+03	147.618e+03	1.049e+06
2	7	-49.313e+03	-7.332e+03	56.811e+03	759.133e+03
2	8	-68.838e+03	-17.684e+03	-129.131e+03	290.080e+03
2	9	-89.346e+03	-27.052e+03	-657.678e+03	-109.737e+03
2	10	-110.642e+03	-35.633e+03	-1.523e+06	-445.485e+03
3	0	34.670e+03	96.923e+03	-1.523e+06	-445.485e+03
3	1	28.990e+03	82.767e+03	-1.011e+06	-218.562e+03
3	2	22.845e+03	69.076e+03	-672.095e+03	60.805e+03
3	3	16.160e+03	55.925e+03	-426.621e+03	313.506e+03
3	4	8.872e+03	43.377e+03	-255.243e+03	519.799e+03
3	5	916.702e+00	31.497e+03	-129.665e+03	651.388e+03
3	6	-7.751e+03	20.329e+03	-37.302e+03	695.688e+03
3	7	-17.940e+03	10.682e+03	21.846e+03	652.699e+03
3	8	-30.272e+03	3.177e+03	47.779e+03	522.422e+03
3	9	-43.409e+03	-3.520e+03	40.497e+03	304.855e+03
3	10	-57.366e+03	-9.399e+03	0.000e+00	0.000e+00

Strength I Limit State Envelopes

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	15.990e+03	67.665e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	78.682e+03	221.164e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	70.303e+03	207.565e+03	0.000e+00	0.000e+00

4 0.000e+00 0.000e+00 9.399e+03 57.366e+03 0.000e+00 0.000e+00

Service I Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	21.565e+03	45.976e+03	0.000e+00	0.000e+00
1	1	14.211e+03	34.671e+03	127.548e+03	284.307e+03
1	2	6.304e+03	23.920e+03	205.041e+03	486.661e+03
1	3	-2.147e+03	13.713e+03	232.479e+03	607.061e+03
1	4	-11.127e+03	4.035e+03	209.861e+03	645.508e+03
1	5	-20.613e+03	-5.137e+03	137.187e+03	602.000e+03
1	6	-30.575e+03	-13.833e+03	14.457e+03	476.540e+03
1	7	-40.978e+03	-22.088e+03	-158.327e+03	269.125e+03
1	8	-51.783e+03	-29.942e+03	-381.168e+03	-20.242e+03
1	9	-62.937e+03	-37.447e+03	-701.891e+03	-343.737e+03
1	10	-74.387e+03	-44.656e+03	-1.165e+06	-656.637e+03
2	0	44.927e+03	78.240e+03	-1.165e+06	-656.637e+03
2	1	35.563e+03	63.472e+03	-549.108e+03	-256.165e+03
2	2	25.718e+03	49.187e+03	-145.641e+03	136.153e+03
2	3	15.293e+03	35.481e+03	85.083e+03	480.418e+03
2	4	4.221e+03	22.422e+03	227.612e+03	692.079e+03
2	5	-7.538e+03	10.051e+03	286.419e+03	766.666e+03
2	6	-19.996e+03	-1.621e+03	261.504e+03	704.178e+03
2	7	-33.134e+03	-12.614e+03	152.866e+03	504.615e+03
2	8	-46.905e+03	-22.973e+03	-50.799e+03	179.283e+03
2	9	-61.238e+03	-32.771e+03	-443.515e+03	-177.795e+03
2	10	-76.022e+03	-42.118e+03	-1.043e+06	-548.395e+03
3	0	39.402e+03	66.908e+03	-1.043e+06	-548.395e+03
3	1	33.205e+03	57.083e+03	-686.049e+03	-308.676e+03
3	2	26.743e+03	47.524e+03	-437.972e+03	-56.915e+03
3	3	19.972e+03	38.273e+03	-254.056e+03	161.682e+03
3	4	12.857e+03	29.368e+03	-107.045e+03	319.856e+03
3	5	5.360e+03	20.843e+03	3.059e+03	417.606e+03
3	6	-2.543e+03	12.726e+03	76.258e+03	454.933e+03
3	7	-10.878e+03	5.039e+03	112.552e+03	431.835e+03
3	8	-19.660e+03	-2.199e+03	111.940e+03	348.314e+03
3	9	-28.903e+03	-8.977e+03	74.423e+03	204.369e+03
3	10	-38.614e+03	-15.288e+03	0.000e+00	0.000e+00

Service I Limit State Envelopes

Pier	FxMin (lbs)	FxMax (lbs)	FyMin (lbs)	FyMax (lbs)	MzMin (ft-lbs)	MzMax (ft-lbs)
1	0.000e+00	0.000e+00	21.565e+03	45.976e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	89.583e+03	152.627e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	81.520e+03	142.931e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	15.288e+03	38.614e+03	0.000e+00	0.000e+00

Service II Limit State Envelopes

Span	Point	Min Shear (lbs)	Max Shear (lbs)	Min Moment (ft-lbs)	Max Moment (ft-lbs)
1	0	20.358e+03	52.093e+03	0.000e+00	0.000e+00
1	1	12.921e+03	39.519e+03	119.011e+03	322.798e+03
1	2	4.764e+03	27.665e+03	187.967e+03	554.073e+03
1	3	-4.100e+03	16.519e+03	206.867e+03	693.824e+03
1	4	-13.652e+03	6.059e+03	175.712e+03	742.053e+03
1	5	-23.860e+03	-3.742e+03	94.501e+03	698.759e+03
1	6	-34.689e+03	-12.925e+03	-36.765e+03	563.941e+03
1	7	-46.091e+03	-21.534e+03	-218.087e+03	337.601e+03
1	8	-58.015e+03	-29.621e+03	-449.465e+03	19.737e+03
1	9	-70.392e+03	-37.255e+03	-793.074e+03	-327.473e+03
1	10	-83.154e+03	-44.504e+03	-1.307e+06	-645.895e+03
2	0	44.393e+03	87.700e+03	-1.307e+06	-645.895e+03
2	1	34.966e+03	71.247e+03	-621.757e+03	-240.931e+03
2	2	24.911e+03	55.421e+03	-187.784e+03	178.549e+03
2	3	14.105e+03	40.348e+03	46.741e+03	560.676e+03

2	4	2.455e+03	26.117e+03	191.729e+03	795.536e+03
2	5	-10.086e+03	12.780e+03	252.995e+03	877.316e+03
2	6	-23.537e+03	350.374e+00	230.538e+03	806.015e+03
2	7	-37.871e+03	-11.195e+03	124.359e+03	581.633e+03
2	8	-53.029e+03	-21.917e+03	-80.238e+03	218.869e+03
2	9	-68.917e+03	-31.909e+03	-505.486e+03	-160.050e+03
2	10	-85.390e+03	-41.316e+03	-1.175e+06	-531.429e+03
3	0	39.122e+03	74.881e+03	-1.175e+06	-531.429e+03
3	1	32.889e+03	63.931e+03	-778.350e+03	-287.766e+03
3	2	26.311e+03	53.326e+03	-512.750e+03	-17.375e+03
3	3	19.332e+03	43.123e+03	-319.486e+03	220.973e+03
3	4	11.904e+03	33.368e+03	-163.128e+03	391.844e+03
3	5	3.981e+03	24.109e+03	-43.676e+03	495.234e+03
3	6	-4.471e+03	15.379e+03	38.869e+03	531.146e+03
3	7	-13.483e+03	7.209e+03	84.510e+03	499.578e+03
3	8	-23.078e+03	-379.127e+00	93.246e+03	400.531e+03
3	9	-33.271e+03	-7.368e+03	65.075e+03	234.005e+03
3	10	-44.073e+03	-13.749e+03	0.000e+00	0.000e+00

Service II Limit State Envelopes

Pier	FxMin(lbs)	FxMax(lbs)	FyMin(lbs)	FyMax(lbs)	MzMin(ft-lbs)	MzMax(ft-lbs)
1	0.000e+00	0.000e+00	20.358e+03	52.093e+03	0.000e+00	0.000e+00
2	0.000e+00	0.000e+00	88.897e+03	170.855e+03	0.000e+00	0.000e+00
3	0.000e+00	0.000e+00	80.439e+03	160.272e+03	0.000e+00	0.000e+00
4	0.000e+00	0.000e+00	13.749e+03	44.073e+03	0.000e+00	0.000e+00

Service III Limit State Envelopes

Span	Point	Min Shear(lbs)	Max Shear(lbs)	Min Moment(ft-lbs)	Max Moment(ft-lbs)
1	0	22.370e+03	41.898e+03	0.000e+00	0.000e+00
1	1	15.072e+03	31.439e+03	133.240e+03	258.647e+03
1	2	7.331e+03	21.424e+03	216.424e+03	441.720e+03
1	3	-845.361e+00	11.843e+03	249.553e+03	549.219e+03
1	4	-9.444e+03	2.685e+03	232.626e+03	581.144e+03
1	5	-18.447e+03	-6.067e+03	165.644e+03	537.495e+03
1	6	-27.832e+03	-14.439e+03	48.606e+03	418.272e+03
1	7	-37.570e+03	-22.458e+03	-118.487e+03	223.474e+03
1	8	-47.629e+03	-30.156e+03	-335.636e+03	-46.896e+03
1	9	-57.967e+03	-37.575e+03	-641.103e+03	-354.579e+03
1	10	-68.542e+03	-44.757e+03	-1.070e+06	-663.799e+03
2	0	45.282e+03	71.933e+03	-1.070e+06	-663.799e+03
2	1	35.962e+03	58.289e+03	-500.675e+03	-266.320e+03
2	2	26.255e+03	45.031e+03	-117.546e+03	107.890e+03
2	3	16.086e+03	32.236e+03	110.644e+03	426.912e+03
2	4	5.398e+03	19.959e+03	251.534e+03	623.108e+03
2	5	-5.839e+03	8.232e+03	308.702e+03	692.900e+03
2	6	-17.635e+03	-2.935e+03	282.148e+03	636.287e+03
2	7	-29.976e+03	-13.560e+03	171.870e+03	453.270e+03
2	8	-42.823e+03	-23.677e+03	-31.173e+03	152.893e+03
2	9	-56.119e+03	-33.345e+03	-402.202e+03	-189.626e+03
2	10	-69.776e+03	-42.653e+03	-955.796e+03	-559.706e+03
3	0	39.588e+03	61.593e+03	-955.796e+03	-559.706e+03
3	1	33.416e+03	52.518e+03	-624.514e+03	-322.617e+03
3	2	27.031e+03	43.656e+03	-388.120e+03	-83.275e+03
3	3	20.399e+03	35.040e+03	-210.436e+03	122.155e+03
3	4	13.492e+03	26.701e+03	-69.656e+03	271.864e+03
3	5	6.280e+03	18.666e+03	34.216e+03	365.854e+03
3	6	-1.258e+03	10.957e+03	101.184e+03	404.124e+03
3	7	-9.140e+03	3.593e+03	131.246e+03	386.673e+03
3	8	-17.381e+03	-3.412e+03	124.403e+03	313.502e+03
3	9	-25.990e+03	-10.050e+03	80.654e+03	184.611e+03
3	10	-34.974e+03	-16.313e+03	0.000e+00	0.000e+00

LRFD Pier Live Load Distribution

DOT refers to the Iowa Department of Transportation.
OBS refers to the Iowa DOT Office of Bridges and Structures

Developed on 12/09/2006
Last Modified on 8/26/2010

Disclaimer: This software is intended for use by Iowa DOT personnel and consultants working for the OBS in their development of projects for the Iowa DOT. Any other use is at the sole discretion of the user. The Iowa DOT makes the software available "AS IS" and assumes no liability nor makes any warranty of any kind, including warranties of noninfringement, fitness or merchantability whether expressed or implied, to the accuracy or functionality of this software. By downloading or using this file, you are agreeing to this disclaimer.

The OBS will only support those persons using this software in connection with Iowa DOT related business.

Please report any spreadsheet errors to the Iowa DOT OBS.

This spreadsheet was developed to aid the design of typical Iowa DOT piers. The Iowa DOT Bridge Design Manual (BDM) should be consulted for the most up-to-date policies.

Description:

This spreadsheet allows the user to determine live load beam reactions to a pier cap for varying transverse live load positions and varying numbers of lanes loaded. The distribution of live load through the slab to the beams is based on the assumption that the slab between beams is simply supported. Office practice is to distribute the live load to the exterior beam with the assumption that all of the live load on the slab overhang is transferred to the exterior beam. [However, provision is made in the spreadsheet to distribute live load on the slab overhang to the exterior and first interior beam based on slab continuity over the simple exterior beam support.] This spreadsheet is designed to facilitate input into the LEAP[®] RC-PIER[®] (RC-Pier) program.

RC-Pier Import Feature:

The loads generated by this spreadsheet can be exported to a text file that can be imported directly into RC-Pier.

Steps:

- 1.) The user must determine the HL-93 live load axle pier reaction from a software such as QConBridge™. The truck and lane axle reactions must be determined separately. Impact should be removed from the live load truck reaction. Multiple Presence Factors should be excluded as well.
- 2.) The user should fill in the cell input entries on the **Geometry** tab. Cell input entries are typically shown in bold blue text as: **Input**
Cells with calculated output are typically shown in bold red text as: **Output**
- 3.) The **Placement** tab allows the user to place lanes of live load in different positions along the slab. The resulting beam reactions are based on unit load influence values of 1.000 kip for the lane and truck axle live loads (see the **Geometry** tab). Each load case can be stored, recalled, and/or deleted using the buttons on the **Placement** tab. (The calculated beam reactions include the Multiple Presence Factors.)
- 4.) The **PierResults** tab allows the user to scale the unit load influence beam reactions by the actual truck and lane axle reactions for up to four piers (i.e. four different live load pier reactions). These live load reactions can be exported to a text file which can be imported directly into RC-Pier.
- 5.) The **LoadGraphs** tab allows the user to print a copy of the graphs showing the live load arrangements for each load case.

Limitations:

- 1.) Up to 10 beam lines can be entered.
- 2.) Up to 8 lanes of live load can be present in a load case.
- 3.) Up to 20 load cases can be stored.
- 4.) Beam reactions, based on the same unit load influence values, can be stored for up to 4 piers.

Notes:

- 1.) The user must manually place the live loads in order to create a suitable envelope of loads for a pier design. On the **Geometry** tab the user has the option to enter some of the pier geometry. Entering this geometry allows the pier to be graphed on the **Placement** tab. The intent is to help the user to visualize how the live loads should be placed in order to generate the live load envelopes needed for pier design.
- 2.) On the **Placement** tab, you must enter both the traffic location and the distributed lane location in order for the graph to plot the new load and for the beam reactions to be recalculated for the new load.
- 3.) A truck axle load is placed on the slab as two concentrated wheel loads spaced 6' apart. The lane axle load is placed as a 10' wide uniformly distributed load. The truck load is always centered about the lane load.
- 4.) If you change something on the **Geometry** tab you should recall each saved load case and resave to overwrite the previous one. The spreadsheet does not automatically update the beam reactions for changes.
- 5.) The **unitLoadResults**, **calcGraph**, and **calcBeamRxn** tabs contain most of the calculations needed for the spreadsheet to work.

Specify Bridge Geometry and Live Load

Note: Roadway dimensions and beam spacing should be taken as perpendicular to roadway.

Out to Out Slab Width (vOOS)	43.160	ft
Roadway Width (vRW)	40.000	ft
Left Curb Width (vLCW): Slab Edge to Gutterline	1.580	ft

Beam Height (vBH)	4.500	ft
Number of Beams (vNB)	6	
Left Slab Edge to Beam 1 (vBM01)	3.080	ft
Beam 1 to Beam 2 (vBM12)	7.400	ft
Beam 2 to Beam 3 (vBM23)	7.400	ft
Beam 3 to Beam 4 (vBM34)	7.400	ft
Beam 4 to Beam 5 (vBM45)	7.400	ft
Beam 5 to Beam 6 (vBM56)	7.400	ft
Beam 6 to Beam 7 (vBM67)		ft
Beam 7 to Beam 8 (vBM78)		ft
Beam 8 to Beam 9 (vBM89)		ft
Beam 9 to Beam 10 (vBM910)		ft

Overhang: 1 = Continuous, 0 = Hinged (vOHG) 0

Traffic Lane Width for Placement (vTLWP) 12.000 ft

* Unit Truck Axle Reaction (vTAR) 1.000 k
Unit Lane Axle Reaction (vLAR) 1.000 k

Traffic Lane Width for Max # of Lanes	12.000	ft
Max. Number of Possible Lanes (vNPL)	3	
Transv. Wheel Spacing (vWS)	6.000	ft
Transv. Lane Distribution Width (vLDW)	10.000	ft

Note: Blue text is for user input
Red text is typ. calculated

#	Graph Pier: 1 = Yes, 0 = No (vGP)	1
	Note: Fill out information below if you want to graph the pier.	
	Skew, always positive (vSKW)	32.000 deg

Pier dimensions should be based on distances along the skewed cap.		
Cap Length (vCL)	49.000	ft
Left Cap Edge to Beam 1 (vLCEB1)	2.688	ft
Cap Height (vCH)	7.000	ft
Round Column: 1 = Yes, 0 = No (vRCOL)	0	
Column Diameter or Width (vCW)	20.000	ft
Number of Columns (vNC)	1	
Left Cap Edge to Column 1 (vCOL01)	24.500	ft
Column 1 to Column 2 (vCOL12)		ft
Column 2 to Column 3 (vCOL23)		ft
Column 3 to Column 4 (vCOL34)		ft
Column 4 to Column 5 (vCOL45)		ft

<- Office practice is to use Hinged.

RC-Pier uses Continuous for auto-generation of LL.

<- Office practice is to use 12' RC-Pier uses 10'.

<- Unit loads for truck and lane.

Number of Lanes	MPF
1 Lane (vMPF1)	1.20
2 Lanes (vMPF2)	1.00
3 Lanes (vMPF3)	0.85
> 3 Lanes (vMPF4)	0.65

* The truck and lane axle reactions will be treated as influence values first. Thus piers with similar geometry, but different live load reactions may be scaled from the same set of influence values for different live load positions.

Graphing the pier allows the user to better visualize the column locations with respect to the beam locations.

Place Traffic Lane Loads

Roadway Width 40.00000 ft


Lane #	Traffic Lane Location - ft (based on left gutterline)		
	Min	Max	Actual
Lane 1	0.00000	28.00000	2.00000
Lane 2	14.00000	28.00000	14.00000
Lane 3	26.00000	28.00000	26.00000
Lane 4			
Lane 5			
Lane 6			
Lane 7			
Lane 8			
Lane 9			
Lane 10			
Number of Lanes Occupied			3

Number of Load Cases Stored (20 Max.) = 7

Store As Case # 7
Recal Case #
Delete Case #

Uniform Lane Load	0.100	k/ft	
Conc Truck Load	0.500	k	
One wheel Line			
Lane #	Distributed Lane Location - ft (based on left lane edge)		
	Min	Max	Actual
Lane 1	0.00000	2.00000	2.00000
Lane 2	0.00000	2.00000	1.00000
Lane 3	0.00000	2.00000	0.00000
Lane 4			
Lane 5			
Lane 6			
Lane 7			
Lane 8			
Lane 9			
Lane 10			

Beam Reactions	Truck	Lane	MPF =	0.85
Beam #	Rxn (k)	Rxn (k)	Total	Rxn (k)
1	0.167	0.138	0.304	
2	0.505	0.572	1.078	
3	0.603	0.565	1.168	
4	0.603	0.565	1.168	
5	0.505	0.572	1.078	
6	0.167	0.138	0.304	
Total	2.550	2.550	5.100	



Live Load Placement Screen showing the 7th live load case.

These are influence values.

Unit Load Results

For RC-Pier live load input:

- 1.) Impact should be excluded from the (truck) reactions.
- 2.) Multiple Presence Factors (MPF) are included in the reactions.
- 3.) Beam reactions for truck and lane loads should be entered separately.
- 4.) Truck load results should be entered first, followed by lane load results.
- 5.) Auto-generation of live load in RC-Pier assumes the overhang is continuous over the exterior beam.
- 6.) Auto-generation of live load in RC-Pier assumes 10' traffic lanes.

These are the pier 1 LL reactions from QConBridge (no impact).

Export Pier 1 Loads to Text Files

This button allows the user to export these loads to a text file that may be imported into RC-Pier.

Pier 1											
Enter Truck Axle Rxn at Pier	85.662	k									
Enter Lane Axle Rxn at Pier	54.683	k									
Truck Axle Rxn Used	85.662	k									
Lane Axle Rxn Used	54.683	k									
									Unit Truck Axle Rxn Influence Value	1.000	
									Unit Lane Axle Rxn Influence Value	1.000	
Beam Reactions (kips)											
Case Number		Beam 1	Beam 2	Beam 3	Beam 4	Beam 5	Beam 6	Beam 7	Beam 8	Beam 9	Beam 10
1	Truck	54.175	48.619	0.000	0.000	0.000	0.000				
	Lane	34.122	30.961	0.536	0.000	0.000	0.000				
2	Truck	0.000	0.000	0.000	0.000	48.619	54.175				
	Lane	0.000	0.000	0.000	0.536	30.961	34.122				
3	Truck	45.146	53.828	50.934	21.416	0.000	0.000				
	Lane	28.435	32.632	36.294	12.004	0.000	0.000				
4	Truck	0.000	0.000	21.416	50.934	53.828	45.146				
	Lane	0.000	0.000	12.004	36.294	32.632	28.435				
5	Truck	38.374	45.754	43.294	43.294	43.294	4.428				
	Lane	24.170	27.738	30.850	26.035	28.008	2.641				
6	Truck	4.428	43.294	43.294	43.294	45.754	38.374				
	Lane	2.641	28.008	26.035	30.850	27.738	24.170				
7	Truck	14.267	43.294	51.658	51.658	43.294	14.267				
	Lane	7.541	31.302	30.878	30.878	31.302	7.541				
8	Truck										
	Lane										
9	Truck										
	Lane										
10	Truck										
	Lane										


These loads may be entered or imported directly into RC-Pier. As required by RC-Pier: impact is not included, but multiple presence factors (MPFs) are included.

Location of Live Loads (ft)									
Case Number		Lane 1	Lane 2	Lane 3	Lane 4	Lane 5	Lane 6	Lane 7	Lane 8
1	Traffic Lane Location	0.000							
	Distributed Lane Location	0.000							
2	Traffic Lane Location	28.000							
	Distributed Lane Location	2.000							
3	Traffic Lane Location	0.000	12.000						
	Distributed Lane Location	0.000	0.000						
4	Traffic Lane Location	16.000	28.000						
	Distributed Lane Location	2.000	2.000						
5	Traffic Lane Location	0.000	12.000	24.000					
	Distributed Lane Location	0.000	0.000	0.000					
6	Traffic Lane Location	4.000	16.000	28.000					
	Distributed Lane Location	2.000	2.000	2.000					
7	Traffic Lane Location	2.000	14.000	26.000					
	Distributed Lane Location	2.000	1.000	0.000					
8	Traffic Lane Location								
	Distributed Lane Location								
9	Traffic Lane Location								
	Distributed Lane Location								
10	Traffic Lane Location								
	Distributed Lane Location								


Describes the location of each live load for each load case with respect to the left gutterline.

Graphs depict live load locations for each load case.


Load Case 1




Load Case 2




Load Case 3




Load Case 4




Load Case 5




Load Case 6



Load Case 7



Load Case 8



Geometrical Considerations for Various Loadings


Average span length is used for superstructure wind loading and braking forces.

$$\text{Avg Span Length} = (0.5) * (70.75' + 91.5') = 81.125'$$

Typically average step height, bearing pad height, and average haunch are used for determining exposed wind areas and distances from lateral superstructure loads to the top of the pier cap. RC-Pier is not really able to accommodate this in its load auto-generation procedure. Since these additional depths are relatively small for this bridge they will be ignored.

$$\begin{aligned} \text{Avg Step Hgt} &= [(693.71 + 693.94 + 694.18 + 694.35 + 694.29 + 694.23)/(6 \text{ Beams})] - 693.71 \\ &= 0.407' \text{ -- Ignored} \end{aligned}$$

$$\text{Bearing Pad Hgt} + \text{Pintle Plate Thk} = 2.5'' + 1.5'' = 0.333' \text{ -- Ignored}$$



Length x Width = 20'' x 10''
 Pad Area = 200 in²
 Neoprene Thk = 2.5'' - (4 plates)*(0.125'') = 2''
 Shear Modulus, Gmax = 0.130 ksi -- 50 Durometer

$$\text{Avg Haunch} = 1'' = 0.083' \text{ -- Ignored}$$

$$\begin{aligned} \text{Superstructure Wind Area} &= (2.833' \text{ SBC Hgt}) + (8'' \text{ Slab Thk})/(12 \text{ in/ft}) + (4.5' \text{ Beam Hgt}) \\ &= 8.00' \end{aligned}$$

$$\text{Center of Gravity of Superstructure Wind Area to Top of Pier Cap} = (0.5) * (8.00') = 4.00'$$

$$\text{Dist from Slab Top to Top of Pier Cap} = (8'' \text{ Slab Thk})/(12 \text{ in/ft}) + (4.5' \text{ Beam Hgt}) = 5.17'$$


Earth cover on top of footing is used not only for the fill weight on the footing. It can also figure into the exposed wind area of the substructure, stream flow forces, and ice forces.

$$\text{Depth of Earth Cover over Top of Footing} = 10' \text{ approximate}$$

Equivalent Column Dimensions

$$\begin{aligned} W_R &= [(0.5) * (\pi * R^2)] / (2 * R) \\ W_R &= [(0.5) * (\pi) * (1.5')^2] / (2 * 1.5') = 1.178' \end{aligned}$$

$$\begin{aligned} \text{Equiv Column Length} &= 17' + 2 * W_R \\ \text{Equiv Column Length} &= 17' + 2 * 1.178' \\ \text{Equiv Column Length} &= 19.356' \end{aligned}$$



Use 19.5' for equivalent column length and 3.0' for column width.

Temperature Considerations


1.) Superstructure Temperature Movement

Pier 1 has laminated neoprene expansion bearings. Pier 2 has fixed bearings. The abutments are integral. The temperature change is 50 degrees each way from 50 degrees F. The coefficient of thermal expansion is $\mu = 6 \times 10^{-6}$ per degree F.

$$\Delta = (91.5') * (6 \times 10^{-6} \text{ per degree F}) * (50 \text{ degrees F}) = 0.02745' = 0.3294''$$

$$\Delta z = \Delta * \cos\theta = (0.02745') * (\cos(32 \text{ deg})) = 0.02328'$$

$$\Delta x = \Delta * \sin\theta = (0.02745') * (\sin(32 \text{ deg})) = 0.01455'$$



Load Factors for Temperature Loads

Aashto Lrfd 3.4.1, 5th Edition, Top of Page 3-12

For substructure design Iowa typically uses gross inertia for the pier components. This means we will use the smaller load factors in Aashto Lrfd Load Tables 3.4.1-1 and 3.4.1-3 for TU when calculating force effects.

PIER TEMPERATURE FORCES

Developed on 6/27/2006
Last Modified on 8/26/2010

DOT refers to the Iowa Department of Transportation.
OBS refers to the Iowa DOT Office of Bridges and Structures

Disclaimer: This software is intended for use by Iowa DOT personnel and consultants working for the OBS in their development of projects for the Iowa DOT. Any other use is at the sole discretion of the user. The Iowa DOT makes the software available "AS IS" and assumes no liability nor makes any warranty of any kind, including warranties of noninfringement, fitness or merchantability whether expressed or implied, to the accuracy or functionality of this software. By downloading or using this file, you are agreeing to this disclaimer.

The OBS will only support those persons using this software in connection with Iowa DOT related business.

Please report any spreadsheet errors to the Iowa DOT OBS.

This spreadsheet was developed to aid the design of typical Iowa DOT piers. The Iowa DOT Bridge Design Manual (BDM) should be consulted for the most up-to-date policies.

Description:

This spreadsheet will determine the lateral forces that must be applied to the top of a pier in order to produce the corresponding lateral deflections that are typically induced by the superstructure temperature movements. The spreadsheet can also generate a STAAD input file for verification. There are a number of simplifying assumptions made in the spreadsheet. The user is responsible for understanding those assumptions and for determining their appropriateness for their design.

The "Description", "Input", and "Output" worksheets are the only worksheets the user needs to consider. Some intermediate calculations are performed on the "Input" worksheet. The worksheet area where these are done is clearly marked.

Assumptions & Limitations

- 1.) Bearing pad flexibility can be considered.
- 2.) The pier cap stiffness is not considered for single column piers. The cantilevers if present use the average cross-sectional dimension of the cap height at end and cap height at center. The cap can be considered "infinitely" stiff (the cap area and inertia are set to 10,000 ft² and 100,000 ft⁴ respectively if this option is used).
- 3.) One to five columns can be input. Each column can be of a different height and cross-sectional dimension. Columns can be round or rectangular, and if rectangular they can also be tapered in one or both directions. Columns are split into five segments and the average cross-sectional dimensions of the individual segments are used for member properties. Column height input by the user is used in both directions. The column height is not adjusted by the spreadsheet (ie. column height is not adjusted by one-half of the cap height.)
- 4.) The rotational flexibility of the pile footings due to axial pile shortening can be input. Up to 50 piles per footing can be entered. Each footing can have a different pile arrangement and pile type. Pile arrangements must be symmetrical about the centerline of the column.
- 5.) The Direct Stiffness Method is used to solve the problem.
- 6.) The pier is assumed to move as a unit in the weak-axis direction (all columns deflect the same amount). The cap does not contribute to the model in the weak-axis direction. In the strong-axis direction, the average deflection of the pier at the top of the columns due to a unit lateral force is used to establish the pier stiffness. This stiffness combined with the actual superstructure deflection due to temperature is then used to determine the actual temperature force.
- 7.) The action and response of the pier in the X and Z axes directions are treated independently of one another.

Pier Stiffness and Temperature Forces

This spreadsheet is designed to determine the forces induced in the pier by temperature movements from the superstructure. The temperature movement along the c.l. of the bridge roadway should be broken down into components transverse and parallel to the pier (always use positive displacements). Once these have been input and the geometry of the pier including any pads and piling have been defined then the program will determine the forces needed to produce those movements. These forces can be entered into RC-Pier as a temperature load. The user must ensure that the sign of the forces entered into RC-Pier are correct.

See previous page for calculation of temperature movements.

Input

	X-Dir'n, ft	Z-Dir'n, ft
Temperature Movement	0.01455	0.02328

Number of Elastomeric Pads	12	0 if no pads
Pad Shear Modulus, G	130.000	psi
Thickness of Neoprene Only	2.000	in
Area of One Pad	200.000	in ²

f _c	3500.000	psi
----------------	----------	-----

Cap Height at Center (Y)	7.000	ft
Cap Height at End (Y)	4.000	ft
Cap Depth (Z)	3.500	ft

Treat Cap as Infinitely Rigid?	N	(Y)es or (N)o
--------------------------------	---	---------------

Left Overhang Length (X)	24.500	ft
Right Overhang Length (X)	24.500	ft

Number of Columns	1	Max of 5
-------------------	---	----------

Distance Between Columns (X)	Column 1-2	Column 2-3	Column 3-4	Column 4-5	ft
------------------------------	------------	------------	------------	------------	----

All Columns the Same?	Y	(Y)es or (N)o	If yes then only enter information for column 1.
-----------------------	---	---------------	--

Column Dimensions	Column 1, ft	Column 2, ft	Column 3, ft	Column 4, ft	Column 5, ft
Column Width at Top (X)	19.500				
Column Width at Bottom (X)	19.500				
Column Depth at Top (Z)	3.000				
Column Depth at Bottom (Z)	3.000				
Column Height (Y)	32.000				



Enter column diameter for round columns.
 Enter 0 if column is round.
 Enter 0 if column is round.
 Enter 0 if column is round.
 Column Height:
 Frame Pier: Top of fig to ctr of cap.
 T-Pier: Top of fig to top of cap.

Include Piling?	N	(Y)es or (N)o
-----------------	---	---------------

All Piling the Same?	Y	(Y)es or (N)o	If yes then only enter information for footing 1.
----------------------	---	---------------	---

Treat Pier Cap Axial Stiffness as Infinitely Rigid?	Y	(Y)es or (N)o
---	---	---------------

Just axial stiffness not bending.



Piling flexibility will be ignored. Even though we have T-Piers on a large skew we have fairly flexible expansion bearings so the temperature forces won't be that significant. Additionally the piling doesn't add much flexibility to the pier since the piling is short and the pile inertia of the group is large.

Piling Information	Footing 1, ft		Footing 2, ft		Footing 3, ft		Footing 4, ft		Footing 5, ft	
Pile: 1=Steel,2=Wood,3=Conc	1									
If Concrete Pile, Enter f _c in psi										
Effective Pile Length, ft	15.000									
Area of One Pile, ft ²	0.117									
Pile Location	X, ft	Z, ft	X, ft	Z, ft	X, ft	Z, ft	X, ft	Z, ft	X, ft	Z, ft
1	12.500	6.000								
2	12.500	2.000								
3	12.500	-2.000								
4	12.500	-6.000								
5	7.500	6.000								
6	7.500	2.000								
7	7.500	-2.000								
8	7.500	-6.000								
9	2.500	6.000								
10	2.500	2.000								
11	2.500	-2.000								
12	2.500	-6.000								
13	-2.500	6.000								
14	-2.500	2.000								
15	-2.500	-2.000								
16	-2.500	-6.000								
17	-7.500	6.000								
18	-7.500	2.000								
19	-7.500	-2.000								
20	-7.500	-6.000								
21	-12.500	6.000								
22	-12.500	2.000								
23	-12.500	-2.000								
24	-12.500	-6.000								
25										
26										
27										

HP 10x57 End Bearing Pile = (0.75)*(20' pile length)

Pile arrangement based on existing plans.

Typically the designer does not take pile flexibility into account since the pile arrangement is unknown and it is conservative to neglect it.

Results

Number of Columns	1
-------------------	----------



Are Pads Present?	Y
Is Cap Infinitely Rigid?	N
Is Piling Considered?	N

	X-Dir'n, ft	Z-Dir'n, ft
Temperature Movement	0.01455	0.02328

	X-Dir'n, k/ft	Z-Dir'n, k/ft
Pier Stiffness	1832.855	984.051

	X-Dir'n, k	Z-Dir'n, k
Temperature Force	26.668	22.909

← These forces are typically divided among the beams and applied to the top of the pier cap in RC-Pier.



Per Beam

$$Z: (22.909 \text{ k}) / (6 \text{ beams}) = 3.82 \text{ k}$$

$$X: (26.668 \text{ k}) / (6 \text{ beams}) = 4.44 \text{ k}$$

Auto-generated Temperature Loads in RC-Pier

The area of the bearing pad must be doubled since we only input one bearing line in RC-Pier. There are a total of 12 bearing pads.

Auto Load generation: Temperature load

Bearing data

Fixed bearings

Expansion bearings

Elastomeric bearings

Stiffness elastomer

Manual input Compute

Stiffness of Elastomer, Kbs: 0 kips/in

Area of bearing, A: 400.00 in²

Shear modulus of Elastomer: 0.13 ksi

Total elastomer thickness: 2.00 in

Superstructure data

Contributing length: 91.5 ft

Change in temperature: 50 °F

Coeff Thermal Expansion, alpha: 6.e-006 /°F

Pier data

Auto compute

User input:

Kcols: 0 kips/in

Generate Cancel

Direction of thermal force (Z): +[Z] -[Z]

RC-Pier does not auto-generate temperature loads for skewed piers according to Iowa DOT policy. First, the program calculates a thermal movement based on user input in the figure above. This thermal movement is assumed to act along the Z-axis of the pier. RC-Pier then calculates a thermal force based on the pier's stiffness about the weak axis (i.e. stiffness about the X-axis). The calculated thermal force is then inconsistently assumed to act along the C.L. of the roadway. Based on that inconsistent assumption, RC-Pier breaks the thermal force into component forces (and subsequently component beam forces) along the X- and Z-axes.

The Iowa DOT assumes the original thermal movement acts along the C.L. of the roadway. This movement is broken down into components along the X- and Z- axes. These component movements are used with the pier's stiffness about the strong and weak axes, respectively, in order to determine the thermal forces in each direction. RC-Pier will only determine the correct thermal forces for piers that are not skewed or for piers that have the same stiffness about both axes.

One additional note is that RC-Pier bases pier stiffness on column heights measured from the bottom of the column to the top of the pier cap. This is a good practice for T-Piers, but not for frame piers.

The temperature loads per beam that RC-Pier would auto-generate for this example based on the input in the figure above are:

$$F_z = -3.8179 \text{ k} \quad F_x = -2.3857 \text{ k}$$

These may be compared to the values calculated per beam on the previous page. The values are not too far off since the bearing pad flexibility is the same along both axes and because it dominates the flexibility.

BR & CE Pier Forces

Developed on 12/15/2005
Last Modified on 8/26/2010

DOT refers to the Iowa Department of Transportation.
OBS refers to the Iowa DOT Office of Bridges and Structures

Disclaimer: This software is intended for use by Iowa DOT personnel and consultants working for the OBS in their development of projects for the Iowa DOT. Any other use is at the sole discretion of the user. The Iowa DOT makes the software available "AS IS" and assumes no liability nor makes any warranty of any kind, including warranties of noninfringement, fitness or merchantability whether expressed or implied, to the accuracy or functionality of this software. By downloading or using this file, you are agreeing to this disclaimer.

The OBS will only support those persons using this software in connection with Iowa DOT related business.

Please report any spreadsheet errors to the Iowa DOT OBS.

This spreadsheet was developed to aid the design of typical Iowa DOT piers. The Iowa DOT Bridge Design Manual (BDM) should be consulted for the most up-to-date policies.

General Input Tab:

- 1.) The axes and direction of skew angle match the sign convention used in RC-Pier.
- 2.) The spreadsheet can handle up to 10 beam lines. The beam spacings can be constant or variable.
- 3.) Slab and beam dimensions should be entered perpendicular to the centerline of the roadway. Do not enter them along the skew of the pier.
- 4.) RC-Pier does not have an option to enter haunch thickness, bearing device thickness, or average step height on its Superstructure Parameters screen. This means the auto-generated loads for BR and CE will not be based on these additional dimensions.

RC-Pier Import Feature:

The loads generated by this spreadsheet can be exported to a text file that can be imported directly into RC-Pier.


BR Force Tab:

- 1.) If you auto-generate the BR loads in RC-Pier, then the entire truck portion of the BR load is applied to the pier. In RC-Pier, the truck portion of the BR load is not distributed proportionally to the pier of interest based on total number of bents, average span length, or bearing types. This contradicts office practice.
- 2.) If you auto-generate the BR loads in RC-Pier, then a torsional moment (M_x) will be generated about the pier cap. Office practice is to exclude such a moment about the pier's weak axis because we assume there is not a sufficient mechanism to transmit a moment from the superstructure to the substructure about this axis.
- 3.) Do not use the "Two Design Trucks + Lane Load" or "Two Design Tandem + Lane Load" options for auto-generating BR loads. These options use 90% of the axle weight for two trucks/tandems. This would contradict office practice.
- 4.) Office practice is to base the BR forces on the maximum number of lanes for all load combinations regardless of the number of lanes used for vertical live load. That is, we treat the BR load case (singular) independently from the vertical live load cases.

CE Force Tab:

- 1.) The total calculated CE force should, in its entirety, be applied to the pier of interest. The CE force is not distributed among the bents.
- 2.) If you auto-generate the CE loads in RC-Pier for a skewed bridge, then a torsional moment (M_x) will be generated about the pier cap. Office practice is to exclude such a moment about the pier's weak axis because we assume there is not a sufficient mechanism to transmit a moment from the superstructure to the substructure about this axis.
- 3.) Do not use the "Two Design Trucks + Lane Load" or "Two Design Tandem + Lane Load" options for auto-generating CE loads. These options use 90% of the axle weight for two trucks/tandems. This would contradict office practice.
- 4.) Office practice is to base the number of lanes for the CE force on the number of loaded lanes for vertical live load. That is, the CE load cases (plural) and the vertical live load cases are dependant on each other.
- 5.) The sign of the CE load depends upon the Pier View Direction. A +CE load in the downstation view is a -CE load in the Upstation View.

Definitions



Distribution of BR and CE through Beams

BR = Braking Force CE = Centrifugal Force

Aashto Lrfd 3.6.4 & 3.6.3

Important Note: Roadway dimensions and beam spacing should be taken as perpendicular to roadway.

Note: Blue text is for user input
Red text is typ. calculated


Pier View Direction (vVIEW), D or U	U	D is downstation, U is upstation
Skew (vSKW), RA is "+" LA is "-"	-32.000	deg

Number of Lanes	MPF
1 Lane (vMPF1)	1.20
2 Lanes (vMPF2)	1.00
3 Lanes (vMPF3)	0.85
> 3 Lanes (vMPF4)	0.65

Slab Thickness (vST)	8.000	in	*
Haunch Thickness (vHT)	0.000	in	*
Beam Height (vBH)	54.000	in	*
Bearing Device Thickness (vBDT)	0.000	in	*
Average Step Height (vASH)	0.000	in	*

* RC-Pier does not provide the option to enter these dimensions for its auto-generate features on the Superstructure Parameters screen, so you may want to set them to 0.

Out to Out Slab Width (vOOS)	43.160	ft
Roadway Width (vRW)	40.000	ft
Left Curb Width (vLCW)	1.580	ft



Number of Beams (vNB)	6	
Left Slab Edge to Beam 1 (vBM01)	3.080	ft
Beam 1 to Beam 2 (vBM12)	7.400	ft
Beam 2 to Beam 3 (vBM23)	7.400	ft
Beam 3 to Beam 4 (vBM34)	7.400	ft
Beam 4 to Beam 5 (vBM45)	7.400	ft
Beam 5 to Beam 6 (vBM56)	7.400	ft
Beam 6 to Beam 7 (vBM67)		ft
Beam 7 to Beam 8 (vBM78)		ft
Beam 8 to Beam 9 (vBM89)		ft
Beam 9 to Beam 10 (vBM910)		ft
Last Beam to Right Slab Edge	3.080	ft
Tot. Distance bet. Ext. Beams (vTBD)	37.000	ft

Distribution of BR through Beams

Aashto Lrfd 3.6.4

Total Truck Axle Weight (72 kips) or Total Tandem Axle Weight (50 kips) (Do not include impact.)	72.000	k	*
Uniformly Distr. Lane Load (0.640 kif)	0.640	kif	
Average Span Length	81.125	ft	#
Total Bridge Length	223.000	ft	%
Number of Traffic Lanes Loaded	2		

* Enter the tandem weight if the tandem controls the live load pier reaction. Enter the truck weight if the truck or double truck controls the live load pier reaction.

For some piers it may be necessary to use a different length than the average length (ex. bridges with friction-acting bearings require special consideration).

% This could also be the distance between superstructure expansion joints.

++

BR: 25% of Truck/Tandem	13.096	k	+
BR: 5% of Design Truck/Tandem + Lane	7.811	k	
Enter BR Force to be Used (vBRF)	13.096	k	!

+ Loads include the number of lanes loaded and the appropriate MPF.

! Allows the user to override the calculated values. Enter positive value.

Height of BR above Top of Slab (vHTS)	6.000	ft	**
---------------------------------------	-------	----	----

** BR is typically assumed to act 6' above top of slab.



How is Mz Transferred to the Pier?	1	##
Enter 1 if by Exterior Beams Only		
Enter 2 if All Beams Participate		

Export Loads to Text Files

The overturning moment, Mz, is transferred to the pier by equal and opposite Fy forces acting through the beams. RC-Pier assumes that only the exterior beams are involved.

Beam #	BR Loads to the Pier (kips)							
	BR acts in +Stationing Dir'n			BR acts in -Stationing Dir'n				
	Fx	Fy	Fz	Fx	Fy	Fz		
1	-1.157	-1.776	-1.851	1.157	1.776	1.851		
2	-1.157	0.000	-1.851	1.157	0.000	1.851		
3	-1.157	0.000	-1.851	1.157	0.000	1.851		
4	-1.157	0.000	-1.851	1.157	0.000	1.851		
5	-1.157	0.000	-1.851	1.157	0.000	1.851		
6	-1.157	1.776	-1.851	1.157	-1.776	1.851		
7								
8								
9								
10								
	Mx (k*ft)		-124.021	%%	Mx (k*ft)		124.021	%%

%% Bridge office practice is to set the overturning moment Mx to 0.00 even though RC-Pier does not. Mx is provided here for information only.



++ Typically 25% of the truck will control for short to medium bridge lengths.

Braking Example Sample Calculations

Use 2 lanes for all vertical LL cases, MPF = 1.0.

Total Truck Axle Weight = 8 k + 32 k + 32 k = 72 k

Average Span Length = (0.5)*(70.75' + 91.5') = 81.125'

Total Bridge Length = 70.75' + 91.5' + 60.75' = 223'

BR Load = (0.25)*(72 k)*(2 lanes)*[(81.125')/(223')]*(1.0) = 13.096 k ← Controls

OR

= (0.05)*[72 k + (0.640 k/ft)*(223')]*(2 lanes)*[(81.125')/(223')]*(1.0) = 7.811 k

$F_{z_total} = (13.096 \text{ k}) * (\cos(32 \text{ deg})) = 11.106 \text{ k}$

$F_{x_total} = (13.096 \text{ k}) * (\sin(32 \text{ deg})) = 6.940 \text{ k}$

$F_z \text{ per beam} = (11.106 \text{ k}) / (6 \text{ Beams}) = 1.851 \text{ k}$

$F_x \text{ per beam} = (6.940 \text{ k}) / (6 \text{ Beams}) = 1.157 \text{ k}$

$M_z = (6.940 \text{ k}) * [6' + (8'') / (12 \text{ in/ft}) + (54'') / (12 \text{ in/ft})] = -77.497 \text{ k*ft}$


$F_y = (-77.497 \text{ k*ft}) / [(5 \text{ Beam Spa}) * (7.4') / (\cos(32 \text{ deg}))] = -1.776 \text{ k}$

Beam 1, $F_y = 1.776 \text{ k}$

Beam 6, $F_y = -1.776 \text{ k}$

$M_x = (11.106 \text{ k}) * [6' + (8'') + (54'') / (12 \text{ in/ft})] = 124.021 \text{ k*ft}$

← Office Policy is to ignore



General Notes for Water Elevations See BDM 6.6.2.7, 6.6.2.9, and 6.6.4.1.3.1

For typical T-piers over water there are 5 water elevations of interest:

1.) Average Low Water Elevation

If the average low water elevation is not listed on the Situation (or TS&L = Type, Size, and Location) Plan prepared by Preliminary Bridge then average low water may be set as 1' above the average stream bed elevation. This water elevation is used in the design for the Strength and Service Limit State combinations.

2.) Design High Water (50 year flood) Elevation

Iowa typically uses this water elevation as the Design Flood for Waterway Opening from Aashto Lrfd 2.2. This water elevation should always be given on the Situation Plan. This water elevation is used in the design for the Strength and Service Limit State combinations.

3.) Ice Elevation

If this elevation is not listed on the Situation Plan then it may be assumed to be midway between Design High Water and Average Low Water. This elevation is used with ice loads in the Extreme Event Limit State.

4.) Design Flood (100 year flood) Elevation

This elevation shall be considered for checking pile scour for the Strength and Service Limit States. See BDM 6.6.4.1.3.1 and Aashto Lrfd 2.2, 2.6.4.4.2, 3.7.5, 10.5.5.3.2, and 11.7.2.3.

5.) Check Flood (500 year flood or Super Flood) Elevation

This elevation shall be considered for checking pile scour for the Strength and Service Limit States. See BDM 6.6.4.1.3.1 and Aashto Lrfd 2.2, 2.6.4.4.2, 3.7.5, 10.5.5.3.2, and 11.7.2.3.

Additional Notes:

- A sixth water elevation is included when a seal coat design is required for coffer dams. This water elevation is based on 25 year flood. See BDM 6.6.4.1.4.
- The 100 year flood is used to determine the need for venting of the superstructure. If venting of the superstructure is required then the designer shall also investigate a special extreme event design condition for the 500 year check flood (BDM 6.6.2.7). The load case will include both vertical and lateral loads on the pile.
- In some instances it may make sense to assume "No Water" rather than "Average Low Water" as a load case. Typically this may make sense when a stream bed is dry for part of the year. Using a "No Water" condition would remove buoyancy loading from the footing and the fill and thus produce a maximum axial load condition for the footing design.


Water Elevations for 1203 Jefferson

1.) Average Low Water Elevation

Average low water elevation is not listed on the Situation plan. The average stream bed elevation is listed as 664.11. So, 1' above that elevation is 665.11 which is the elevation of the Excavation Classification Line.

2.) Design High Water (50 year flood) Elevation

The design high water elevation is listed as 675.49. The Situation plan should typically list the average stream velocity for Q_{50} ; however, this plan does not so we will calculate it.



$$\text{Channel width} = (226.542' \text{ bridge length}) * (\cos(32 \text{ deg})) - (2) * (3' \text{ abut. Width}) - (2) * (3' \text{ berm width}) \\ = 180.119'$$

$$Q_{50} \text{ discharge} = 4308.4 \text{ cfs}$$

$$\text{Stream area} = (11.38') * (40.794') + (2.5 \text{ slope}) * (11.38') * (11.38') = 788 \text{ ft}^2$$

$$\text{Avg velocity} = (4308.4 \text{ cfs}) / (788 \text{ ft}^2) = 5.47 \text{ ft/s}$$

Note: The pier cross-sectional area may be ignored when determining average stream velocity.

Since the average stream velocity is greater than 5.0 ft/s, the pier will be designed for stream flow forces. The forces will be small since the average velocity is quite low and because the pier is aligned with the channel.

3.) Ice Elevation

The ice elevation is not listed on the Situation plan. This elevation may be assumed to be midway between Design High Water and Average Low Water which is $(0.5) * (675.49 + 665.11) = 670.30$. The drainage area for this bridge is only 3.75 square miles so ice loads may not be a concern according to BDM 6.6.1.1.2 and 6.6.2.9. However, this design will still consider ice load.

4.) Design Flood (100 year flood) Elevation

This elevation is given as 676.12 on the Situation plan. The calculated scour is 6.23'. This example will not consider the scour checks.

5.) Check Flood (500 year flood or Super Flood) Elevation

This elevation is not listed on the Situation plan. The policy for including this data was not yet in-place when this bridge was designed. This example will not consider the scour checks.

Notes: There is no indication that coffer dams are needed for this structure. The 100 year design flood elevation is well below the bottom of the prestressed beams. Stream and wind forces are assumed not to act below the top of the (exposed) footing.

Water Elevation Load Combinations

The load cases below are assumed to cover the force envelope needed for this particular design with respect to the loads considered below. Other pier designs may require additional load cases.

Strength/Service Load Combinations

Case 1 -- Maximum Axial Load

- Average low water
- Full soil cover / No scour
- No stream forces needed for average low water
- Bouyancy for average low water
- Wind on substructure above pier's soil cover (the soil cover at the pier is higher than the average low water elevation)

Case 2 -- Minimum Axial Load

- Design high water
- No soil cover / Full scour
- Stream forces based on design high water
- Bouyancy for design high water
- Wind on substructure above design high water

Extreme Event 2 Combination

Case 3 -- Must assume the soil is scoured away if ice forces are to be present on the pier

- Ice elevation
- No soil cover / Full scour
- Stream forces ignored since they will be minimal
- Bouyancy based on ice elevation
- Wind forces are not a part of Extreme Event 2

Summary of Elevations

- Footing thickness = 4'
- Top of footing elevation = 661.71'
- Bottom of footing elevation = 657.71'

- Average low water elevation = 665.11'
- Design high water elevation = 675.49'
- Ice elevation = 670.30'

Soil elevation = 671.71' (assumed 10' of cover on top of footing)

WA & IC Pier Forces

DOT refers to the Iowa Department of Transportation.
 OBS refers to the Iowa DOT Office of Bridges and Structures

Developed on 12/20/2006
 Last Modified on 8/26/2010

Forces calculated include stream flow, buoyancy and ice. These loads are for the cap and column design since the point of fixity is assumed to be at base of column.

Disclaimer: This software is intended for use by Iowa DOT personnel and consultants working for the OBS in their development of projects for the Iowa DOT. Any other use is at the sole discretion of the user. The Iowa DOT makes the software available "AS IS" and assumes no liability nor makes any warranty of any kind, including warranties of noninfringement, fitness or merchantability whether expressed or implied, to the accuracy or functionality of this software. By downloading or using this file, you are agreeing to this disclaimer.

The OBS will only support those persons using this software in connection with Iowa DOT related business.

Please report any spreadsheet errors to the Iowa DOT OBS.

This spreadsheet was developed to aid the design of typical Iowa DOT piers. The Iowa DOT Bridge Design Manual (BDM) should be consulted for the most up-to-date policies.

General Input Tab:

1.) The axes and direction of skew angle match the sign convention used in RC-Pier.

WA Force Tab:

- Stream flow pressure and buoyancy are considered.
- The TS&L should report the design high water and check flood events. The average low water may also be given on the TS&L.
- For piers nominally parallel with stream flow in streams with low average velocities, 0 to 5 ft/s, stream flow pressures may be neglected. However, if there is any skew between the pier and the stream flow, the designer shall determine the longitudinal and lateral pressures even if the average velocity is below 5 ft/s. Also, if the average velocity exceeds 5 ft/s then the designer shall determine the stream flow pressures.
- Normally the design highwater and average low water will be used for Strength and Service Limit States. The check flood events are limited to the Extreme Event Limit States. Foundation scour should be considered as appropriate.
- Stream flow forces on the superstructure are not considered in this spreadsheet, but they should be addressed if the possibility exists.
- A longitudinal drag coefficient, C_D , of 1.4 based on debris being present is assumed when computing stream pressures. However, the dimensions of the pier should be used in determining stream flow forces unless there is specific information about debris raft dimensions.
- Buoyancy forces should always be applied to the footing, soil, column, cap, and superstructure as is appropriate to the water level under consideration.

IC Force Tab:

- Only dynamic ice force effects are considered in this spreadsheet -- Aashto Lrfd 3.9.2.
- The effective ice crushing strength should be taken as 24.0 ksf per BDM 6.6.2.9. The design ice thickness is also given in the same section of the BDM.
- It is permissible to use the small stream reduction factor for stream widths less than 300' at mean water level. As a simplification, Iowa assumes stream width is equal to bridge length.
- Iowa does not typically slope the nose of T-Piers; thus the ice force is usually controlled by crushing rather than flexure.
- Normally the pier is aligned with the stream; however, provision is made in this spreadsheet to account for piers skewed to flow -- see Aashto Lrfd 3.9.2.4.2.

Loads WA and IC

WA = Water Loads IC = Ice Load

Pier View Direction (vVIEW), D or U	U	D is downstation, U is upstation
Skew (vSKW), RA is "+", LA is "-"	-32.000	deg

Note: **Blue text is for user input**
Red text is typ. calculated


Important Note: **Cap length, column width, and footing length should be taken along the skew (X axis).**

Cap Length, X (vCPL)	49.000	ft
Lgth of Non-Tapered Segment, X (vCPT)	20.500	ft
Cap Depth, Z (vCPD)	3.500	ft
Cap Min. Height, Y (vCPMN)	4.000	ft
Cap Max. Height, Y (vCPMX)	7.000	ft


Column Width, X (vCLW)	19.500	ft
Column Depth, Z (vCLD)	3.000	ft
Column Height, Y (vCLH)	25.000	ft

Footing Length, X (vFTL)	28.000	ft
Footing Width, Z (vFTW)	15.000	ft
Footing Depth, Y (vFTD)	4.000	ft


Column Extension to Fixity, Y (vFIX) **0.000** ft Typically 0'. This is only used to adjust start and end fractions (y_1 / L and y_2 / L) for loads.



Downstation Pier View



Upstation Pier View



WA Force (Stream Flow & Bouyancy)

Up to 4 cases may be evaluated.

Aashto Lrfd 3.7

	Case 1	Case 2	Case 3	Case 4	
Height of Water above Top of Footing	3.400	13.780	8.590	0.000	ft
Height of Soil above Top of Footing	10.000	0.000	0.000	0.000	ft

Do not enter negative values for heights of soil and water above top of footing.

Stream Flow

Longit. Drag Coefficients Aashto Lrfd Table 3.7.3.1-1



Pier Nose Type	C _D
Semi-circular nosed pier	0.70
Square-ended pier	1.40
Debris lodged against the pier	1.40
Wedge nose pier: nose ang. 90 deg. or less	0.80
Longitudinal Drag Coefficient Used, C _D	1.40

There is no Case 4.

BDM policy is to assume debris is present.

Lateral Drag Coefficients Aashto Lrfd Table 3.7.3.2-1

Stream Flow Angle θ	C _L
0 degrees	0.00
5 degrees	0.50
10 degrees	0.70
20 degrees	0.90
>= 30 degrees	1.00
Lateral Drag Coefficient Used, C _L	0.00



If stream velocity at the pier is 5 ft/sec. or less and CL = 0.00 then stream pressure can be ignored.

	Case 1	Case 2	Case 3	Case 4	
Average Stream Velocity, Vavg = Q / A	5.470	5.470	5.470	0.000	ft/sec.

The maximum pressure is double the average pressure and the pressure distribution to the pier is triangular with the maximum pressure at the highest elevation. (See Aashto Std Spec 3.18.1.1)

The Aashto Std. Spec. has a better description than the Lrfd Spec.

	Case 1	Case 2	Case 3	Case 4	
Longitudinal pressure (average)	0.0419	0.0419	0.0419	0.0000	ksf
Lateral pressure (average)	0.0000	0.0000	0.0000	0.0000	ksf

The "Lower" part of the pier cap is treated like an equivalent rectangle for the determination of stream loading. The total lateral pier cap stream load is averaged over the entire pier cap length. In RC-Pier, all pier cap stream loads are applied at the mid-height of the "Upper" part of the pier cap. The loads have not been adjusted to account for the change in point of application. The user must enter the appropriate sign into RC-Pier to account for the direction of stream flow. Note: Stream flow forces on the footing are not considered. Also, it is assumed that stream velocity and pressure at the top of the footing can not be greater than 0. The column start and end fractions have been adjusted for point of fixity (vFIX).

	Stream Loads on the Pier Cap					Stream Loads on the Column					
	Type of Load	Direction	Magnitude	Start Fraction x1 / L	End Fraction x2 / L	Type of Load	Direction	Start Mag. 1	Start Fraction y1 / L	End Mag. 2	End Fraction y2 / L
Case 1	Force (k)	X	0.000	0.500	-----	Trap (k/ft)	X	0.000	0.000	0.000	0.000
	UDL (k/ft)	Z	0.000	0.000	1.000	Trap (k/ft)	Z	0.000	0.000	0.000	0.000
Case 2	Force (k)	X	0.000	0.500	-----	Trap (k/ft)	X	0.000	0.000	0.251	0.459
	UDL (k/ft)	Z	0.000	0.000	1.000	Trap (k/ft)	Z	0.000	0.000	0.000	0.459
Case 3	Force (k)	X	0.000	0.500	-----	Trap (k/ft)	X	0.000	0.000	0.251	0.286
	UDL (k/ft)	Z	0.000	0.000	1.000	Trap (k/ft)	Z	0.000	0.000	0.000	0.286
Case 4	Force (k)	X	0.000	0.500	-----	Trap (k/ft)	X	0.000	0.000	0.000	0.000
	UDL (k/ft)	Z	0.000	0.000	1.000	Trap (k/ft)	Z	0.000	0.000	0.000	0.000

Fill elev. is higher than water elev. so there are no stream forces for Case 1.

As stated earlier, stream flow forces for Case 3 will be ignored.

Bouyancy

Specific Weight of Water	0.0624	kcf
--------------------------	--------	-----

In RC-Pier, all pier cap bouyancy loads are applied at the mid-height of the "Upper" part of the pier cap. For calculating soil bouyancy the column is assumed to extend infinitely upwards and is, therefore, deducted from the soil volume (the cap is ignored). Soil is assumed to be 1/3 void. The column start and end fractions have been adjusted for point of fixity (vFIX).

	Bouyancy on the Pier Cap					Bouyancy on the Column					Bouyancy on the Soil			
	Type of Load	Direction	Magnitude	Start Fraction x1 / L	End Fraction x2 / L	Type of Load	Direction	Magnitude	Start Fraction y1 / L	End Fraction y2 / L	Total Col. Bouyant Force (k)	Type of Load	Direction	Magnitude
Case 1	Force (k)	Y	0.000	0.500	-----	UDL (k/ft)	Y	3.650	0.000	0.113	12.411	Force (k)	Y	51.131
Case 2	Force (k)	Y	0.000	0.500	-----	UDL (k/ft)	Y	3.650	0.000	0.459	50.303	Force (k)	Y	0.000
Case 3	Force (k)	Y	0.000	0.500	-----	UDL (k/ft)	Y	3.650	0.000	0.286	31.357	Force (k)	Y	0.000
Case 4	Force (k)	Y	0.000	0.500	-----	UDL (k/ft)	Y	3.650	0.000	0.000	0.000	Force (k)	Y	0.000

Bouyancy on the Footing		
Type of Load	Direction	Magnitude
Force (k)	Y	104.832

Footing is assumed to be entirely immersed.

IC Force (Ice)

Aashto Lrfd 3.9

Height of Ice Force above Top of Footing	8.590	ft	Typically, halfway between design high water and average low water. The ice force is assumed to act on the column not on the cap.
--	-------	----	---

Effective Ice Strength, p Aashto Lrfd 3.9.2.1

Description	p	
Breakup at melt. temp., ice structure is substantially disintegrated	8.00	ksf
Breakup at melt. temp., ice structure is somewhat disintegrated	16.00	ksf
Breakup or major ice movement at melt. temp.; large sound ice movements	24.00	ksf
Breakup or major ice movement when avg. ice temp. is below melt. temp.	32.00	ksf
Effective Ice Strength Used, p	24.00	ksf

BDM Policy is to use 24 ksf for typical bridges.

Ice Thickness, t

District	t	
5	1.2500	ft
1, 4, 6	1.4167	ft
2, 3	1.5833	ft
Ice Thickness Used, t	1.2500	ft

BDM 6.6.2.9

Stream Width (equal to bridge length)	223.000	ft
Longest Adjacent Span Length	91.500	ft

Red'n Factor K_i for Small Streams Aashto Lrfd Table C3.9.2.3-1

A/r^2	K_i
1000	1.00
500	0.90
200	0.70
100	0.60
50	0.50
Calculated A/r^2	1298.87
Calculated K_i	1.000

If the stream width (i.e. bridge length) exceeds 300' then $K_i = 1.00$.

Parallel Ice Flow

Aashto Lrfd 3.9.2.4.1

Crushing Coefficient, C_a	1.756
-----------------------------	-------

Inclination of Pier Nose from Vertical, α	0.000	deg	Iowa does not typically slope the nose of T-Piers.
--	-------	-----	--

Flexure Coefficient, C_n	N/A
----------------------------	-----

Horizontal Crushing Ice Force, F_c	158.035	k
Horizontal Flexure Ice Force, F_b	N/A	k
Long. Ice Force Used, F	158.035	k

F_b is not applicable if $\alpha \leq 15$ or pier width to ice thickness > 6 .
Use the minimum of crushing or flexure.

The user must enter the appropriate sign into RC-Pier to account for the direction of stream flow. The column start and end fractions have been adjusted for point of fixity (vFIX).

Note: According to Aashto Lrfd 3.9.2.4.1 both the longitudinal and transverse ice forces shall be assumed to act at the nose of the pier. This implies that the user should enter a torque loading, M_y , about the column's vertical axis. Office practice does not address this effect for typical bridges.

Ice Loads on the Pier Column - Case 1				
Type of Load	Direction	Magnitude	Start Fraction y_1/L	End Fraction y_2/L
Force (k)	X	158.035	0.286	-----
Force (k)	Z	23.705	0.286	-----

Use full longitudinal value.
Transverse is 15% of longitudinal.

Pier Nose Angle in a Horizontal Plane	100.000	deg	Use 100 degrees for rounded pier nose.
Friction Angle bt. Ice and Pier Nose	6.000	deg	Assume 6 degrees -- see BDM 6.6.2.9.

Ice Loads on the Pier Column - Case 2				
Type of Load	Direction	Magnitude	Start Fraction y_1/L	End Fraction y_2/L
Force (k)	X	79.017	0.286	-----
Force (k)	Z	53.298	0.286	-----

Use 50% of full longitudinal value.
Percent of longitudinal based on nose and friction angles.

Skewed Ice Flow

Aashto Lrfd 3.9.2.4.2

The assumption here is that the ice will fail by crushing since we are using a projected area that is not likely to have an inclination angle.

Skew Angle between Ice Floe and Pier	0.000	deg	If the skew angle is 0 degrees then these forces are not applicable.
--------------------------------------	-------	-----	--

Projected Column Face	3.000	ft
Crushing Coefficient, C_a	1.756	

Horizontal Crushing Ice Force, F_c	158.035	k	This force will be resolved into components along the X and Z axes. The transverse force (Z-axis) must be at least 20% of the total.
--------------------------------------	---------	---	--

The user must enter the appropriate sign into RC-Pier to account for the direction of stream flow. The column start and end fractions have been adjusted for point of fixity (vFIX).

Ice Loads on the Pier Column				
Type of Load	Direction	Magnitude	Start Fraction y_1/L	End Fraction y_2/L
Force (k)	X	158.035	0.286	-----
Force (k)	Z	31.607	0.286	-----

Skewed ice flow is not applicable.

Stream Force Calculations for Case 2

Sample Calculations

$V_{avg} = 5.47 \text{ ft/s}$

Drag Coefficients: Longitudinal, $C_D = 1.40$
 Lateral, $C_L = 0.00$

Office policy is to assume debris is present.
 There is no skew between pier and stream flow.

Avg Longitudinal Pressure = $[(C_D) \cdot (V_{avg})^2] / 1000 = [(1.40) \cdot (5.47 \text{ ft/s})^2] / 1000 = 0.0419 \text{ ksf}$

Avg Lateral Pressure = $[(C_L) \cdot (V_{avg})^2] / 1000 = [(0.00) \cdot (5.47 \text{ ft/s})^2] / 1000 = 0.00 \text{ ksf}$

Max Longitudinal Pressure = $(2) \cdot (0.0419 \text{ ksf}) = 0.0838 \text{ ksf}$

Max Lateral Pressure = $(2) \cdot (0.00 \text{ ksf}) = 0.00 \text{ ksf}$

Column Depth (Z-axis) = 3.00'



Equivalent Column Width (X-axis) = 19.50'

Height of Water = 13.78' above top of footing

Stream Force on Column

Longitudinal = $(0.0838 \text{ ksf}) \cdot (3') = 0.2514 \text{ k/ft}$

Lateral = $(0.00 \text{ ksf}) \cdot (19.5') = 0.00 \text{ k/ft}$



Note: Dashed line indicates structural model.

For Column and Cap Design:

Start Fraction = $(0.00') / (30.00') = 0.00$

End Fraction = $(13.78') / (30.00') = 0.4593$

For Footing Design: The point of fixity will move to the bottom of the footing.

Start Fraction = $(4.00') / (34.00') = 0.1176$

End Fraction = $(17.78') / (34.00') = 0.5229$

Bouyancy Calculations for Case 2

Sample Calculations

Total Column Bouyancy Force = $(13.78') \cdot (19.50') \cdot (3.00') \cdot (0.0624 \text{ kcf}) = 50.303 \text{ k up}$

The column bouyancy is typically applied as a distributed vertical load.

Column Bouyancy Force per foot = $(19.50') \cdot (3.00') \cdot (0.0624 \text{ kcf}) = 3.650 \text{ k up}$

For Column and Cap Design:

Start Fraction = $(0.00') / (30.00') = 0.00$

End Fraction = $(13.78') / (30.00') = 0.4593$


For Footing Design: The point of fixity will move to the bottom of the footing.

Start Fraction = $(4.00') / (34.00') = 0.1176$

End Fraction = $(17.78') / (34.00') = 0.5229$

Footing Bouyancy Force = $(4.00') \cdot (28.00') \cdot (15.00') \cdot (0.0624 \text{ kcf}) = 104.832 \text{ k up}$

Note: The soil is assumed to have been scoured away for the Case 2 condition.



Ice Load Calculations for Case 3

Sample Calculations

Ice elevation = 8.590' above top of footing

Effective ice strength, $p = 24.00$ ksf Office policy

Ice thickness, $t = 1.25'$

Jefferson County is in District 5

Stream width = 223.00'

Office policy is to set stream width equal to bridge length

Longest adjacent span length = 91.50'

Column width, $w = 3.00'$

Small Stream Reduction Factor, K_1 , Aashto Lrfd 3.9.2.3

Stream width = 223.00' < 300.00' so reduction factor may be considered

Plan area of largest ice floe, $A = (\pi) * [(2/3) * (0.5) * (91.5')]^2 = 2922.5 \text{ ft}^2$

Radius of pier nose = 1.50'

$A/r^2 = (2922.5 \text{ ft}^2) / [(1.50')^2] = 1298.9 > 1000$ so $K_1 = 1.00$ No small stream reduction factor

Crushing or Flexing Ice Force, Aashto Lrfd 3.9.2.2

$w/t = 3.00' / 1.25' = 2.40 \leq 6.0$ which means the ice force, F , should be the lesser of the crushing force, F_c , or the flexing force, F_b

$F_c = (C_a) * (p) * (t) * (w)$ where $C_a = (5t/w + 1)^{0.5}$

$F_b = (C_n) * (p) * (t^2)$ where $C_n = 0.5 / (\tan(\alpha - 15))$

The flexing force, F_b , is not applicable since the nose of the T-Pier is not inclined.

$C_a = [((5) * (1.25')) / (3.00') + 1]^{0.5} = 1.756$

$F_c = (1.756) * (24.00 \text{ ksf}) * (1.25') * (3.00') = 158.035 \text{ k}$

$F = F_c = 158.035 \text{ k}$

Ice Forces for Piers Parallel to Flow, Aashto Lrfd 3.9.2.4.1

a.) A longitudinal force equal to F shall be combined with a transverse force of $0.15 * F$

$F_x = F = 158.035 \text{ k}$

$F_z = 0.15 * F = (0.15) * (158.035 \text{ k}) = 23.705 \text{ k}$

b.) A longitudinal force of $0.5 * F$ shall be combined with a transverse force of F_t

$F_x = 0.5 * F = (0.5) * (158.035 \text{ k}) = 79.017 \text{ k}$

$F_z = F_t = F / [2 * \tan(\beta/2 + \theta_f)] = (158.035 \text{ k}) / [(2) * (\tan((0.5) * (100 \text{ deg}) + (6 \text{ deg})))]] = 53.298 \text{ k}$

Note: The F_z ice forces may act in both directions.

For Column and Cap Design:

Point of Column Application = $(8.59') / (30.00') = 0.2863$

For Footing Design: The point of fixity will move to the bottom of the footing.

Point of Column Application = $(12.59') / (34.00') = 0.3703$

Wind Load Cases

Simplified wind loading will be used. This is also referred to as wind on usual slab and girder bridges in Aashto Lrfd 3.8. Iowa has extended the applicability of this Lrfd code provision to cover more cases – see BDM 6.6.2.8.

There are essentially 3 different wind load cases on the substructure due to the various water and fill elevations. The different cases only affect the application of the wind load to the T-pier, not its magnitude.

Case 1: Average Low Water Elevation

Average low water elevation = 665.11'

Soil elevation = 671.71' (assumed 10' of cover on top of footing)

Case 2: Design High Water (50 year flood) Elevation

Design high water elevation = 675.49'

Case 3: Ice Elevation

Ice elevation = 670.30'

The footing elevations are:

Footing thickness = 4'

Top of footing elevation = 661.71'

Bottom of footing elevation = 657.71'

LRFD Simplified Wind Loading for Usual Girder Bridges

DOT refers to the Iowa Department of Transportation.

OBS refers to the Iowa DOT Office of Bridges and Structures

Developed on 12/20/2005

Last Modified on 8/26/2010

Disclaimer: This software is intended for use by Iowa DOT personnel and consultants working for the OBS in their development of projects for the Iowa DOT. Any other use is at the sole discretion of the user. The Iowa DOT makes the software available "AS IS" and assumes no liability nor makes any warranty of any kind, including warranties of noninfringement, fitness or merchantability whether expressed or implied, to the accuracy or functionality of this software. By downloading or using this file, you are agreeing to this disclaimer.

The OBS will only support those persons using this software in connection with Iowa DOT related business.

Please report any spreadsheet errors to the Iowa DOT OBS.

This spreadsheet was developed to aid the design of typical Iowa DOT piers. The Iowa DOT Bridge Design Manual (BDM) should be consulted for the most up-to-date policies.

Description:

This spreadsheet is designed to generate the wind loads used as input into RC-Pier. Specifically, it generates the wind loads for the simplified wind loading case. The definition of "usual girder bridge" in AASHTO Lrfd 3.8.1.2.2 and 3.8.1.3 has been modified by the Iowa DOT in order to extend the range of applicability. The individual span length has been extended from 125' to 160' in order to allow this loading to be used for the BTE155s. The maximum height of 30' above low ground or water level has been increased to 100'.

RC-Pier Import Feature:

The loads generated by this spreadsheet can be exported to a text file that can be imported directly into RC-Pier.

General Input Tab:

- 1.) The axes and direction of skew angle match the sign convention used in RC-Pier.
- 2.) Axes may be based on Downstation or Upstation Pier View.
- 3.) The spreadsheet can handle up to 10 beam lines. The beam spacings can be constant or variable.
- 4.) Slab and beam dimensions should be entered perpendicular to the centerline of the roadway. Do not enter them along the skew of the pier.
- 5.) RC-Pier does not have an option to enter haunch thickness, bearing device thickness, or average step height on its Superstructure Parameters screen. This means the auto-generated loads for W and WL will not be based on these additional dimensions.
- 6.) The spreadsheet can handle up to 5 columns. The column spacing input is not required.




W Force Tab:

- 1.) If the top of barrier rail is less than or equal to 100' above the ground or water surface then office practice is to use the simplified wind pressure values from Aashto Lrfd 3.8.1.2.2. If the top of barrier rail is above the 100' mark then the user should adjust the wind pressures upward.
- 2.) If the top of the pier cap is less than or equal to 100' above the ground or water surface then office practice is to use a 0.040 ksf wind pressure (Aashto Lrfd 3.8.1.2.3) in both orthogonal directions at the same time. If the top of the pier cap is above the 100' mark then the user should adjust the wind pressure upward.
- 3.) Currently RC-Pier's auto-generate feature for WS loads does not handle uplift forces correctly when they are reversible, nor does it restrict uplift to Strength 3 loading. Aashto Lrfd 3.8.2 also restricts vertical wind pressure to a 0 degree wind skew angle. Uplift will be used in conjunction with Strength 3 loading and the simplified wind loading. Typical piers should use a set of wind load cases both with and without uplift.

WL Force Tab:

- 1.) This spreadsheet uses the wind pressure values from Aashto Lrfd 3.8.1.3. The user may adjust these pressures.

Definitions



General Input

Note:	Blue text is for user input
	Red text is typ. calculated

Pier View Direction (vVIEW), D or U	U		D is downstation, U is upstation
Skew (vSKW), RA is "+" LA is "-"	-32.000	deg	

Important Note:	Roadway dimensions and beam spacing should be taken as perpendicular to roadway.
-----------------	---

Out to Out Slab Width (vOOS)	43.160	ft
Roadway Width (vRW)	40.000	ft
Left Curb Width (vLCW)	1.580	ft

Barrier Rail Height (vBRH)	34.000	in	
Slab Thickness (vST)	8.000	in	
Haunch Thickness (vHT)	0.000	in	#
Beam Height (vBH)	54.000	in	
Bearing Device Thickness (vBDT)	0.000	in	#
Average Step Height (vASH)	0.000	in	#

RC-Pier does not provide the option to enter these dimensions, so you may want to set them to 0.

Number of Beams (vNB)	6	
Left Slab Edge to Beam 1 (vBM01)	3.080	ft
Beam 1 to Beam 2 (vBM12)	7.400	ft
Beam 2 to Beam 3 (vBM23)	7.400	ft
Beam 3 to Beam 4 (vBM34)	7.400	ft
Beam 4 to Beam 5 (vBM45)	7.400	ft
Beam 5 to Beam 6 (vBM56)	7.400	ft
Beam 6 to Beam 7 (vBM67)		ft
Beam 7 to Beam 8 (vBM78)		ft
Beam 8 to Beam 9 (vBM89)		ft
Beam 9 to Beam 10 (vBM910)		ft
Last Beam to Right Slab Edge	3.080	ft
Tot. Distance bet. Ext. Beams (vTBD)	37.000	ft

Important Note:	Cap length and column spacing should be taken along the skew (X axis).
-----------------	---

Cap Length (vCPL)	49.000	ft
Length of Non-Tapered Segment (vCPT)	20.500	ft
Cap Min. Height (vCPMN)	48.000	in
Cap Max. Height (vCPMX)	84.000	in
Cap Depth (vCPD)	42.000	in

It is assumed to be centered.

Column Width or Diameter (vCLW)	234.000	in
Col. Depth - enter 0 for round col. (vCLD)	36.000	in
Col. Height (vCLH)	25.000	ft

Bottom of column to bottom of cap.

Number of Columns (vNC)	1	
Left Cap Edge to Col. 1 (vCL01)	24.500	ft
Col. 1 to Col. 2 (vCL12)		ft
Col. 2 to Col. 3 (vCL23)		ft
Col. 3 to Col. 4 (vCL34)		ft
Col. 4 to Col. 5 (vCL45)		ft
Last Column to Right Cap Edge	24.500	ft

Distribution of W to Pier

Aashto Lrfd 3.8

Case 1 is input into the spreadsheet.

V ₃₀ , wind velocity at 30' height	80.000	mph
V _B , base wind velocity of 100 mph at 30' hgt	100.000	mph
Enter Upstream Surface Condition (1 to 4)	1	
V _o , friction velocity	8.200	mph
Z _o , friction length of upstream fetch	0.23	ft
Hgt above col. base to ground / water surf.	10.000	ft

Office policy is to use V₃₀ = 80 mph

Office policy is to use Open Country

This height is used to establish Z and is also used in determining the exposed column area for wind loading. RC-Pier always bases Z on the bottom of the column.

Aashto Lrfd Table 3.8.1.1-1

Upstream Surface Condition	Open Country 1	Suburban 2	City 3	User Option 4
V _o (mph)	8.20	10.90	12.00	0.00
Z _o (ft)	0.23	3.28	8.20	0.00

Aashto Lrfd Eqn 3.8.1.1-1 and 3.8.1.2.1-1

$$V_{DZ} = 2.5 * V_o * (V_{30} / V_B) * \ln(Z / Z_o) \rightarrow \text{where } V_{DZ} \text{ is the wind design velocity at elevation Z}$$

$$P_D = P_B * (V_{DZ} / V_B)^2 \rightarrow \text{where } P_B \text{ is the base wind pressure}$$

Superstructure Wind

Calc. Z (top of curb to ground/water surf.)	30.000	ft
User's Z	100.000	ft
V _{DZ} , calculated design velocity at User's Z	99.627	mph
User's V _{DZ}	100.000	mph

Aashto Lrfd 3.8.1.2.2

Skew Angle of Wind	Simplified Superstr. Wind Press. for Girders	
	Lateral	Longit.
Degrees	ksf	ksf
N/A	0.050	0.012

Based on User's Factor

Adjusted Simplified Superstr. Wind Press. for Girders	
Lateral	Longit.
ksf	ksf
0.050	0.012

Calc. Wind Press. Factor due to User's V _{DZ}	1.000
User's Factor	1.000

See Aashto Lrfd Eqn 3.8.1.2.1-1

Office practice is to use the simplified wind pressures given in Aashto Lrfd 3.8.1.2.2 when individual span lengths are 160' or less and when Z is 100' or less. In other words, the Factor will typically be 1.000. **Do not use a Factor less than 1.000.** Minimum wind pressures should be 0.050 ksf lateral and 0.012 ksf longitudinal.

Above 100' pressures are to be adjusted based on V₃₀ = 80 mph for individual span lengths less than 160'. In other words, the Factor will be greater than 1.000.

RC-Pier's auto-generate feature uses adjusted wind pressures if Z is greater than 30' and if the adjusted pressures are higher than those in Aashto Lrfd Table 3.8.1.2.2-1.

The user needs to ensure that the transverse wind loading requirement of 0.300 kif in Aashto Lrfd 3.8.1.2.1 is met. If the superstructure height (includes rail) is greater than 6.00' then this requirement is met because (0.050ksf)*(6) = 0.300 kif.

Enter positive wind pressures to be used on the superstructure below.

User's Lateral Spstr. Wind Pressure	0.050	ksf
User's Longit. Spstr. Wind Pressure	0.012	ksf

According to Aashto the vertical wind pressure or uplift force should only be applied when the wind skew angle is 0 degrees. Also, it should only be included in W combinations which do not involve WL (ie. Strength 3). See Aashto Lrfd 3.8.2. Office practice is to apply uplift in the Strength 3 combination for simplified wind loading. Vertical wind pressure is not to be adjusted for height or velocity.


Vertical Wind Pressure	0.020	ksf
Average Span Length	81.125	ft

Uplift Moment Arm	Past in-house pier programs based moment arm on length along pier cap which will be greater for skewed bridges. RC-Pier uses perpendicular distance.
Enter 1 for In-House	
Enter 2 for RC-Pier	
2	


The overturning moment, M_z, is transferred to the pier by equal and opposite F_y forces acting through the beams. RC-Pier assumes that only the exterior beams are involved. User can involve all beams if desired.

How is M _z Transferred to the Pier?	
Enter 1 if by Exterior Beams Only	
Enter 2 if All Beams Participate	
1	

Downstation Pier View



Upstation Pier View



Wind forces with and without uplift will conservatively be applied to all loading combinations. This is in lieu of doing separate RC-Pier runs in order to keep the proper wind loading with the proper load combinations.

The results shown in the tables below are split into 4 groups based on combinations of the \pm wind force and \pm wind angle. In RC-Pier the user can vary the wind angle magnitude and sign. The wind force direction is typically varied automatically because the load, by default, is treated as a reversible load. In RC-Pier the vertical wind load, if used, is reversed as well which is undesirable. This spreadsheet always assumes vertical wind acts upward.

Wind Uplift Not Included

Beam #	W Loads to the Pier (kips)																							
	+ Wind Force, + Wind Angle			+ Wind Force, - Wind Angle			- Wind Force, + Wind Angle			- Wind Force, - Wind Angle														
	Fx	Fy	Fz	Fx	Fy	Fz	Fx	Fy	Fz	Fx	Fy	Fz												
1	-3.899	-2.145	3.967	-5.274	-2.901	1.765	3.899	2.145	-3.967	5.274	2.901	-1.765												
2	-3.899	0.000	3.967	-5.274	0.000	1.765	3.899	0.000	-3.967	5.274	0.000	-1.765												
3	-3.899	0.000	3.967	-5.274	0.000	1.765	3.899	0.000	-3.967	5.274	0.000	-1.765												
4	-3.899	0.000	3.967	-5.274	0.000	1.765	3.899	0.000	-3.967	5.274	0.000	-1.765												
5	-3.899	0.000	3.967	-5.274	0.000	1.765	3.899	0.000	-3.967	5.274	0.000	-1.765												
6	-3.899	2.145	3.967	-5.274	2.901	1.765	3.899	-2.145	-3.967	5.274	-2.901	-1.765												
7																								
8																								
9																								
10																								
	Mx (k*ft)			95.202			Mx (k*ft)			42.365			Mx (k*ft)			-95.202			Mx (k*ft)			-42.365		

Bridge office practice is to set the overturning moment Mx to 0.00. Currently, RC-Pier does not calculate an Mx for W, however, Leap's plans are to include it in a future version (probably as an option).

Wind Uplift Included

Beam #	W Loads to the Pier (kips)																							
	+ Wind Force, + Wind Angle			+ Wind Force, - Wind Angle			- Wind Force, + Wind Angle			- Wind Force, - Wind Angle														
	Fx	Fy	Fz	Fx	Fy	Fz	Fx	Fy	Fz	Fx	Fy	Fz												
1	-3.899	-7.792	3.967	-5.274	-8.549	1.765	3.899	31.134	-3.967	5.274	31.891	-1.765												
2	-3.899	11.671	3.967	-5.274	11.671	1.765	3.899	11.671	-3.967	5.274	11.671	-1.765												
3	-3.899	11.671	3.967	-5.274	11.671	1.765	3.899	11.671	-3.967	5.274	11.671	-1.765												
4	-3.899	11.671	3.967	-5.274	11.671	1.765	3.899	11.671	-3.967	5.274	11.671	-1.765												
5	-3.899	11.671	3.967	-5.274	11.671	1.765	3.899	11.671	-3.967	5.274	11.671	-1.765												
6	-3.899	31.134	3.967	-5.274	31.891	1.765	3.899	-7.792	-3.967	5.274	-8.549	-1.765												
7																								
8																								
9																								
10																								
	Mx (k*ft)			95.202			Mx (k*ft)			42.365			Mx (k*ft)			-95.202			Mx (k*ft)			-42.365		

Bridge office practice is to set the overturning moment Mx to 0.00. Currently, RC-Pier does not calculate an Mx for W, however, Leap's plans are to include it in a future version (probably as an option).



Substructure Wind

Calc. Z (pier cap top to ground/water surf.)	22.000	ft
User's Z	100.000	ft

V _{DZ} , calculated design velocity at User's Z	99.627	mph
User's V _{DZ}	100.000	mph

Calc. Wind Press. Factor due to User's V _{DZ}	1.000	See Aashto Lrfd Eqn 3.8.1.2.1-1
User's Factor	1.000	

Office practice is to use simplified wind pressures for substructure when individual span lengths are 160' or less and when Z is 100' or less. In other words, the Factor will typically be 1.000. Do not use a Factor less than 1.000. Minimum wind pressures should be 0.040 ksf parallel (X dir.) and 0.040 ksf perpendicular (Z dir.) to the pier. This loading is unique to Iowa and cannot be found in the Aashto Specifications.

Above 100' pressures are to be adjusted based on V₃₀ = 80 mph for individual span lengths less than 160'. In other words, the Factor will be greater than 1.000.

RC_Pier will only use the adjusted wind pressures if Z is greater than 30' and if the adjusted pressures are higher 0.040 ksf (see Aashto Lrfd 3.8.1.2.3).

Enter positive wind pressures to be used on the substructure below.

User's Parallel Wind Press. (X dir.)	0.040	ksf
User's Perpendicular Wind Press. (Z dir.)	0.040	ksf

Aashto Lrfd 3.8.1.2.3

Skew Angle of Wind	Simplified Substr. Wind Press. for Piers	
	Parallel	Perpend.
Degrees	ksf	ksf
N/A	0.040	0.040

Based on User's Factor

Adjusted Simplified Substr. Wind Press. for Piers	
Parallel	Perpend.
ksf	ksf
0.040	0.040

Export Super- and Sub-structure Wind Loads to Text Files

Cap Loads								
Exposed Pier Cap Area (ft ²)	Type of Load	Direction	+ WF + WA Magnitude	+ WF - WA Magnitude	- WF + WA Magnitude	- WF - WA Magnitude	Start Fraction x1 / L	End Fraction x2 / L
24.500	Force (k)	X	-0.980	-0.980	0.980	0.980	0.500	-----
300.250	UDL (k/ft)	Z	0.245	0.245	-0.245	-0.245	0.000	1.000

The sign of the substr. wind loads depends on the sign of the superstr. wind loads.

Note: UDL stands for uniformly distributed load. The total load in the Z direction is averaged over the length of the pier cap.

Column Loads (apply loads to all columns in pier)								
Exposed Pier Col. Area (ft ²)	Type of Load	Direction	+ WF + WA Magnitude	+ WF - WA Magnitude	- WF + WA Magnitude	- WF - WA Magnitude	Start Fraction y1 / L	End Fraction y2 / L
45.000	UDL (k/ft)	X	-0.120	-0.120	0.120	0.120	0.333	0.833
292.500	UDL (k/ft)	Z	0.780	0.780	-0.780	-0.780	0.333	0.833

The sign of the substr. wind loads depends on the sign of the superstr. wind loads.

Note: UDL stands for uniformly distributed load. The start and end fractions are based on a column height that extends to the middle of the minimum cap height.

Wind on Live Load

Aashto Lrfd 3.8.1.3

Height of WL above Top of Slab **6.000** ft Typically, WL is assumed to act 6' above the top of the slab.

Enter positive wind loads to be used on the superstructure below.
 User's Normal WL **0.100** kif
 User's Parallel WL **0.040** kif

WL is not varied based on elevation or wind speed.


Aashto Lrfd 3.8.1.3

Skew Angle of Wind	Simplified Wind Components on Live Load	
	Normal	Parallel
Degrees	kif	kif
N/A	0.100	0.040

Average Span Length **81.125** ft

The overturning moment, M_z , is transferred to the pier by equal and opposite F_y forces acting through the beams. RC-Pier assumes that only the ext. beams are involved. User can involve all beams if desired.

How is M_z Transferred to the Pier?
 Enter 1 if by Exterior Beams Only
 Enter 2 if All Beams Participate **1**



The results shown in the tables below are split into 4 groups based on combinations of the \pm wind force and \pm wind angle. In RC-Pier the user can vary the wind angle magnitude and sign. The wind force direction is typically varied automatically because the load, by default, is treated as a reversible load.

For Strength 5 and Service 1 Loading

Beam #	WL Loads to the Pier (kips)											
	+ Wind Force, + Wind Angle			+ Wind Force, - Wind Angle			- Wind Force, + Wind Angle			- Wind Force, - Wind Angle		
	Fx	Fy	Fz	Fx	Fy	Fz	Fx	Fy	Fz	Fx	Fy	Fz
1	-0.860	-1.321	1.175	-1.433	-2.201	0.258	0.860	1.321	-1.175	1.433	2.201	-0.258
2	-0.860	0.000	1.175	-1.433	0.000	0.258	0.860	0.000	-1.175	1.433	0.000	-0.258
3	-0.860	0.000	1.175	-1.433	0.000	0.258	0.860	0.000	-1.175	1.433	0.000	-0.258
4	-0.860	0.000	1.175	-1.433	0.000	0.258	0.860	0.000	-1.175	1.433	0.000	-0.258
5	-0.860	0.000	1.175	-1.433	0.000	0.258	0.860	0.000	-1.175	1.433	0.000	-0.258
6	-0.860	1.321	1.175	-1.433	2.201	0.258	0.860	-1.321	-1.175	1.433	-2.201	-0.258
7												
8												
9												
10												
			78.735			17.275			-78.735			-17.275

Bridge office practice is to set the overturning moment M_x to 0.00. Currently, RC-Pier does not calculate an M_x for WL, however, Leap's plans are to include it in a future version (probably as an option).

These loads will have to be used twice in RC-Pier. WL is dependent on WS and WS is applied with and without uplift.

Wind on Superstructure Sample Calculations

Uplift = 20 psf
 Lateral Pressure = 50 psf
 Longitudinal Pressure = 12 psf

Superstructure Wind Area

SBC Height	34"
Slab Thickness	8"
<u>Beam Height</u>	<u>54"</u>
Total	96" = 8.00'

Average Span Length = $(0.5)*(70.75' + 91.5') = 81.125'$

$F_{x'} = (-0.050 \text{ ksf})*(8')*(81.125') = -32.450 \text{ k}$


$F_{z'} = (0.012 \text{ ksf})*(8')*(81.125') = 7.788 \text{ k}$

$F_x = (-32.450 \text{ k})*(\cos(32 \text{ deg})) + (7.788 \text{ k})*(\sin(32 \text{ deg})) = -23.392 \text{ k}$

$F_z = (32.450 \text{ k})*(\sin(32 \text{ deg})) + (7.788 \text{ k})*(\cos(32 \text{ deg})) = 23.800 \text{ k}$

$F_x \text{ per beam} = (-23.392 \text{ k})/(6 \text{ Beams}) = -3.899 \text{ k}$

$F_z \text{ per beam} = (23.800 \text{ k})/(6 \text{ Beams}) = 3.967 \text{ k}$



Assigning the sign to the results is done by observation.

Uplift = $(0.02 \text{ ksf})*(43.16)*(81.125') = 70.027 \text{ k}$

$F_y \text{ for Beams 2-5} = (70.027 \text{ k})/(6 \text{ Beams}) = 11.671 \text{ k}$

$M_z = (23.392 \text{ k})*(0.5)*(8') + (70.027 \text{ k})*(0.25)*(43.16') = 849.160 \text{ k*ft}$


$F_y \text{ for Beams 1 and 6} = \pm(849.160 \text{ k*ft})/[(5 \text{ Beam Spa})*(7.4')/(\cos(32 \text{ deg}))] + 11.671 \text{ k}$



Beam 1, $F_y = -7.792 \text{ k}$

Beam 6, $F_y = 31.134 \text{ k}$

$M_x = (23.800 \text{ k})*(0.5)*(8') = 95.200 \text{ k*ft}$

← Office Policy is to ignore





The signs for simplified substructure wind loads are made to correspond with the sign for the superstructure wind loads.

$$A_{cap_x} = (7')*(3.5') = 24.5 \text{ ft}^2$$

$$A_{cap_z} = (49')*(7') - (3')*(14.25') = 300.25 \text{ ft}^2$$

$$A_{col_x} = (3')*(25' - 10' \text{ fill}) = 45 \text{ ft}^2 \text{ per column (exposed)}$$

$$A_{col_z} = (19.5')*(25' - 10' \text{ fill}) = 292.5 \text{ ft}^2 \text{ per column (exposed)}$$

$$F_{cap_x} = (0.04 \text{ ksf})*(24.5 \text{ ft}^2) = -0.98 \text{ k}$$

$$F_{cap_z} = (0.04 \text{ ksf})*(300.25 \text{ ft}^2) = 12.01 \text{ k}$$

Signs based on 1st case sign convention for superstructure wind loads.

$$F_{col_x} = (0.04 \text{ ksf})*(45 \text{ ft}^2) = -1.80 \text{ k}$$

$$F_{col_z} = (0.04 \text{ ksf})*(292.5 \text{ ft}^2) = 11.70 \text{ k}$$

Cap Loads

$$F_x = -0.98 \text{ k} \text{ applied at midpoint of cap}$$

$$UDL_z = (12.01 \text{ k})/(49') = 0.245 \text{ klf} \text{ applied along cap length}$$

Column Load

$$UDL_x = (-1.80 \text{ k})/(15') = -0.120 \text{ klf} \text{ from } (10')/(30') = 0.333$$

$$UDL_z = (11.70 \text{ k})/(15') = 0.780 \text{ klf} \text{ to } (25')/(30') = 0.833$$



Loads are applied to each column.

Note: The start and end fractions will change for the wind loadings on the column for the footing design because the column is extended 4.00'. The fractions are:



$$\text{Start Fraction} = (10' + 4')/(30' + 4') = 0.412$$



$$\text{End Fraction} = (25' + 4')/(30' + 4') = 0.853$$

Cap and Column Design



Click OK when this warning appears.





Currently it is easier to use the "Multi Columns" option to design T-piers rather than the "Hammer head" option. The "Hammer head" option requires the cap and column to be the same width.

The T-pier column shape will be modeled as an equivalent rectangle.

Typical T-piers will use the tapered cap shape.

I recommend using the "Upstation" pier view option.

Superstructure Parameters

Number of Lanes:

Beam Height: in

Beam Section Area: in²

Beam Inertia (I_{xx}): in⁴

Beam Inertia (I_{yy}): in⁴

Beam C.G (Y_{cg}): in

Barrier/Railing Height: in

Depth of Slab: in

Span Number Rear to Current Pier:

Curb to Curb Distance: ft

Auto compute geometry by girders

Span #	Span Length ft	Bridge Width ft
1	70.750	43.160
2	91.500	43.160
3	60.750	43.160
End Bridge	-	43.160

Buttons: Add, Modify, Delete

This screen only needs to be filled out if you intend to auto-generate loads.

These entries are only important for auto-generation of EQ loads.

There are no entries for haunch thickness, pad thickness, or step height. This means auto-generated wind area excludes haunch. Also, lateral superstructure loads can't be elevated further above top of pier cap.

Gutter to Gutter

Not sure what this check box does.

Bridge width was added to allow for flared girders.

Tapered Cap Parameters

Cap Length (X): ft

Length of Non-tapered Segment (X): ft

Cap Min Height (Y): in

Cap Max Height (Y): in

Cap Depth (Z): in

Factor of Reduced Moment of Inertia:

Start Elevation: ft

End Elevation: ft

Skew Angle (deg):

Buttons: OK, Cancel

Recommend setting bottom of column elevation at 0'. This way the (top of) cap elevation will simply be the height from the bottom of the column to the top of the cap.

Left ahead skews are negative. The skew angle only needs to be input if you intend to auto-generate loads.

This factor may be used to reduce member stiffness in the structural model (i.e. simulate a cracked section). The Iowa DOT will typically use gross inertia.

Rectangular Non-Tapered Column

Loc. from left of cap: ft Bot. Elev.: ft Width (X): in Depth (Z): in Factor of Reduced MI: Column fixity:

No.#	Loc. from left of cap: ft	Bot. Elev.: ft	Width (X): in	Depth (Z): in	Factor of Reduced MI:	Column fixity:
1	24.5	0	234	36	1	Fixed

Spring ?
Drilled Shaft ?
Add
Delete
Modify
OK
Cancel

Typically set bottom of column elevations to 0'.

This factor may be used to reduce column stiffness in the structural model. The Iowa DOT typically use gross inertia.

The bottom of column may have spring supports. This may be used to model pile flexibility. We will assume a fully fixed condition.

Bearing / Girders

Configuration
Bearing Line: Single Double

Eccentricity from CL of Cap
First Line: 0. ft Second Line: 0. ft

Line
 First Second

Distance From
 Cap Left End Last Point 0. ft

Line	Point	From	Dist./Abs. Dist.
1	1	Left	2.4/2.4
2	2	Left	10.44/10.44
3	3	Left	18.48/18.48
4	4	Left	26.52/26.52
5	5	Left	34.56/34.56
6	6	Left	42.6/42.6

Add
Delete
Modify
OK
Cancel

Bearing lines will typically be modeled as "Single" for both steel and prestressed bridges. Exceptions may include situations that yield a significant unsymmetrical loading about the c.l. of the cap such as would be caused by unbalanced spans or actual eccentric bearing lines. Variable width bridges that drop a beam line at a pier is another example.

Enter beam spacing along the skew of the pier cap.

Materials

Concrete Strength (psi):
Cap: 3500
Column: 3500
Footing: 3500

Concrete Density (pcf):
Cap: 150
Column: 150
Footing: 150

Concrete Modulus of Elasticity (ksi):
Cap: 3586.62
Column: 3586.62
Footing: 3586.62

Steel Yield Strength (ksi):
Cap (flex): 60
Cap (shear): 60
Column: 60
Footing: 60

Concrete Type:
Cap: Normal
Column: Normal
Footing: Normal

OK
Cancel

Blank entries indicate a default check point generated automatically by RC-Pier. "F/S" of "F" indicates face of support points which may be generated using the option buttons under "Cap design". Entries with an "*" indicate "Additional Check Points" that have been entered directly by the user. No "Additional Check Points" have been input since it is easier to do T-pier cap design in a spreadsheet.

The screenshot shows the 'Structure Model' dialog box with the following data in the table:

Member	Node	Hinge	Check Point	Distance (ft)	Elem Length (ft)
4	5			11.41	
5	6			14.25	2.84
6	13	F/S		15.22	0.97
7	7	F/S		15.22	
			*	20.14	4.92
			*	20.14	

Additional Check Points section:

- Input: 33.785 ft From Left
- Table:

15.22	ACTIVE
33.78	ACTIVE
- Buttons: Add, Delete, Modify, (De)Activate

Cap design section:

- Flexure:
 - Centerline of column
 - Face of support
 - Offset from CL of the column
- Shear:
 - Centerline of column
 - Face of support
 - Offset from CL of the column
- Offset values: 9.285 ft

Plastic Hinge locations:


- Near Column Top:
 - Cap Column joint
 - At Cap Soffit
 - Below Cap Soffit [0. ft]
- Near Column Bottom:
 - At Column Base
 - Above Column Base [0. ft]

$$(0.5) * (17') + (2/3) * (W_R) = 9.285'$$
 where $W_R = 1.178'$
 24.500' to c.l. column
 - 9.285' offset
 15.215'


This 3rd option allows us to create additional check points on each side of each column to act as the critical section or new "Face of support". So here we may enter the W/3 distance $[(2/3) * (W_R)]$.

One short-coming of this 3rd option is that the c.l. of the column is still used for a cap design point when designing cap R/I on the "Cap" tab. The 2nd option, "Face of Support", suppresses the c.l. of the column point when doing cap design. It would be nice if the 3rd option followed the pattern of the 2nd option.

The user could do a separate RC-Pier run for the cantilever with the special loading requirements and with additional check points on the cantilever, but that won't be done in this example.




Nodes



Members

The c.l. of the cap for the structural model is placed at the midpoint of the minimum cap height. The minimum cap height is the end cap taper height.




Normally this list starts out empty, but I have already entered all the load data.



See the next page for the screen captures related to this button.

This example uses simplified wind loads. These loads will be entered twice – once without wind uplift (WS1 to WS4) and once with wind uplift (WS5 to WS8). Technically wind uplift only needs to be applied for the Strength 3 combination when the wind angle is 0 degrees. However, it is simpler and conservative to check each group with and without uplift. Since the WS loads are repeated the WL loads are also repeated due to the dependency between them.

The Iowa load groups correspond with the default load groups except that the reversible feature for the wind loads has been set to uni-directional. This was done because wind uplift is uni-directional and should not be reversed as will be done in RC-Pier if the setting is not changed.




Here I am simply displaying the other loadings that did not get displayed on the screen capture above.



Use "Dependent Load Case Combinations" since it will reduce the number of load cases by maintaining load dependencies.

RC-Pier defaults with a dependency of BR on LL. Often we set this to "None" because we typically use only the worst BR load irrespective of how many lanes of LL are on the bridge.



The only dependent loads we typically use for frame piers are:

CE to LL
WL to WS

This means that if we have 8 WS cases then we must have 8 WL cases. Thus, WL1 is always and only associated with WS1, and WL2 is always and only associated with WS2, and so on.

CAUTION: Clicking "Print" sends ALL the load combination equations immediately to a printer.

LOAD COMBINATIONS - AASHTO LRFD

Comb #	Equation
1	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL1 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
2	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL2 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
3	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL3 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
4	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL4 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
5	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL5 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
6	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL6 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
7	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL7 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
8	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL1 + 1.75 BR1 + 1.00 WAL + 0.50 TU2)
9	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL2 + 1.75 BR1 + 1.00 WAL + 0.50 TU2)
10	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL3 + 1.75 BR1 + 1.00 WAL + 0.50 TU2)
11	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL4 + 1.75 BR1 + 1.00 WAL + 0.50 TU2)
12	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL5 + 1.75 BR1 + 1.00 WAL + 0.50 TU2)
13	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL6 + 1.75 BR1 + 1.00 WAL + 0.50 TU2)

Click on "Default Comb" to generate all the default load combinations.

LOAD COMBINATIONS - AASHTO LRFD

Comb #	Equation
1292	(IA SER 1) = 1.00 (1.00 DC1 + 1.00 DW1 + 1.00 LL3 - 1.00 BR1 + 1.00 WAL + 0.30 WS8 + 1.00 WL8 + 1.00 TU2)
1293	(IA SER 1) = 1.00 (1.00 DC1 + 1.00 DW1 + 1.00 LL4 - 1.00 BR1 + 1.00 WAL + 0.30 WS8 + 1.00 WL8 + 1.00 TU2)
1294	(IA SER 1) = 1.00 (1.00 DC1 + 1.00 DW1 + 1.00 LL5 - 1.00 BR1 + 1.00 WAL + 0.30 WS8 + 1.00 WL8 + 1.00 TU2)
1295	(IA SER 1) = 1.00 (1.00 DC1 + 1.00 DW1 + 1.00 LL6 - 1.00 BR1 + 1.00 WAL + 0.30 WS8 + 1.00 WL8 + 1.00 TU2)
1296	(IA SER 1) = 1.00 (1.00 DC1 + 1.00 DW1 + 1.00 LL7 - 1.00 BR1 + 1.00 WAL + 0.30 WS8 + 1.00 WL8 + 1.00 TU2)

Load Combinations for Columns only:

Comb #	Equation
1C	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL1 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
2C	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL2 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
3C	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL3 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
4C	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL4 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
5C	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL5 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
6C	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL6 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)
7C	(IA STR 1) = 1.00 (1.25 DC1 + 1.50 DW1 + 1.75 LL7 + 1.75 BR1 + 1.00 WAL + 0.50 TU1)


A different set of combinations is used for the column and cap.

Not sure the two sets are necessary for LRFD. It is probably a hold-over from the Aashto Std. Spec. since there was a separate β_d factor of 0.75 and 1.00 for columns.

Note: There are a number of features on this screen that will not be demonstrated in this example. For instance, you can

- delete combinations
- edit combinations
- add your own combinations


These features are particularly useful for testing loading scenarios and trouble-shooting problems.




This is the Library Setup screen from Leap Bridge.

This is the Library Setup screen from RC-Pier.


This library contains the Iowa Load Groups.



Not sure why these libraries are not included in the Leap Bridge library setup screen above.



The Iowa Load Groups



Notice that the wind loads have been switched from "Reversible" to "Uni-directional"

In general Iowa will use the smaller values for the TU and SH load factors along with gross inertia of the pier members. See Aashto Lrfd 3.4.1, the first paragraph on page 3-12 of the 5th edition (2010).

DC1

The "1" in "DC1" refers to the 1st load case number in the generic DC load type numbering sequence. So, the "DC1" load data includes DC1 loads (e.g. slab, beams, etc.) and DC2 loads (SBC).

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	Y	-136.7040
1	2	Y	-146.2640
1	3	Y	-146.2640
1	4	Y	-146.2640
1	5	Y	-146.2640
1	6	Y	-136.7040

Name: DC1

Multiplier for Loads: 1.0

Note: Vertically downward loads be added as negative loads in Y direction.

Common mistakes to avoid when entering DC (and DW) load data manually are:

- Forgetting to change the "Bearing Point #" to the correct beam line.
- Forgetting to change the "Dir" to the proper global axis direction.
- Getting the sign on the load wrong.

These loads can be auto-generated, but the magnitude of the load will typically be too small since RC-Pier is not able to capture all the dead load involved (e.g. pier and intermediate diaphragms, haunches, slab overhang thickening).

The spreadsheet that was setup to calculate DC1 loads will not generate standardized text files in order to import the loads. The DC (and DW) input is relatively minor for this load case.

DW1

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	Y	-12.2490
1	2	Y	-12.2490
1	3	Y	-12.2490
1	4	Y	-12.2490
1	5	Y	-12.2490
1	6	Y	-12.2490

Name: DW1

Multiplier for Loads: 1.0

Note: Vertically downward loads be added as negative loads in Y direction.

These loads can be auto-generated, but the load is distributed based on tributary area. We normally distribute the FWS equally among all the beams.

LL1

Impact is excluded. Multiple presence factors are included.

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	Y	-54.1750
1	2	Y	-48.6190
1	3	Y	0.0000
1	4	Y	0.0000
1	5	Y	0.0000
1	6	Y	0.0000
1	1	Y	-34.1220
1	2	Y	-30.9610
1	3	Y	-0.5360
1	4	Y	0.0000

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
--------	-----------	-----	------	------	------	------	-------

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units
-----------	-----	----------	------	------	------	------	-------

Name: LL1
Description:
Multiplier for Loads: 1
Generate Import

There are 7 LL cases, but I will only show the first one.

Live loads are imported from the text files generated by the in-house spreadsheet for bridge pier live loads.

Look in: 1203 Jefferson 2010-10-10

- PDFExample
- WordExample
- BRLoads001.txt
- BRLoads002.txt
- LLPier1Loads001.txt**
- LLPier1Loads002.txt
- LLPier1Loads003.txt
- LLPier1Loads004.txt
- LLPier1Loads005.txt
- LLPier1Loads006.txt
- LLPier1Loads007.txt
- RCPierColumnOutput.txt
- WLLoads001.txt
- WLLoads002.txt
- WLLoads003.txt
- WLLoads004.txt
- WSLoadsNoUplift001.txt
- WSLoadsNoUplift002.txt
- WSLoadsNoUplift003.txt
- WSLoadsNoUplift004.txt
- WSLoadsYesUplift001.txt
- WSLoadsYesUplift002.txt
- WSLoadsYesUplift003.txt
- WSLoadsYesUplift004.txt

File name: LLPier1Loads001.txt
Files of type: Import loads from file (*.txt)

```
Bearing Loads
1, 1, Y, -54.175
1, 2, Y, -48.619
1, 3, Y, 0
1, 4, Y, 0
1, 5, Y, 0
1, 6, Y, 0
1, 1, Y, -34.122
1, 2, Y, -30.961
1, 3, Y, -0.536
1, 4, Y, 0
1, 5, Y, 0
1, 6, Y, 0
```

This is the content of "LLPier1Loads001.txt" which is imported into RC-Pier for LL1.

TU1

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	X	-4.4400
1	1	Z	-3.8200
1	2	X	-4.4400
1	2	Z	-3.8200
1	3	X	-4.4400
1	3	Z	-3.8200
1	4	X	-4.4400
1	4	Z	-3.8200
1	5	X	-4.4400
1	5	Z	-3.8200
1	6	X	-4.4400

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
--------	-----------	-----	------	------	------	------	-------

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units
-----------	-----	----------	------	------	------	------	-------

Strain Load

Unit: 0

+ Expansion - Contraction

Name: TU1

Description:

Factors: Multiplier for Loads: 1

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

By default this load is not reversible in the load library so I need to enter two load cases: TU1 and TU2.

These loads can be auto-generated, but the procedure is not according to DOT policy.

The spreadsheet that was setup to calculate TU loads will not generate standardized text files in order to import the loads.

TU2

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	X	4.4400
1	1	Z	3.8200
1	2	X	4.4400
1	2	Z	3.8200
1	3	X	4.4400
1	3	Z	3.8200
1	4	X	4.4400
1	4	Z	3.8200
1	5	X	4.4400
1	5	Z	3.8200
1	6	X	4.4400

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
--------	-----------	-----	------	------	------	------	-------

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units
-----------	-----	----------	------	------	------	------	-------

Strain Load

Unit: 0

+ Expansion - Contraction

Name: TU2

Description:

Factors: Multiplier for Loads: 1

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

BR1

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	X	-1.1570
1	1	Y	-1.7760
1	1	Z	-1.8510
1	2	X	-1.1570
1	2	Y	0.0000
1	2	Z	-1.8510
1	3	X	-1.1570
1	3	Y	0.0000
1	3	Z	-1.8510
1	4	X	-1.1570
1	4	Y	0.0000

Braking force is set as a reversible load in the load library. This means I only need to enter one BR load because the program will reverse it for me.

Braking can be auto-generated. We typically distribute the concentrated truck portion of this force among the contributing bents; however, RC-Pier puts the entire load on the pier being analyzed.

These loads were imported from text file "BRLoads001.txt" generated by the spreadsheet for BR loads.

```
Bearing Loads
1, 1, X, -1.157
1, 1, Y, -1.776
1, 1, Z, -1.851
1, 2, X, -1.157
1, 2, Y, 0
1, 2, Z, -1.851
1, 3, X, -1.157
1, 3, Y, 0
1, 3, Z, -1.851
1, 4, X, -1.157
1, 4, Y, 0
1, 4, Z, -1.851
1, 5, X, -1.157
1, 5, Y, 0
1, 5, Z, -1.851
1, 6, X, -1.157
1, 6, Y, 1.776
1, 6, Z, -1.851
```

WA1

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	UDL	Y	3.6500	0.0000	0.0000	0.1130	klf
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units

Strain Load

Unit:

+ Expansion - Contraction

Name:

Description:

Factors: Multiplier for Loads:

Auto Generation:

Import Loads:

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

The only water loads that affect the column and cap design for Case 1 are the buoyancy loads on the column.

The spreadsheet that was setup to calculate WA loads will not generate standardized text files in order to import the loads.

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	X	-3.8990
1	1	Y	-2.1450
1	1	Z	3.9670
1	2	X	-3.8990
1	2	Y	0.0000
1	2	Z	3.9670
1	3	X	-3.8990
1	3	Y	0.0000
1	3	Z	3.9670
1	4	X	-3.8990
1	4	Y	0.0000

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	UDL	X	-0.1200	0.3330	0.0000	0.8330	
1	UDL	Z	0.7800	0.3330	0.0000	0.8330	

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L
Force	X	0.0000	-0.9800	0.5000	0.0000	0.0000
UDL	Z	0.0000	0.2450	0.0000	0.0000	1.0000

Strain Load

Unit: 0

+ Expansion - Contraction

Name: WS1

Description:

Factors: Multiplier for Loads: 1

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

There are 8 WS cases (4 cases with uplift and 4 cases without), but I will only show the first one.

Remember that the reversible feature for wind loads was turned off in the library.

Wind loads can be auto-generated, but generating simplified wind loads requires a few tricks and some editing of the load results.

The wind loads above were imported from text file "WSLoadsNoUplift001.txt" which was generated from the in-house spreadsheet for wind loads.

```

Bearing Loads
1, 1, X, -3.899
1, 1, Y, -2.145
1, 1, Z, 3.967
1, 2, X, -3.899
1, 2, Y, 0
1, 2, Z, 3.967
1, 3, X, -3.899
1, 3, Y, 0
1, 3, Z, 3.967
1, 4, X, -3.899
1, 4, Y, 0
1, 4, Z, 3.967
1, 5, X, -3.899
1, 5, Y, 0
1, 5, Z, 3.967
1, 6, X, -3.899
1, 6, Y, 2.145
1, 6, Z, 3.967
Cap Loads
Force, X, 0, -0.98, 0.5
UDL, Z, 0.245, 0, 1
Column Loads
1, UDL, X, -0.12, 0.333, 0.833
1, UDL, Z, 0.78, 0.333, 0.833
    
```

WL1

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	X	-0.8600
1	1	Y	-1.3210
1	1	Z	1.1750
1	2	X	-0.8600
1	2	Y	0.0000
1	2	Z	1.1750
1	3	X	-0.8600
1	3	Y	0.0000
1	3	Z	1.1750
1	4	X	-0.8600
1	4	Y	0.0000

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L
--------	-----------	-----	------	------	------	------

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L
-----------	-----	----------	------	------	------	------

Strain Load

Unit: 0.0

+ Expansion - Contraction

Name: WL1

Description:

Factors: Multiplier for Loads: 1.0

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

There are 8 WL cases, but I will only show the first one.

Remember that the WL cases are dependent on the WS cases. This means that WL1 is the only WL load that can appear in the same combination with WS1.

Bearing Loads

```
1, 1, X, -0.86
1, 1, Y, -1.321
1, 1, Z, 1.175
1, 2, X, -0.86
1, 2, Y, 0
1, 2, Z, 1.175
1, 3, X, -0.86
1, 3, Y, 0
1, 3, Z, 1.175
1, 4, X, -0.86
1, 4, Y, 0
1, 4, Z, 1.175
1, 5, X, -0.86
1, 5, Y, 0
1, 5, Z, 1.175
1, 6, X, -0.86
1, 6, Y, 1.321
1, 6, Z, 1.175
```

Wind loads can be auto-generated, but generating simplified wind loads requires some editing of the load results.

The wind loads above were imported from text file "WLLoads001.txt" which was generated from the in-house spreadsheet for wind loads.

Run the Analysis

Run Analysis... Type: Load Case Item: DC1 Filter

A/D Parameters Effect: Forces & Moment Format: General Right

Type of Analysis: Frame Strut and Tie Coord. System: Local Global Print...

Memb	Node	Fx	Fy	Fz	Mx	My	Mz
1	1	-0	858.5	0	-0	0	-0.0005215
1	2	-0	-858.5	0	-0	0	0.0005215
2	3	0	0	0	0	0	0
2	4	0	0	0	0	0	0
			-136.7				
			136.7				
			-283				
			283				
			-283				
			283				
			-429.2				
			429.2				
			429.2				3661
8	2	0	-429.2	0	0	0	-5534
8	8	0	-429.2	0	0	0	5534
9	8	0	283	0	0	0	-3661
9	14	0	-283	0	0	0	3661
10	14	0	283	0	0	0	-2268
10	9	0	-283	0	0	0	2268
11	9	0	283	0	0	0	-1995
11	10	0	-283	0	0	0	1995
12	10	0	136.7	0	0	0	-1193
12	11	0	-136.7	0	0	0	1193
13	11	0	0	0	0	0	0
13	12	0	0	0	0	0	0

See screen on the next page for the analysis and design parameter settings.

The filter allows you to specify what members and nodes you want to see as well as which forces.

Recommend viewing results in global coordinates.

This screen is useful for checking reasonableness of results and for resolving differences among designers and checkers since you can look at load cases, load combinations, and envelopes.

Analysis and Design Parameters

Typically fatigue is not considered.

z-check

Not of interest for cap and column design.

Don't use

We will use "Phi as per 2006 classification". This means we look at sections as being Tension Controlled, In-Transition, or Compression Controlled. See Aashto Lrfd Fig. C5.5.4.2.1-1 for information on how the "c/dt ratio" used in the calculation of the flexural resistance factors in transition.

We typically use moment magnification for column design. The parameters we use can be entered on the column design screen.

The Bridge Manual does not specify which shear method to use for cap design. A general recommendation is to base shear design for the cap on the "Simplified" method or the "Beta-Theta" method. The "Beta-Theta" method is actually the procedure listed in Aashto Lrfd 5.8.3.4.2 (General Procedure with closed form solution) rather than that found in Aashto Lrfd Appendix B5 (General Procedure with tables). The "General" method listed on the screen above is the one found in Aashto Lrfd Appendix B5.

RC-Pier does not check column shear. Designers may want to verify that column shear is OK.

Design status report is printed out a few pages over.

Pier Cap Design: RC-Pier

Selection: Cap

Buttons: Auto Design, Design Status, Edit/View, Main bars, Stirrups, Show Cap End Results

Location:	Bar Size:	# Bars	From: ft	To: ft	Bar dist. in	Hook:
Top	#11	8	0.16	48.84	3.50	None
Top	#11	8	0.16	48.84	7.50	None
Top	#11	4	0.16	48.84	11.50	None
Bottom	#6	4	0.16	48.84	3.25	None

Buttons: Add, Modify, Delete, Delete All, Sketch

We'll include this, but there really isn't a need to do so.

The flexure reinforcement is as shown in the plan set.

Beam cap R/I can be automatically generated if desired. More than likely the generated reinforcement will need to be modified. I manually entered the flexure and shear reinforcement.

Selection: Cap



Buttons: Auto Design, Design Status, Edit/View, Main bars, Stirrups, Show Cap End Results

Stirrup Size	n legs	Av/s: in/ft	From: ft	To: ft	Spacing: in
#3		0.	0.	0.	0.
#5	4	1.380	0.00	11.00	10.75
#5	4	2.480	11.00	15.00	6.00
#5	4	0.827	15.00	24.00	18.00
#5	4	1.240	24.00	25.00	12.00
#5	4	0.827	25.00	34.00	18.00
#5	4	2.480	34.00	38.00	6.00
#5	4	1.380	38.00	49.00	10.75

Buttons: Add, Modify, Delete, Delete All, Sketch

The shear reinforcement is as shown in the plan set.

The stirrup spacing does not need to divide exactly into the distance covered between the "From" and "To" entries. For instance, double #5s at 10.75" doesn't divide evenly into 11.00'. RC-Pier just assumes the stirrup area of the double #5s at 10" applies over the first 11.00' of the pier cap.



CAP DESIGN

I've included some portions of RC-Pier's output for the cap design.

CAP DESIGN

Code: AASHTO LRFD 2007 (with Interims)

Units: US

Pier View: Upstation.

DESIGN PARAMETERS

$f_c = 3500.0$ psi

F_y flex = 60000.0 psi F_y shear = 60000.0 psi

ϕ tens = 0.90

ϕ comp = 0.75 ϕ shear = 0.90

Tens below = 0.375 Comp Above = 0.600

$E_c = 3586.6$ ksi $E_s = 29000.0$ ksi

Crack check as per 2005 Interims

Crack control Exposure = 1.00

Concrete Type : Normal Weight.

Design of cap at centerline of column.

CAP GEOMETRY

Tapered Cap : Length(X) = 49.00 ft Depth(Z) = 42.00 in

Cap Section Properties

Sec.	Area ft ²	I _{xx} in ⁴	I _{zz} in ⁴
1	24.50	2074464.00	518616.00

MAIN REINFORCEMENT

	Bar size	Quantity	Bar dist in	A _s total in ²	From ft	To ft	Hook
TOP							
	# 11	8	3.50	12.480	0.16	48.84	None
	# 11	8	7.50	12.480	0.16	48.84	None
	# 11	4	11.50	6.240	0.16	48.84	None
BOTTOM							
	# 6	4	3.25	1.760	0.16	48.84	None

STIRRUPS

From ft	To ft	Stirrup Size	n legs	Spacing in	A _{prvs} in ² /ft
0.00	11.00	# 5	4	10.75	1.38
11.00	15.00	# 5	4	6.00	2.48
15.00	24.00	# 5	4	18.00	0.83
24.00	25.00	# 5	4	12.00	1.24
25.00	34.00	# 5	4	18.00	0.83
34.00	38.00	# 5	4	6.00	2.48
38.00	49.00	# 5	4	10.75	1.38

FLEXURE DESIGN

Bottom R/I

Top R/I

Span 1: From 0.00 ft To 24.50 ft											
Loc ft	AbsLoc ft	H in	Mmax Mmin kips-ft	Mr kips-ft	Comb CL	Asb-req in ²	Asb-prv in ²	Asb-eff in ²	Ast-req in ²	Ast-prv in ²	Ast-eff in ²
0.0	0.0	48	0.0	0.0	0 T	0.85	0.00*	0.00*	0.85	0.00*	0.00*
			0.0	-0.0	0 T	0.85	0.00*	0.00*	0.85	0.00*	0.00*
2.7	2.7	55	11.9	786.7	156 T	0.90	1.76	1.76	0.90	31.20	31.20
			-29.4	-2221.7	114 T	0.90	1.76	1.76	0.90	31.20	10.82
11.4	11.4	77	0.0	961.3	0 T	1.03	1.76	1.76	1.03	31.20	31.20
			-3529.2	-8880.5	1 T	1.03	1.76	1.76	11.65	31.20	31.20
14.3	14.3	84	0.0	1018.0	0 T	1.06	1.76	1.76	1.06	31.20	31.20
			-5775.1	-9886.4	1 T	1.06	1.76	1.76	17.56	31.20	31.20
15.2	15.2	84	0.0	1018.0	0 T	1.06	1.76	1.76	1.06	31.20	31.20
			-6547.4	-9886.4	1 T	1.06	1.76	1.76	20.07	31.20	31.20
20.1	20.1	84	0.0	1018.0	0 T	1.06	1.76	1.76	1.06	31.20	31.20
			-10562.7	-9886.4*	1 T	1.06	1.76	1.76	33.94	31.20	31.20
24.5	24.5	84	0.0	1018.0	0 T	1.06	1.76	1.76	1.06	31.20	31.20
			-15399.2	-9886.4*	3 T	1.06	1.76	1.76	52.99	31.20*	31.20*
Span 2: From 24.50 ft To 49.00 ft											
Loc ft	AbsLoc ft	H in	Mmax Mmin kips-ft	Mr kips-ft	Comb CL	Asb-req in ²	Asb-prv in ²	Asb-eff in ²	Ast-req in ²	Ast-prv in ²	Ast-eff in ²
0.0	24.5	84	0.0	1018.0	0 T	1.06	1.76	1.76	1.06	31.20	31.20
			-15399.2	-9886.4*	25 T	1.06	1.76	1.76	52.99	31.20*	31.20*
4.4	28.9	84	0.0	1018.0	0 T	1.06	1.76	1.76	1.06	31.20	31.20
			-10562.7	-9886.4*	23 T	1.06	1.76	1.76	33.94	31.20*	31.20*
9.3	33.8	84	0.0	1018.0	0 T	1.06	1.76	1.76	1.06	31.20	31.20
			-6547.4	-9886.4	23 T	1.06	1.76	1.76	20.07	31.20	31.20
10.3	34.8	84	0.0	1018.0	0 T	1.06	1.76	1.76	1.06	31.20	31.20
			-5775.1	-9886.4	23 T	1.06	1.76	1.76	17.56	31.20	31.20
13.1	37.6	77	0.0	961.3	0 T	1.03	1.76	1.76	1.03	31.20	31.20
			-3529.2	-8880.5	23 T	1.03	1.76	1.76	11.65	31.20	31.20
21.8	46.3	55	11.9	786.7	146 T	0.90	1.76	1.76	0.90	31.20	31.20
			-29.4	-2221.7	124 T	0.90	1.76	1.76	0.90	31.20	10.82
24.5	49.0	48	0.0	0.0	0 T	0.85	0.00*	0.00*	0.85	0.00*	0.00*
			0.0	-0.0	0 T	0.85	0.00*	0.00*	0.85	0.00*	0.00*

Iowa has special loading requirements for the pier cap overhang design which were not included in this RC-Pier run. Further on in this example is a spreadsheet design addresses these requirements.

The cap end results could have been excluded if we had left the "Show Cap End Results" check box unchecked.

I will show some hand calculations for the top reinforcement at this location (15.2') a little later in the example.

Ideally the C.L. of the column would be excluded when the user specifies offsets from the C.L. of columns as we did.

Flexure Design : Notes
 CL: Section classification as per LRFD 2006 interims for provided reinforcement.
 C = Compression controlled, I = In-Transition, T = Tension controlled.
 * The provided reinforcement is not adequate, either less than required or larger than maximum allowed.

SHEAR AND TORSION DESIGN

Required Shear R/I

Provided Shear R/I

Span 1: From 0.00 ft To 24.50 ft

Loc ft	AbsLoc ft	Pos	Vu kips	Comb	Tu kips-ft	Comb	phi*Vc kips	T-lim kips-ft	Avs/s in ² /ft	2A _{ts} /s in ² /ft	Av/s in ² /ft	Aprv/s in ² /ft	Alx in ²
0.00	0.00	R	0.0	0	0.0	0	214.7	99.0	0.00	0.00	0.00	1.38	0.00
2.69	2.69	L	7.6	1	0.0	0	203.5	120.0	0.00	0.00	0.00	1.38	0.00
		R	385.7	1	14.9	125	203.5	120.0	0.89	0.00	0.89	1.38	0.00
11.41	11.41	L	417.1	1	14.9	115	282.3	192.1	0.50	0.00	0.50	2.48	0.00
		R	785.7	1	29.9	121	282.3	192.1	1.77	0.00	1.77	2.48	0.00
14.25	14.25	L	798.1	1	29.9	115	312.2	216.6	1.55	0.00	1.55	2.48	0.00
		R	798.1	1	29.9	121	312.2	216.6	1.55	0.00	1.55	2.48	0.00
15.22	15.22	L	802.6	1	29.9	115	312.2	216.6	1.56	0.00	1.56	0.83**	2.10
		R	802.6	1	29.9	121	312.2	216.6	1.56	0.00	1.56	0.83**	2.10
20.14	20.14	L	825.2	1	29.9	115	312.2	216.6	1.63	0.00	1.63	0.83**	15.27
		R	1192.5	3	44.8	121	312.2	216.6	2.80	0.00	2.80	0.83**	20.80
24.50	24.50	L	1212.6	3	44.8	115	312.2	216.6	2.87	0.00	2.87	1.24**	36.67

Additional longitudinal reinforcement required based on Aashto Lrfd 5.8.3.5. As of the printing of this example the Iowa DOT Bridge Design Manual requires that this provision be met all along the cap for pier cap design.

Span 2: From 24.50 ft To 49.00 ft

Loc ft	AbsLoc ft	Pos	Vu kips	Comb	Tu kips-ft	Comb	phi*Vc kips	T-lim kips-ft	Avs/s in ² /ft	2A _{ts} /s in ² /ft	Av/s in ² /ft	Aprv/s in ² /ft	Alx in ²
0.00	24.50	R	1212.6	25	44.8	115	312.2	216.6	2.87	0.00	2.87	1.24**	36.67
4.36	28.86	L	1192.5	25	44.8	121	312.2	216.6	2.80	0.00	2.80	0.83**	20.80
		R	825.2	23	29.9	115	312.2	216.6	1.63	0.00	1.63	0.83**	15.27
9.28	33.78	L	802.6	23	29.9	121	312.2	216.6	1.56	0.00	1.56	0.83**	2.10
		R	802.6	23	29.9	115	312.2	216.6	1.56	0.00	1.56	0.83**	2.10
10.25	34.75	L	798.1	23	29.9	121	312.2	216.6	1.55	0.00	1.55	2.48	0.00
		R	798.1	23	29.9	115	312.2	216.6	1.55	0.00	1.55	2.48	0.00
13.09	37.59	L	785.7	23	29.9	121	282.3	192.1	1.77	0.00	1.77	2.48	0.00
		R	417.1	23	14.9	119	282.3	192.1	0.50	0.00	0.50	2.48	0.00
21.81	46.31	L	385.7	23	14.9	121	203.5	120.0	0.89	0.00	0.89	1.38	0.00
		R	7.6	1	0.0	0	203.5	120.0	0.00	0.00	0.00	1.38	0.00
24.50	49.00	L	0.0	0	0.0	0	214.7	99.0	0.00	0.00	0.00	1.38	0.00

Torsion is usually not a factor for a typical T-pier design. There are essentially two reasons for this. The first reason is that we often use a single line of bearings centered on the pier cap. Modeling the pier this way reduces M_x cap moments. The second reason is that we generally assume lateral superstructure loading does not generate M_x cap moments between the superstructure and the top of the cap. The user needs to determine if these modeling assumptions are appropriate for their design.

Shear and Torsion Design : Notes

** Provided stirup area (Aprv/s) is not adequate.

- Pos is the design position. L suggests the calculation is done at immediate left of "Loc" and R suggests at immediate right of it.

- T-lim is the limiting value of torsion for the concrete section. If actual torsion is higher than this value, torsional steel has to be provided.

- Avs/s is the required area of steel per unit length for shear force.

- 2A_{ts}/s is the required area of steel per unit length for two legs of torsional reinforcement.

- Av/s is the total required area of steel per unit length due to shear plus torsion.

- Aprv/s is the total provided area of steel per unit length due to shear (stirups).

- Alx is the EFFECTIVE longitudinal steel required in addition to the PROVIDED EFFECTIVE flexural steel.

CRACKING/FATIGUE CHECK

Span 1: From 0.00 ft To 24.50 ft											
Loc ft	AbsLoc ft	H in	Cracking Comb	Cracking fs-t fs-b ksi	Cracking dc in	Cracking Srqt Srqb in	Cracking Sprt Sprb in	Fatigue fs-t fs-b ksi	Fatigue ratio fs-t ratio fs-b	Fatigue Comb	
0.00	0.0	48.0	0	0.0	0.0	42.0	0.0	0.0	0.00	0	
			0	0.0	0.0	42.0	0.0	0.0	0.00	0	
2.69	2.7	54.8	1080	0.6	3.5	42.0	5.0	0.0	0.00	0	
			1262	1.2	3.3	42.0	12.0	0.0	0.00	0	
11.41	11.4	76.8	1108	15.3	3.5	35.9	5.0	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	
14.25	14.3	84.0	1108	22.4	3.5	22.4	5.0	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	
15.22	15.2	84.0	1108	25.4	3.5	18.9	5.0	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	
20.14	20.1	84.0	1080	41.0	3.5	9.1	5.0	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	
24.50	24.5	84.0	1082	60.0	3.5	4.0	5.0*	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	

Span 2: From 24.50 ft To 49.00 ft											
Loc ft	AbsLoc ft	H in	Cracking Comb	Cracking fs-t fs-b ksi	Cracking dc in	Cracking Srqt Srqb in	Cracking Sprt Sprb in	Fatigue fs-t fs-b ksi	Fatigue ratio fs-t ratio fs-b	Fatigue Comb	
0.00	24.5	84.0	1265	60.0	3.5	4.0	5.0*	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	
4.36	28.9	84.0	1263	41.0	3.5	9.1	5.0	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	
9.28	33.8	84.0	1291	25.4	3.5	18.9	5.0	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	
10.25	34.8	84.0	1291	22.4	3.5	22.4	5.0	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	
13.09	37.6	76.8	1291	15.3	3.5	35.9	5.0	0.0	0.00	0	
			0	0.0	3.3	42.0	12.0	0.0	0.00	0	
21.81	46.3	54.8	1262	0.6	3.5	42.0	5.0	0.0	0.00	0	
			1080	1.2	3.3	42.0	12.0	0.0	0.00	0	
24.50	49.0	48.0	0	0.0	0.0	42.0	0.0	0.0	0.00	0	
			0	0.0	0.0	42.0	0.0	0.0	0.00	0	

Cracking and fatigue Check : Notes

* Provided rebar spacing is not adequate for crack control.

Hand Calculations for Top Reinforcement in Span 1 at Location 15.2'

$M_{max} = -6547.4 \text{ k}\cdot\text{ft}$

$\rho = A_s / (b \cdot d) = (31.2 \text{ in}^2) / [(42'') \cdot (77.30'')] = 0.0096101$

$\rho_b = [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot [87 / (87 + f_y)] = [(0.85 \cdot 0.85 \cdot (3.5 \text{ ksi})) / (60 \text{ ksi})] \cdot [87 / (87 + 60 \text{ ksi})] = 0.02494345$

$\rho_{max} = 0.634 \cdot \rho_b = 0.0158141$ (See derivation below.)

RC-Pier has $M_r = 9886.4 \text{ k}\cdot\text{ft}$ since it treats the section as doubly-reinforced.

$\rho_{max} > \rho$ which means the section is tension-controlled: $f_s = f_y$ and $\phi = 0.90$

$a = A_s \cdot f_y / [(0.85) \cdot (f'_c) \cdot (b)] = (31.2 \text{ in}^2) \cdot (60 \text{ ksi}) / [(0.85) \cdot (3.5 \text{ ksi}) \cdot (42'')] = 14.9820''$

$\phi M_n = \phi A_s \cdot f_y \cdot (d - a/2) = (0.9) \cdot (31.2 \text{ in}^2) \cdot (60 \text{ ksi}) \cdot [(77.30'') - (14.9820'')/2] / (12 \text{ in/ft}) = 9801.2 \text{ k}\cdot\text{ft}$

$f_r = 0.37 \cdot (f'_c)^{0.5} = 0.37 \cdot (3.5 \text{ ksi})^{0.5} = 0.692207 \text{ ksi}$

$M_{cr} = f_r \cdot I / c = [(0.692207 \text{ ksi}) \cdot (1/12) \cdot (42'') \cdot (84'')^3] / [(0.5) \cdot (84'') \cdot (12 \text{ in/ft})] = 2849.12 \text{ k}\cdot\text{ft}$

$1.2M_{cr} = (1.2) \cdot (2849.12 \text{ k}\cdot\text{ft}) = 3418.95 \text{ k}\cdot\text{ft} < \phi M_n = 9801.2 \text{ k}\cdot\text{ft}$


So $1.2M_{cr} = 1036.65 \text{ k}\cdot\text{ft}$ controls the design – Find required A_s based on $1.2 \cdot M_{cr}$

$R_n = R_u / \phi = M_u / (\phi \cdot b \cdot d^2) = (6547.4 \text{ k}\cdot\text{ft}) \cdot (12 \text{ in/ft}) / [(0.9) \cdot (42'') \cdot (77.30'')^2] = 0.34786 \text{ ksi}$

$\rho = (0.85 \cdot f'_c / f_y) \cdot [1 - (1 - (2 \cdot R_n) / (0.85 \cdot f'_c))^{0.5}]$

$= [(0.85) \cdot (3.5 \text{ ksi}) / (60 \text{ ksi})] \cdot [1 - [1 - ((2) \cdot (0.34786 \text{ ksi})) / ((0.85) \cdot (3.5 \text{ ksi}))]^{0.5}] = 0.006183$

Required $A_s = \rho \cdot b \cdot d = (0.006183) \cdot (42'') \cdot (77.30'') = 20.074 \text{ in}^2$ ← Matches RC-Pier



Derivation of $\rho_{max} = 0.634 \cdot \rho_b$ [Ensuring tension controlled sections for singly-reinforced concrete beams.]

<u>Compression Controlled</u>	<u>Transition</u>	<u>Tension Controlled</u>
0.75	$\phi = 0.65 + 0.15 \cdot (d_t/c - 1)$	0.90
$\epsilon_t \leq 0.002$		$\epsilon_t \geq 0.005$
$d_t/c \leq 1.667$		$d_t/c \geq 2.667$
$c/d_t \geq 0.600$		$c/d_t \leq 0.375$

To get $\phi = 0.90$ the $\epsilon_t \geq 0.005$ and $c/d_t \leq 0.375$

Note: $c/d_t = \epsilon_u / (\epsilon_u + \epsilon_s)$

At yield: $\rho_b = [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot [87 / (87 + f_y)] = [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot [\epsilon_u / (\epsilon_u + \epsilon_s)]$
 $= [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot [0.003 / (0.003 + (60 \text{ ksi}) / (29,000 \text{ ksi}))]$ $\epsilon_s = 0.00207 \text{ in/in}$
 $= [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot (0.5918367)$
 $= [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot (3/5)$ approximately

At $\epsilon_s = 0.005$: $\rho_{max} = [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot [0.003 / (0.003 + 0.005)]$
 $= [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot (0.375)$
 $= [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot (3/8)$ approximately

So $\rho_{max} = C_1 \cdot \rho_b \Leftrightarrow [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot (0.375) = C_1 \cdot [(0.85 \cdot B_1 \cdot f'_c) / f_y] \cdot (0.5918367)$
 $C_1 = 0.375 / 0.5918367 = 0.634$ which is approximately $[(3/8) / (3/5)] = 5/8 = 0.625$

So in order to ensure $\phi = 0.90$ the value of ρ must be less than the new $\rho_{max} = 0.634 \cdot \rho_b$

Pier Cantilever Design

There are two beams on the cantilever. Loads were calculated earlier in example.

<u>DC Loads</u>	<u>Exterior Beam</u>	<u>Interior Beam</u>
Beam	53.895 k	53.895 k
Slab	58.723 k	60.318 k
Haunch	1.688 k	1.688 k
Intermediate Diaphragm	0.141 k	0.281 k
Pier Diaphragm	9.213 k	14.423 k
Pier Steps	-----	2.615 k
SBC (All to exterior beams)	39.136 k	-----
Total	162.796 k	133.220 k

<u>DW Loads</u>	<u>Exterior Beam</u>	<u>Interior Beam</u>
FWS	12.249 k	12.249 k

Live Load

Max. LL+I Reaction = 168.615 k Dual Truck Train + Lane Controls


Since there are two beams on the pier cap overhang we are not required to use live load shear distribution factors to determine the beam live load reactions. The live loading for the beams may be based on the pier live loading which assumes simple supports between the beams. From the pier live load spreadsheet results it appears that one loaded lane will produce the maximum live load reactions (and maximum moment and shear in the pier cap overhang) for the beams on the overhang. The pier live load spreadsheet already includes multiple presence factors, but does not include impact for the truck portion.

Exterior Beam: $(54.175 \text{ k}) \cdot (1.33) + (34.122 \text{ k}) = 106.175 \text{ k}$

Interior Beam: $(48.619 \text{ k}) \cdot (1.33) + (30.961 \text{ k}) = 95.624 \text{ k}$

Spreadsheet for Pier Cap Overhang Design

PIER CAP OVERHANG DESIGN Includes T-Piers or Frame Piers with either one or two beams on the overhang. Sections checked include points A, B, C and 5th points along taper.



General Input

Note: X1, H3, and R_e are calculated based on other dimensions

All dimensions are along skew of pier cap

Is this a T-Pier? Y or N	Y	This entry only affects the calculation of R_e
Edge Dist. bt. Column and Cap Taper, L1 (Typ. 3")	3.000	in
Taper Length, L2	14.250	ft
Column Radius, R	1.500	ft
Cap Height, H1	7.000	ft
Cap Height at End, H2	4.000	ft
Beam Spa, X2 -- Enter 0 if only one beam on overhang	8.725	ft
Distance bt. Exterior Beam and Cap End, X3	2.688	ft
Pier Cap Depth, B	3.500	ft
Estimated Dist. from Cap Top to C.G. of Top R/l, d'	6.700	in

Note: Input items P1 and X2 shall be set to 0 if there is only one beam on the overhang. [P1 shall only be considered to be on the overhang if it falls to the right of the effective column face.]

Concentrated Beam Loads Enter 0 kips for all Int. Beam Loads (P1 Loads) if only one beam is on the overhang.	Unfactored Loads		Hover for extended comment
	Interior Beam, P1	Exterior Beam, P2	
DC Load (DC1 and DC2)	133.220	162.796	k
DW Load	12.249	12.249	k
LL+IM Load (Truck with Impact and Lane)	95.624	106.175	k
Total Load	241.093	281.220	k

Load Factors
1.250
1.500
1.750

Factored Loads		
Interior Beam, P1	Exterior Beam, P2	
166.525	203.495	k
18.374	18.374	k
167.342	185.806	k
352.241	407.675	k

	Unfactored Load
Distributed Pier Diaphragm Weight	0.001 k/ft

Load Factors
1.250

Factored Load	
0.001	k/ft

Bar Size for the Side Reinforcing Bars: 7 Currently not used

Concrete Strength, f_c	3.500	ksi
Reinforcement Yield Strength, f_y	60.000	ksi
Reinforcement Modulus of Elasticity, E_s	29000.000	ksi
Flexure Resistance Factor, ϕ_r	0.900	Begin by assuming a tension-controlled section, $\phi = 0.9$ -- Aashto Lrfd 5.5.4.2
Shear Resistance Factor, ϕ_v	0.900	
Exposure Factor, γ_e (Typically 1.00)	1.000	Class 1 and 2 exposure factors are 1.00 and 0.75 respectively
Concrete Unit Weight, γ_c	0.150	kcf

Intermediate Calculations

Modular Ratio, n	8.000	
Height of Tapered Section, H3	3.000	ft
Distance from C.L. Column to Interior Beam, X1	4.588	ft
Dist. from C.L. Column to Effective Column Face, R _E	0.785	ft

If only one beam is on the overhang then this is the distance to the exterior beam
Calculation is slightly different depending on pier type

	Critical Points			Fifth Points Along Taper						
	A	B	C	0	1	2	3	4		5
Dist. from C.L. Column to Point of Interest, X	0.785	4.588	13.313	1.750	4.600	7.450	10.300	13.150	16.000	ft
Dist. from Cap End to Point of Interest, X1+X2+X3-X	15.215	11.413	2.688	14.250	11.400	8.550	5.700	2.850	0.000	ft
Section Height, Hx	7.000	6.403	4.566	7.000	6.400	5.800	5.200	4.600	4.000	ft
Estimat'd Dist. from Cap Bot. to C.G. of Bar Group, d _s	6.442	5.844	4.007	6.442	5.842	5.242	4.642	4.042	3.442	ft
Factored Shear, V _u , due to P1	352.24	352.24	0.00	352.24	0.00	0.00	0.00	0.00	0.00	k
Factored Shear, V _u , due to P2	407.67	407.67	407.67	407.67	407.67	407.67	407.67	407.67	0.00	k
Factored Shear, V _u , due to Diaphragm	0.02	0.01	0.00	0.02	0.01	0.01	0.01	0.00	0.00	k
Factored Shear, V _u , due to Pier Cap	55.86	38.96	7.55	51.43	38.90	27.49	17.21	8.04	0.00	k
Total Factored Shear, V _u	815.80	798.88	415.23	811.37	446.59	435.18	424.89	415.72	0.00	k
Factored Moment, Mu due to P1	1339.25	0.00	0.00	999.48	0.00	0.00	0.00	0.00	0.00	k*ft
Factored Moment, Mu due to P2	5106.98	3556.96	0.00	4713.74	3551.87	2389.99	1228.12	66.25	0.00	k*ft
Factored Moment, Mu due to Diaphragm	0.14	0.08	0.00	0.13	0.08	0.05	0.02	0.01	0.00	k*ft
Factored Moment, Mu due to Pier Cap	384.90	205.17	9.93	333.15	204.69	110.34	46.91	11.19	0.00	k*ft
Total Factored Moment, Mu	6831.28	3762.22	9.93	6046.50	3756.63	2500.38	1275.05	77.45	0.00	k*ft

Estimate Flexural R/I Required

	Critical Points			Fifth Points Along Taper						
	A	B	C	0	1	2	3	4		5
Rough Estimate of A _s required at each section	21.010	12.452	0.046	18.438	12.439	9.154	5.204	0.355	0.000	in ²

Rough Estimate of Maximum A _s required	21.010	in ²
Estimate of the number of bars required for bar sizes:		
#7	36	
#8	27	
#9	22	
#10	17	
#11	14	

Note: The flexural reinforcement information on the left is an estimate of what is required for the overhang. In the next section of the spreadsheet the user can enter the actual reinforcement to be used in the design checks.

Enter Flexural and Shear R/I for Design Checks

Stirrup Bar Size (i.e. #4, #5, etc.)	5	
Number of Stirrup Legs (Typ. 4 legs for double hoops)	4	
Total Area of Shear Stirrups	1.240	in ²

Stirrup spacing is entered later.

Bar Size for Flexural Reinforcement (i.e. #9, #10, etc.)	11
--	----

Layer	d' (in) by Layer	No. of Bars per Layer
1	3.5	8
2	7.5	8
3	11.5	4
4	15.5	

Total Bar Area Input, A _s provided	31.200	in ²
Distance from Top of Cap to C.G. of Bar Group, d'	6.700	in

Total bar area is lumped at its center of gravity.

Crack Control and S&T Reinforcement

Crack Control: Flexure R/I Aashto Lrfd 5.7.3.4. Spacing should also comply with Aashto Lrfd 5.10.3.1 and 5.10.3.2. See cell G56 to change the Exposure Factor, γ_e , which is typically set to 1.00 (Class 1) for pier caps.

	Critical Points			Fifth Points Along Taper						
	A	B	C	0	1	2	3	4		5
Concrete Cover Thickness to R/I Center, d_c	3.500	3.500	3.500	3.500	3.500	3.500	3.500	3.500	3.500	in
β_s	1.062	1.068	1.097	1.062	1.068	1.076	1.085	1.097	1.112	
Service Moment, M_s due to P1	916.660	0.000	0.000	684.101	0.000	0.000	0.000	0.000	0.000	k*ft
Service Moment, M_s due to P2	3522.872	2453.645	0.000	3251.606	2450.129	1648.652	847.175	45.698	0.000	k*ft
Service Moment, M_s due to Diaphragm	0.116	0.065	0.004	0.102	0.065	0.037	0.016	0.004	0.000	k*ft
Service Moment, M_s due to Pier Cap	307.920	164.139	7.941	266.520	163.750	88.271	37.526	8.955	0.000	k*ft
Total Service Moment, M_s	4747.567	2617.849	7.945	4202.329	2613.944	1736.960	884.717	54.657	0.000	k*ft
Reinforcement Ratio, ρ	0.00961	0.01059	0.01545	0.00961	0.01060	0.01181	0.01334	0.01532	0.01799	
Factor for Distance to Neutral Axis, k	0.323	0.336	0.389	0.323	0.336	0.350	0.367	0.387	0.412	
Reinforcement Stress at Service Level	26.469	16.165	0.073	23.429	16.148	12.025	6.962	0.498	0.000	ksi
Max. Spacing of Bot Layer of Pos. Flexural R/I, s	17.9	33.5	8730.1	21.1	33.6	47.1	85.7	1275.4	n/a	in

Crack Control: Skin R/I Aashto Lrfd 5.7.3.4. Spacing should also comply with Aashto Lrfd 5.10.3.1 and 5.10.3.2.

	Critical Points			Fifth Points Along Taper						
	A	B	C	0	1	2	3	4		5
Is Skin R/I Required ? (Is $d_s = d_c > 3.00'$?)	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	
Area of Skin R/I Required per Face, A_{sk}	0.568	0.482	0.217	0.568	0.481	0.395	0.308	0.222	0.136	in ² /ft
Max Spacing of Skin R/I Required	12.000	11.689	8.015	12.000	11.683	10.483	9.283	8.083	6.883	in

Shrinkage and Temp. R/I Aashto Lrfd 5.10.8. Spacing should also comply with Aashto Lrfd 5.10.3.1 and 5.10.3.2.

Area of Skin R/I Required per Face, A_{sk}	0.303	0.294	0.258	0.303	0.294	0.284	0.272	0.258	0.243	in ² /ft
Max Spacing of Skin R/I Required	12.000	12.000	12.000	12.000	12.000	12.000	12.000	12.000	12.000	in

Fatigue in Reinforcement

Aashto Lrfd 5.5.3

Office policy is to neglect checking fatigue.

Column Design: RC-Pier

$$\text{Column Area} = (17')*(3') + (\pi)*(1.5')^2 = 58.069 \text{ ft}^2$$

The equivalent rectangular column used in RC-Pier has a slightly larger area since I rounded the column length:

$$\text{Equivalent Column Area, } A_g = (19.5')*(3') = 58.5 \text{ ft}^2$$

$$\text{Column R/I Area, } A_s = (46 \text{ bars})*(1.27 \text{ in}^2) = 58.42 \text{ in}^2 = 0.40569 \text{ ft}^2 \quad \text{from the plans}$$

$$\% \text{ R/I} = [(0.40569 \text{ ft}^2)/(58.5 \text{ ft}^2)]*(100) = 0.693\%$$

Aashto Lrfd 5.7.4.2 specifies that the minimum area of R/I shall be:

$$(A_s*f_y)/(A_g*f'_c) \geq 0.135$$

$$[(0.40569 \text{ ft}^2)*(60 \text{ ksi})]/[(58.5 \text{ ft}^2)*(3.5 \text{ ksi})] = 0.1189 < 0.135 \quad \text{-- The current column needs more R/I.}$$

Typically $f'_c = 3.5 \text{ ksi}$ and $f_y = 60 \text{ ksi}$ so that the minimum area of reinforcement equation may be rewritten as:

$$(A_s*f_y)/(A_g*f'_c) \geq 0.135$$

$$(A_s)/(A_g) \geq (0.135)*(f'_c / f_y) = (0.135)*[(3.5 \text{ ksi})/(60 \text{ ksi})] = 0.007875 \quad \text{or} \quad 0.7875\%$$

Aashto Lrfd 5.7.4.2 does allow the area of column R/I to drop below 0.7875% for bridges in seismic zone 1, but a reduced effective column area must be used. The code says that the minimum percentage of R/I area of the reduced effective column area is to be the greater of 1% or the value from the equation above. Additionally the reduced effective area and the gross area must be capable of resisting all loads.

Note that the equation above reaches 1% when $f'_c = 4.444 \text{ ksi}$

$$(A_s)/(A_g) \geq (0.135)*(f'_c / f_y) = (0.135)*[(4.444 \text{ ksi})/(60 \text{ ksi})] = 0.0100 \quad \text{or} \quad 1.00\%$$

So, in order for us to achieve 1.00% our effective column area must be:

$$A_e = (A_s)/(0.01) = (0.40569 \text{ ft}^2)/(0.01) = 40.57 \text{ ft}^2$$


BDM 6.6.4.1.2.1 says, "For frame pier columns the designer shall provide the minimum reinforcing required by the AASHTO LRFD Specifications [AASHTO-LRFD Equation 5.7.4.2-3], without reduction in column cross section. For T-pier columns in Seismic Zone 1 the designer may reduce reinforcing based on a reduced cross section [AASHTO-LRFD 5.7.4.2]."

In order to mimic a reduced column area without actually reducing the cross-sectional column area is to reduce the concrete strength proportionally. RC-Pier does this automatically. spColumn does this when you specify the column as architectural rather than structural. The proportionality ratio in this case would be $(0.693\%)/(1\%) = 0.693$. [See the July 2009 Bridge Newsletter for more information.] Another way to reduce column area would be to remove some of the concrete from the center of the column; however, there doesn't appear to be a simple way to do this in a software package. One additional method that has been used by the DOT is to reduce the column dimensions. This method is typically more conservative than the other methods since changing the column dimensions changes the effective depth of the column. This method is illustrated on the following page.

$$A_g = (19.5')*(3') = 58.5 \text{ ft}^2$$

$$A_s = (46 \text{ bars})*(1.27 \text{ in}^2) = 58.42 \text{ in}^2 = 0.40569 \text{ ft}^2$$

$$A_e = (A_s)/(0.01) = (0.40569 \text{ ft}^2)/(0.01) = 40.57 \text{ ft}^2$$



$$40.57 \text{ ft}^2 = [(3')*(\text{Reduction Factor})]*[(19.5')*(\text{Reduction Factor})]$$

$$\text{Reduction Factor} = [(40.57 \text{ ft}^2)/((3')*(19.5'))]^{0.5} = 0.8328$$


Effective Column Dimensions

$$\text{Length} = (19.5')*(0.8328) = 16.239'$$

$$\text{Width} = (3.0')*(0.8328) = 2.498'$$



$$\text{Effective Column Area} = (16.239')*(2.498') = 40.57 \text{ ft}^2$$

$$\% R/I = [(0.40569 \text{ ft}^2)/(40.57 \text{ ft}^2)]*(100) = 1.00\%$$



The next step with this method would involve putting the effective dimensions in spColumn along with the reinforcement. Next the user would input the column loads and check if the column performance ratios were okay.

For this example I'll just run the equivalent column diameter with the column reinforcement shown in the plan.



Column R/I can be auto-designed; however, I manually entered the column R/I that was specified on the plans.

The effective length factors were entered manually.

RC-Pier calculates magnification factors a little differently than Aashto. For instance, only the sidesway term is used for unbraced frames.

Column Design

COLUMN DESIGN - Column: 1

Code: AASHTO LRFD 2007

Units: US

Pier View: Upstation.

Design/Analysis Method: Moment Magnification - Unbraced Column.

I've included some portions of RC-Pier's output for the column design.

Column Type: Rectangular 234.00 x 36.00 in

Column Section Properties

Sec.	Area ft ²	I _{xx} in ⁴	I _{zz} in ⁴
1	58.50	909792.00	38438712.00

DESIGN PARAMETERS

$f_c = 3500.0$ psi	$f_y = 60000.0$ psi
$\phi_{tens} = 0.90$	$\phi_{comp} = 0.75$
Tens below = 0.375	Comp Above = 0.600
$E_c = 3586.6$ ksi	$E_s = 29000$ ksi
Concrete Type : Normal Weight.	

Reinforcement

Rebar Pattern: Rectangular

Rebar Orientation: Face Parallel

Reinforcement Schedule

Layer	Dir	Size	No. bars	Bar Dist in
1	X	10	20	3.13
1	Z	10	5	3.13

Reinforcement summary

Main bars summary:

46 # 10 bars

Total number of bars in the column: 46

Ties size: # 4

Moment Magnification calculation - Mx (global)							
Loc ft	Comb	K	Cm	Beta	Delta B	Delta S	pPc kips
0.00	85	2.1000	1.0000	0.1575	—	1.1146	14604.97
30.00	85	2.1000	1.0000	0.6947	—	1.1520	9974.88
0.00	173	2.1000	1.0000	0.0700	—	1.0711	15798.65
30.00	173	2.1000	1.0000	1.0000	—	1.1139	8452.30

Moment Magnification calculation - Mz (global)							
Loc ft	Comb	K	Cm	Beta	Delta B	Delta S	pPc kips
0.00	85	2.1000	1.0000	0.0981	—	1.0023	650409.57
30.00	85	2.1000	1.0000	0.0903	—	1.0020	655084.70
0.00	173	2.1000	1.0000	0.3725	—	1.0020	520387.48
30.00	173	2.1000	1.0000	0.4731	—	1.0018	484840.86

Design values used after Moment Magnification (e-min effect included).								
Loc ft	Comb	Fx kips	Fy kips	Fz kips	Mx kips-ft	My kips-ft	Mz kips-ft	
0.00	85	25.5	1501.4	30.9	1101.9	0.0	-7213.6	
30.00	85	-25.5	1316.3	-30.9	-212.3	0.0	6445.8	
0.00	173	23.3	1049.3	-78.0	-2381.9	-0.0	-1899.4	
30.00	173	-20.8	864.2	61.6	134.8	-0.0	1229.6	

COLUMN DESIGN								
Bot/Top Elev. ft	Comb	Pu kips	Mux kips-ft	Muz kips-ft	pMn kips-ft	Incl deg	pPn/Pu	pMn/Mu
0.00	173	1049.3	2381.9	1899.4	6426.1	38.57	1.00	2.10926**
30.00	85	1316.3	212.3	6445.8	34455.6	88.11	1.00	5.34252**

Column passes. The controlling combination is plotted from RC-Pier a couple of pages over.

The result is flagged because the minimum reinforcement ratio has been violated.

COLUMN DESIGN				
Bot/Top Elev. ft	Comb	As_min in^2	As_max in^2	As_req in^2
0.00	173	66.34	673.92	66.34
30.00	85	66.34	673.92	66.34

K values for all columns used in unbraced moment magnification


Column	K _x	K _z
1	2.10	2.10

Column Design : Notes

Min reinforcement = 0.7875 % of $A_g = 66.34 \text{ in}^2$.

** Minimum/Maximum requirement for reinforcement ratio violated.

— Values do not exist at that location as computation is done at the top and bottom of clear length of column.



$$P_u = 1049.28 \text{ k}$$

$$M_u = [(2381.9 \text{ k}\cdot\text{ft})^2 + (1899.4 \text{ k}\cdot\text{ft})^2]^{0.5} = 3046.50 \text{ k}\cdot\text{ft}$$

$$P_R = \phi M_n / M_u = (6426.1 \text{ k}\cdot\text{ft}) / (3046.50 \text{ k}\cdot\text{ft}) = 2.109$$

Column Design: spColumn v4.50

spColumn Input Screens

General Information [X]

Labels
Project: 1203 Jefferson
Column: Column Bot Engineer: MN

Units: English Run Option: Investigation
 Metric Design

Run Axis: About X-Axis Design Code: ACI 318-08
 About Y-Axis ACI 318-05
 Biaxial ACI 318-02
 CSA A23.3-04
 CSA A23.3-94

Consider slenderness? Yes No

[OK] [Cancel]

Material Properties [X]

Concrete
Strength, f_c : 3.5 ksi
Elasticity, E_c : 3372.1 ksi
Max stress, f_c : 2.975 ksi
Beta(1): 0.85
Ultimate strain: 0.003

Reinforcing Steel
Strength, f_y : 60 ksi
Elasticity, E_s : 29000 ksi

[OK] [Cancel]

Rectangular Section [X]

Width (along X): 234 in
Depth (along Y): 36 in

[OK] [Cancel]


Sides Different [X]

	Top	Bottom	Left	Right
No. of bars:	20	20	3	3
Bar size:	#10	#10	#10	#10
Clear cover:	2	2	2	2

Cover to: Transverse bars Longitudinal bars


[OK] [Cancel]

spColumn Input Screens



The 'Confinement' dialog box has a title bar with a close button. It contains a 'Confinement' dropdown menu set to 'Other'. Below it is a section for 'Capacity Reduction Factors, Phi' with three input fields: 'Axial compression (a):' set to 0.8, 'Tension-controlled failure (b):' set to 0.9, and 'Compression-controlled failure (c):' set to 0.75. A 'Tie Sizes' section follows with two rows of dropdown menus: '#4' ties with '#10' bars or smaller, and '#4' ties with larger bars. At the bottom are 'OK' and 'Cancel' buttons.


Confinement was set to "Other" in order to input modify the default Compression-controlled failure value to 0.75 for Aashto requirements.



The 'Factored Loads' dialog box has a title bar with a close button. It features a table with columns 'Load', 'X-Moment', and 'Y-Moment'. The values are 1049.28 (kip), 2381.9 (k-ft), and 1899.4 (k-ft) respectively. Below the table are 'Insert', 'Modify', and 'Delete' buttons. A larger table below shows a single row with columns 'No.', 'P', 'Mx', and 'My', containing the values 1, 1049.28, 2381.9, and 1899.4. At the bottom are 'OK' and 'Cancel' buttons.

These are the loads as found in Combination 173 from RC-Pier.

When executing the solver the program asks if the column should be treated as architectural or structural since the reinforcement ratio is less than 1%. As was done for this example, the user should generally select architectural.



The 'Note' dialog box has a title bar with a close button and a question mark icon. The text reads: 'Reinforcement ratio is less than 1%. Consider column as Architectural (i.e. f_c is reduced by reinforcement ratio)?'. At the bottom are 'Yes', 'No', and 'Cancel' buttons.

spColumn Output Screens

```

                                oooooo          o
                                oo   oo        oo
ooooo  ooooooo  oo          oooooo  oo   oo   o ooooooooooooo  o oooooo
oo   o  oo  oo  oo          oo  oo  oo          oo  oo  oo  oo  oo  oo  oo  oo
oo          oo  oo  oo          oo  oo  oo          oo  oo  oo  oo  oo  oo  oo  oo
oooooo  oo  oo  oo          oo  oo  oo          oo  oo  oo  oo  oo  oo  oo  oo
          oo  ooooooo  oo          oo  oo  oo          oo  oo  oo  oo  oo  oo  oo
o   oo  oo          oo  oo  oo  oo  oo  oo  oo  o   oo  oo  oo  oo  oo  oo  oo
ooooo  oo          ooooooo  oooooo  ooo  oooooo  o  oo  oo  oo  oo  oo  oo (TM)

```

```

=====
                                spColumn v4.50 (TM)
Computer program for the Strength Design of Reinforced Concrete Sections
Copyright © 1988-2009, STRUCTUREPOINT, LLC.
All rights reserved
=====

```

Licensee stated above acknowledges that STRUCTUREPOINT (SP) is not and cannot be responsible for either the accuracy or adequacy of the material supplied as input for processing by the spColumn computer program. Furthermore, STRUCTUREPOINT neither makes any warranty expressed nor implied with respect to the correctness of the output prepared by the spColumn program. Although STRUCTUREPOINT has endeavored to produce spColumn error free the program is not and cannot be certified infallible. The final and only responsibility for analysis, design and engineering documents is the licensee's. Accordingly, STRUCTUREPOINT disclaims all responsibility in contract, negligence or other tort for any analysis, design or engineering documents prepared in connection with the use of the spColumn program.

spColumn Output Screens

```

STRUCTUREPOINT - spColumn v4.50 (TM)
Licensed to: Iowa Department of Transportation. License ID: 56461-1020268-4-29625-22F82
W:\Highway\Bridge\Automation\Development\LRFD_T-Pier\1203 Jefferson 2010-10-10\spCol1001.col
Page 2
09/29/10
12:56 PM

General Information:
=====
File Name: W:\Highway\Bridge\Automation\Development\LRFD_T-Pier\1203 Jefferson 2010-... \spCol1001.col
Project: 1203 Jefferson
Column: Column Bot
Code: ACI 318-08
Engineer: MN
Units: English

Run Option: Investigation
Run Axis: Biaxial
Slenderness: Not considered
Column Type: Architectural

Material Properties:
=====
f'c = 3.5 ksi
Ec = 3372.17 ksi
Ultimate strain = 0.003 in/in
Beta1 = 0.85
fy = 60 ksi
Es = 29000 ksi

Section:
=====
Rectangular: Width = 234 in
Depth = 36 in

Gross section area, Ag = 8424 in^2
Ix = 909792 in^4
rx = 10.3923 in
Xo = 0 in
Iy = 3.84387e+007 in^4
ry = 67.55 in
Yo = 0 in

Reinforcement:
=====
Bar Set: ASTM A615
Size Diam (in) Area (in^2) Size Diam (in) Area (in^2) Size Diam (in) Area (in^2)
-----
# 3 0.38 0.11 # 4 0.50 0.20 # 5 0.63 0.31
# 6 0.75 0.44 # 7 0.88 0.60 # 8 1.00 0.79
# 9 1.13 1.00 # 10 1.27 1.27 # 11 1.41 1.56
# 14 1.69 2.25 # 18 2.26 4.00

Confinement: Other; #4 ties with #10 bars, #4 with larger bars.
phi(a) = 0.8, phi(b) = 0.9, phi(c) = 0.75

Layout: Rectangular
Pattern: Sides Different (Cover to transverse reinforcement)
Total steel area: As = 58.42 in^2 at rho = 0.69% (Note: rho < 1.0%)
Minimum clear spacing = 6.16 in

Top Bottom Left Right
-----
Bars 20 #10 20 #10 3 #10 3 #10
Cover(in) 2 2 2 2

Factored Loads and Moments with Corresponding Capacities:
=====
Pu Mux Muy fMnx fMny fMn/Mu NA depth Dt depth eps_t Phi
No. kip k-ft k-ft k-ft k-ft
-----
1 1049.28 2381.90 1899.40 5093.23 4061.50 2.138 8.75 39.59 0.01341 0.900


*** End of output ***

```

Architectural was selected.

This is a good match between the calculated performance ratios from spColumn and RC-Pier. If the column had been treated as structural rather than architectural in spColumn then the performance ratio would have been 2.204.

spColumn Interaction Diagram



REINFORCEMENT:
 =====
 46 #10 bars @ 0.693%
 $A_s = 58.42$ in²
 Confinement: Other
 Clear Cover = 2.50 in
 Min Clear Spacing = 6.16 in
SLENDERNESS:
 =====
 N/A

Aashto Lrfd 5.7.4.4 and 5.5.4.2

$$P_r = \phi P_n = \phi \phi_a P_o \quad \text{where } P_o = 0.85 * f'_c * (A_g - A_{st}) + f_y * A_{st}$$

Ratio f'_c for Architectural column considerations – see discussion on previous pages (use ratio of 0.69349):

$$P_n = 0.80 * [(0.85) * (0.69349 * 3.5 \text{ ksi}) * (8424 \text{ in}^2 - 58.42 \text{ in}^2) + (60 \text{ ksi}) * (58.42 \text{ in}^2)] = 16,611.7 \text{ k}$$

$$\phi_b = 0.90 \text{ for tension-controlled}$$

$$\phi_c = 0.75 \text{ for compression-controlled}$$

$$\phi_a = 0.80$$

$$P_r = \phi_c P_n = (0.75) * (16,611.7 \text{ k}) = 12,458.8 \text{ k}$$

Moment Magnification Calculations

Moment Magnification Calculations for Load Combination 173 for Bottom of Column
Aashto Lrfd 5.7.4.3 and 4.5.3.2.2b

Factored Load Reactions from RC-Pier

$$\begin{aligned}F_y &= 1049.28 \text{ k} \\M_x &= -2223.75 \text{ k}\cdot\text{ft} \\M_z &= -1895.61 \text{ k}\cdot\text{ft}\end{aligned}$$

RC-Pier assumes minimum eccentricity according to Aashto Std. Spec. 8.16.5.2.8

$$\begin{aligned}e_{\min z} &= 0.6 + 0.03 \cdot h = 0.6 + (0.03) \cdot (234'') = 7.62'' = 0.635' \\M_{x_min} &= (F_y) \cdot (e_{\min z}) = (1049.28 \text{ k}) \cdot (0.635') = 666.293 \text{ k}\cdot\text{ft}\end{aligned}$$

$$\begin{aligned}e_{\min z} &= 0.6 + 0.03 \cdot h = 0.6 + (0.03) \cdot (36'') = 1.68'' = 0.140' \\M_{z_min} &= (F_y) \cdot (e_{\min z}) = (1049.28 \text{ k}) \cdot (0.140') = 146.899 \text{ k}\cdot\text{ft}\end{aligned}$$

Factored Loads Considered

$$\begin{aligned}F_y &= 1049.28 \text{ k} \\M_x &= -2223.75 \text{ k}\cdot\text{ft} \\M_z &= -1895.61 \text{ k}\cdot\text{ft}\end{aligned}$$

Moment Magnification from Aashto Lrfd 4.5.3.2.2b with RC-Pier Modifications

$$\begin{aligned}M_c &= \delta_b M_{2b} + \delta_s M_{2s} && \text{RC-Pier modifies this equation for unbraced frames by assuming} \\M_c &= \delta_s M_2 && \text{that all moments are to be magnified by } \delta_s \text{ alone.}\end{aligned}$$

where $\delta_s = 1 / [1 - \Sigma P_u / (\phi_k \cdot \Sigma P_e)]$

$$\phi_k = 0.75$$

Stiffness reduction factor for concrete

$$P_e = \pi^2 \cdot EI / (k \cdot l_u)^2$$

Euler buckling load

$$EI = (E_c \cdot I_g / 2.5) / (1 + \beta_d)$$

Flexural column stiffness

β_d is ratio of maximum factored dead load moment to maximum factored total moment, always positive

Calculate $\beta_d = | \text{Maximum Factored Dead Load Moment} / \text{Maximum Factored Total Load Moment} |$

Loads from RC-Pier

Unfactored Self-weight

$$\begin{aligned}F_y &= 377.01 \text{ k} \\M_x &= 0.00 \text{ k}\cdot\text{ft} \\M_z &= 0.00 \text{ k}\cdot\text{ft}\end{aligned}$$

Unfactored DC loads

$$\begin{aligned}F_y &= 858.46 \text{ k} \\M_x &= 0.00 \text{ k}\cdot\text{ft} \\M_z &= 0.00 \text{ k}\cdot\text{ft}\end{aligned}$$

Factored Self-weight (Load factor = 0.90)

$$\begin{aligned}F_y &= 339.309 \text{ k} \\M_x &= 0.00 \text{ k}\cdot\text{ft} \\M_z &= 0.00 \text{ k}\cdot\text{ft}\end{aligned}$$

Factored DC loads (Load factor = 0.90)

$$F_y = 772.614 \text{ k}$$

$$M_x = 0.00 \text{ k*ft}$$

$$M_z = 0.00 \text{ k*ft}$$

Factored Self-weight + DC loads

$$F_y = 1111.923 \text{ k}$$

$$M_x = 0.00 \text{ k*ft}$$

$$M_z = 0.00 \text{ k*ft}$$

Check M_{\min} due to minimum eccentricity ($e_{\min x} = 0.635'$, $e_{\min z} = 0.140'$)

$$M_{x_{\min}} = (1111.923 \text{ k}) * (0.140') = 155.669 \text{ k*ft}$$

$$M_{z_{\min}} = (1111.923 \text{ k}) * (0.635') = 706.071 \text{ k*ft}$$

Factored Loads considered for β_d

$$F_y = 1111.923 \text{ k}$$

$$M_x = 155.669 \text{ k*ft}$$

$$M_z = 706.071 \text{ k*ft}$$

β_d Calculations

$$\beta_{dx} = | (155.669 \text{ k*ft}) / (-2223.75 \text{ k*ft}) | = 0.070003$$

$$\beta_{dz} = | (706.071 \text{ k*ft}) / (-1895.61 \text{ k*ft}) | = 0.372477$$

Calculate $EI = (E_c * I_g / 2.5) / (1 + \beta_d)$

$$E_c = (33) * (150 \text{ pcf})^{1.5} * (3500 \text{ psi})^{0.5} * [(144 \text{ in}^2/\text{ft}^2) / (1000 \text{ lb/k})] = 516,472.7 \text{ ksf}$$

$$I_{gx} = (1/12) * b * h^3 = (1/12) * (19.5') * (3.0')^3 = 43.875 \text{ ft}^4$$

$$I_{gz} = (1/12) * h * b^3 = (1/12) * (3.0') * (19.5')^3 = 1853.71875 \text{ ft}^4$$

$$EI_x = [(516,472.7 \text{ ksf}) * (43.875 \text{ ft}^4) / 2.5] / (1 + 0.070003) = 8,471,093.9 \text{ k*ft}^2$$

$$EI_z = [(516,472.7 \text{ ksf}) * (1853.71875 \text{ ft}^4) / 2.5] / (1 + 0.372477) = 279,026,935.3 \text{ k*ft}^2$$

Calculate $P_e = (\pi^2 * EI) / (k * l_u)^2$ $k_x = 2.1$, $k_z = 2.1$, $l_u = 30.0'$

$$P_{ex} = [(\pi^2) * (8,471,093.9 \text{ k*ft}^2)] / [(2.1) * (30.0')]^2 = 21,064.839 \text{ k}$$

$$P_{ez} = [(\pi^2) * (279,026,935.3 \text{ k*ft}^2)] / [(2.1) * (30.0')]^2 = 693,848.695 \text{ k}$$

Calculate $\delta_s = 1 / [1 - \Sigma P_u / (\phi_k * \Sigma P_e)]$

$$\delta_{sx} = 1 / [1 - (1049.28 \text{ k}) / [(0.75) * (21,064.839 \text{ k})]] \\ = 1.0711$$

$$\delta_{sz} = 1 / [1 - (1049.28 \text{ k}) / [(0.75) * (693,848.695 \text{ k})]] \\ = 1.0020$$

Factored Loads with Magnification for Column Bottom


$$F_y = 1049.28 \text{ k}$$


$$M_x = (-2223.75 \text{ k*ft}) * (1.0711) = -2381.9 \text{ k*ft}$$

$$M_z = (-1895.61 \text{ k*ft}) * (1.0020) = -1899.4 \text{ k*ft}$$

Case 2 Loading for Cap and Column Design


RC-Pier screen captures for Case 2 loading for the cap and column will be provided below. I'm only going to show the differences from the Case 1 loading. The only differences include the WA and WS loadings. For this example Case 2 loading does not affect the design of the cap since the cap loading between Case 1 and 2 is the same. The column loading will be different, but the difference for this example is minimal. In fact, the bottom of column design performance ratios for Case 1 and 2 are 2.10928 and 2.14158, respectively. For Case 1 load combination 173 controls whereas for Case 2 load combination 167 controls. The Case 1 and 2 loadings will display more difference with respect to the footing which is covered later in this example.





All the loads from Case 1 apply to Case 2. The differences between the two cases have to do with:

- 1.) The magnitude and the point of application of the WA bouyancy loads and the inclusion of a stream flow load.
- 2.) The point of application of the WS load on the column changes.



WA1

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	UDL	Y	3.6500	0.0000	0.0000	0.4590	k/ft
1	Trapezoidal	X	0.0000	0.0000	0.2510	0.4590	k/ft
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units

Strain Load

Unit:

+ Expansion - Contraction

Name:

Description:

Factors: Multiplier for Loads:

Auto Generation:

Import Loads:

Note: Vertically downward loads be added as negative loads in Y direction.

The water loads that affect the column and cap design for Case 2 are the buoyancy and stream loads on the column. So, Case 2 is different from Case 1 in that there is a stream flow load and the depth of buoyancy has increased.

The spreadsheet that was setup to calculate WA loads will not generate standardized text files in order to import the loads.

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	X	-3.8990
1	1	Y	-2.1450
1	1	Z	3.9670
1	2	X	-3.8990
1	2	Y	0.0000
1	2	Z	3.9670
1	3	X	-3.8990
1	3	Y	0.0000
1	3	Z	3.9670
1	4	X	-3.8990
1	4	Y	0.0000

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	UDL	X	-0.1200	0.4590	0.0000	0.8330	
1	UDL	Z	0.7800	0.4590	0.0000	0.8330	

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L
Force	X	0.0000	-0.9800	0.5000	0.0000	0.0000
UDL	Z	0.0000	0.2450	0.0000	0.0000	1.0000

Strain Load

Unit: 0

+ Expansion - Contraction

Name: WS1

Description:

Factors: Multiplier for Loads: 1

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

There are 8 WS cases (4 cases with uplift and 4 cases without), but I will only show the first one.

Remember that the reversible feature for wind loads was turned off in the library.

Wind loads can be auto-generated, but generating simplified wind loads requires a few tricks and some editing of the load results.

The wind loads above were imported from text file "WSLoadsCase2NoUplift001.txt" which was generated from the in-house spreadsheet for wind loads.

The only difference for Case 2 from Case 1 is the point of application of the wind loads on the column. The water elevation from Case 2 is higher than the fill elevation for Case 1.

```

Bearing Loads
1, 1, X, -3.899
1, 1, Y, -2.145
1, 1, Z, 3.967
1, 2, X, -3.899
1, 2, Y, 0
1, 2, Z, 3.967
1, 3, X, -3.899
1, 3, Y, 0
1, 3, Z, 3.967
1, 4, X, -3.899
1, 4, Y, 0
1, 4, Z, 3.967
1, 5, X, -3.899
1, 5, Y, 0
1, 5, Z, 3.967
1, 6, X, -3.899
1, 6, Y, 2.145
1, 6, Z, 3.967
Cap Loads
Force, X, 0, -0.98, 0.5
UDL, Z, 0.245, 0, 1
Column Loads
1, UDL, X, -0.12, 0.459, 0.833
1, UDL, Z, 0.78, 0.459, 0.833
    
```


Case 3 Loading for Cap and Column Design


RC-Pier screen captures for Case 3 loading for the cap and column will be provided below. I'm only going to show the differences from the Case 1 loading. The only differences include:

- 1.) The Load Group is Extreme Event 2.
- 2.) Changes to the WA loadings.
- 3.) All wind loading can be eliminated since it is not part of Extreme Event 2.
- 4.) Ice loading is added.

For this example Case 3 loading does not control the design of the cap. The main reason for this is that the live load factor for Extreme Event 2 is substantially smaller and the ice loading doesn't affect the cap. For this example Case 3 does not control the column design. In fact, the bottom of column design performance ratios for Case 1 and 3 are 2.10928 and 6.06294, respectively.

It should be noted that the Aashto Lrfd Specifications in Article 1.3.2 seem to allow the resistance factors for many components to be taken as 1.00 for Extreme Events. However, Article 5.7.2 which addresses Strength and Extreme Event Limit States seems to restrict that provision for concrete components in the 1st paragraph of Article 5.7.2.1.





The DC, DW, LL, TU, and BR loads for Case 3 are the same as those for Case 1. The WA load for Case 3 has been modified from Case 1. The WS and WL loads have been eliminated since Extreme Event 2 does not include those loads. The IC loads were added for Case 3.

WA1

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	UDL	Y	3.6500	0.0000	0.0000	0.2860	klf
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units

Strain Load

Unit:

+ Expansion - Contraction

Name:

Description:

Factors: Multiplier for Loads:

Auto Generation:

Import Loads:

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

The water loads that affect the column and cap design for Case 3 are the buoyancy on the column. Case 3 is different from Case 1 in that the depth of buoyancy has increased.

The spreadsheet that was setup to calculate WA loads will not generate standardized text files in order to import the loads.

IC1

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	X	158.0350	0.2860	0.0000	0.0000	kips
1	Force	Z	23.7050	0.2860	0.0000	0.0000	kips
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L

Strain Load

Unit: 0.

+ Expansion - Contraction

Name: IC1

Description:

Factors: Multiplier for Loads: 1.

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

There are a total of 4 load cases for ice. The two cases shown on this page differ only in that the direction of Z ice load is reversed.

The spreadsheet that was setup to calculate IC loads will not generate standardized text files in order to import the loads.

IC2

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	X	158.0350	0.2860	0.0000	0.0000	kips
1	Force	Z	-23.7050	0.2860	0.0000	0.0000	kips
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units

Strain Load

Unit: 0.

+ Expansion - Contraction

Name: IC2

Description:

Factors: Multiplier for Loads: 1.

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

IC3

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
▶			

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
▶ 1	Force	X	79.0170	0.2860	0.0000	0.0000	kips
▶ 1	Force	Z	53.2980	0.2860	0.0000	0.0000	kips
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units
▶							

Strain Load

Unit:

+ Expansion - Contraction

Name:

Description:

Factors: Multiplier for Loads:

Auto Generation:

Import Loads:

Note: Vertically downward loads be added as negative loads in Y direction.

The two cases shown on this page differ only in that the direction of Z ice load is reversed.

IC4

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
▶			

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
▶ 1	Force	X	79.0170	0.2860	0.0000	0.0000	kips
▶ 1	Force	Z	-53.2980	0.2860	0.0000	0.0000	kips
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units
▶							

Strain Load

Unit:

+ Expansion - Contraction

Name:

Description:



Factors: Multiplier for Loads:

Auto Generation:


Import Loads:

Note: Vertically downward loads be added as negative loads in Y direction.

Footing Design



I am going to look at maximum and minimum pile loads only. The footing and fill weight will be placed on the bottom of the column from the "Loads" tab rather than through the entries on the "Footing" tab. Handling loads this way allows me to include these loads in an analysis results file if desired.



Tapered Cap Parameters

Cap Length (X)	49.	ft	Start Elevation:	36.	ft
Length of Non-tapered Segment (X) :	20.5	ft	End Elevation:	36.	ft
Cap Min Height (Y) :	48.	in	Skew Angle (deg):	-32.	
Cap Max Height (Y) :	84.	in			
Cap Depth (Z) :	42.	in			
Factor of Reduced Moment of Inertia:	1.				

OK Cancel

Notice that the column length has been increased by 4.0' from 25' to 29'.

Materials

Concrete Strength		Concrete Density		Concrete Modulus of Elasticity	
psi		pcf		ksi	
Cap:	3500.	Cap:	150.	Cap:	3586.62
Column:	3500.	Column:	150.	Column:	3586.62
Footing:	3500.	Footing:	0.101	Footing:	3586.62

Steel Yield Strength		Concrete Type	
ksi			
Cap (flex):	60.	Cap:	Normal
Cap (shear):	60.	Column:	Normal
Column:	60.	Footing:	Normal
Footing:	60.		

OK Cancel

Set the footing concrete density to a small value so that the self-weight calculated by RC-Pier is negligible.

Structure Model

Objects: Cap Components: 01

Member	Node	Hinge	Check Point	Distance (ft)	Elem Length (ft)
2	3	-		0.00	
	4	-		2.69	2.69
3	4	-		2.69	
	5	-		11.41	8.72
4	5	-		11.41	
	6	-		14.25	2.84
5	6	-		14.25	

Additional Check Points

Add default check points

0. ft From Left

Add Delete Modify (De)Activate

Reset to Base Structure

Reset All

Hinge

Local Direction: Z

Cap design

Flexure	Shear
<input checked="" type="radio"/> Centerline of column	<input checked="" type="radio"/> Centerline of column
<input type="radio"/> Face of support	<input type="radio"/> Face of support
<input type="radio"/> Offset from CL of the column	<input type="radio"/> Offset from CL of the column
<input type="text"/> ft	<input type="text"/> ft

Plastic Hinge locations

Near Column Top

Cap Column joint

At Cap Soffit

Below Cap Soffit ft



Near Column Bottom

At Column Base

Above Column Base ft

OK Cancel

I removed all the additional pier cap check points. This helps speed up the program especially when printing analysis results to a text file.



DC1

Added footing weight as a DC1 load, but also removed the weight due to the 4.0' column extension to counteract the addition of its self-weight: $[(28')*(15') - (19.5')*(3.0')]*(4.0')*(0.150 \text{ kcf}) = 216.9 \text{ k}$

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	Y	-136.7040
1	2	Y	-146.2640
1	3	Y	-146.2640
1	4	Y	-146.2640
1	5	Y	-146.2640
1	6	Y	-136.7040

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	Y	-216.9000	0.0010	0.0000	0.0000	kips

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L

Strain Load

Unit: 0.

Name: DC1

Description:

Factors: Multiplier for Loads: 1.

Note: Vertically downward loads be added as negative loads in Y direction.

The footing weight is placed just above the bottom of the column so that the load will be reflected in the analysis results.

WA1

The buoyancy includes the entire submerged footing, the submerged portion of the column (excluding the 4.0' column extension), and the submerged portion of the soil. Case 1 water depth is 3.4' above top of footing excluding the 4.0' column extension. The fill depth is 10', but only 3.4' is submerged. The soil is assumed to be 1/3 void. $[(28')*(15')*(4')*(0.0624 \text{ kcf}) + [(19.5')*(3.0')*(3.4')*(0.0624 \text{ kcf}) + [(28')*(15') - (19.5')*(3.0')*(3.4')*(2/3)*(0.0624 \text{ kcf})] = 168.374 \text{ k}$

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	Y	168.3740	0.0010	0.0000	0.0000	kips

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L

Strain Load

Unit: 0.

Name: WA1

Description:

Factors: Multiplier for Loads: 1.

Note: Vertically downward loads be added as negative loads in Y direction.

The buoyancy force is placed just above the bottom of the column so that the load will be reflected in the analysis results.

Note that Case 1 does not include any stream flow loads. Note also that the buoyancy load can be entered as a total concentrated load since we are considering the footing.

WS1

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	X	-3.8990
1	1	Y	-2.1450
1	1	Z	3.9670
1	2	X	-3.8990
1	2	Y	0.0000
1	2	Z	3.9670
1	3	X	-3.8990
1	3	Y	0.0000
1	3	Z	3.9670
1	4	X	-3.8990
1	4	Y	0.0000

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	UDL	X	-0.1200	0.4120	0.0000	0.8530	k/ft
1	UDL	Z	0.7800	0.4120	0.0000	0.8530	k/ft

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units
Force	X	0.0000	-0.9800	0.5000	0.0000	0.0000	
UDL	Z	0.0000	0.2450	0.0000	0.0000	1.0000	

Strain Load
Unit: 0.
+ Expansion - Contraction

Name: WS1
Description:

Factors: Multiplier for Loads: 1.
Auto Generation: Generate
Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

Since the column was extended 4.0' to the bottom of the footing, the Start and End locations of the wind loads on the columns were modified.

EV1

Adding fill weight on top of the footing:

$$[(28' * (15') - (19.5') * (3.0')) * (10') * (0.120 \text{ kcf}) = 433.8 \text{ k}$$

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	Y	-433.8000	0.0010	0.0000	0.0000	kips

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units

Strain Load
Unit: 0.
+ Expansion - Contraction

Name: EV1
Description:

Factors: Multiplier for Loads: 1.
Auto Generation: Generate
Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

The fill weight is placed just above the bottom of the column so that the load will be reflected in the analysis results.

RCPier V8i (SELECTseries 1) - W:\Highway\Bridge\Automation\Development\LRFD_T-PierV1203 Jefferson 2010-10-10\FootingDesign\RCPierLRFDftg...

File Show Libraries LEAP Bridge Help

New Open Save Save As Print Image Model Results Diagrams Vehicle Library Load Groups Footing Library Pile Groups Help Bentley Site About E-mail Manual Tutorials

Project Geometry Loads Analysis Cap Column Footing

Run Analysis... Type: Load Case Item: DC1- Units: kips, kips-ft

A/D Parameters Effect: Forces & Moment Format: General Right Filter

Type of Analysis: Frame Strut and Tie Coord. System: Local Global Print...

Memb	Node	Fx	Fy	Fz	Mx	My	Mz
1	1	-0	1075	0	-0	0	-0.0005215
1	2	-0	-858.5	0	-0	0	0.0005215
2	3	0	0	0	0	0	0
2	4	0	0	0	0	0	0
3	4	0	-136.7	0	0	0	0
3	5	0	136.7	0	0	0	-1193
4	5	0	-283	0	0	0	1193
6	6	0	283	0	0	0	-1995
6	7	0	-283	0	0	0	1995
7	7	0	283	0	0	0	-3661
7	8	0	-429.2	0	0	0	3661
2	2	0	429.2	0	0	0	-5534
2	2	0	429.2	0	0	0	5534
8	8	0	-429.2	0	0	0	-3661
8	9	0	283	0	0	0	3661
9	9	0	-283	0	0	0	-1995
9	9	0	283	0	0	0	1995
10	10	0	-283	0	0	0	-1193
10	10	0	136.7	0	0	0	1193
10	11	0	-136.7	0	0	0	0
11	11	0	0	0	0	0	0
11	12	0	0	0	0	0	0

Ready

Click on this for screen below.

All dynamic load allowance factors were set to 0. This would ensure the analysis that if the analysis results were written to a file then impact would be excluded. The results will not be written to a file in this example.

Analysis/Design Parameters (LRFD)

Resistance Factor, phi

Phi as per 2006 classification

Phi as per classic approach

Tension Controlled: 0.9

Shear and torsion: (normal weight) 0.9

Shear and torsion: (lightweight) 0.7

Compression Controlled: (ties) 0.75

Compression Controlled: (spiral) 0.75

Compression in STM: 0.7

Dynamic Load Allowance, IM

	Truck	Lane	Fatigue
Cap:	0.	0.	0.
Column:	0.	0.	0.
Footing:	0.	0.	0.

Crack Control Criteria

LRFD 2004

LRFD 2005 Interims

Fatigue

ff term: 24.

Clear Concrete Cover, in

Cap top/bottom: 2.

Cap side: 2.

Column: 2.

Footing top/bottom: 3.

Footing side: 3.

Multiple Presence Factors

Lane# 1: 1.2

Lane# 2: 1.

Lane# 3: 0.85

Lane# 4: 0.65

Crack Control Factor, z, kips/in

Cap: 170.

Column: 170.

Footing: 130.

Exposure Factors

Cap: 1.

Column: 1.

Footing: 1.

Modulus of rupture

Normal: 0.37 x sqrt(fc)

Sand-lightweight: 0.2 x sqrt(fc)

All-lightweight: 0.17 x sqrt(fc)

Seismic Design

Seismic Design Parameters ...

Column Slenderness Consideration

P-delta Method effective length factors, K

Number of iterations: auto 2.1

Degree of Fixity in Foundations for Moment Magnification 5.

Compute K for braced columns as per Interim 2006

Design cap/footing for magnified moments

Design cap for magnified moments



Design footing for magnified moments

c/dt ratio

Comp -> 0.6 <- Transition -> 0.375 <- Tension

OK Cancel

For this run I'm not concerned about cover requirements since I am not designing footing reinforcement in RC-Pier.



This information is from a library – see following pages.

This is used for graphics display.

See below.

See next page.

Not used in the structural model – it is simply used in the graphic display. I keep the pile short so they don't take up the whole picture.

This value is arbitrary since the Iowa DOT currently bases typical pile designs on the Strength and Extreme Event Combinations.

The software interface includes the following sections:

- Pile Section Types _Components:**
 - Options: User Input, From Library (selected)
 - Pile/Shaft Shape: H-Steel
 - Rotation: 90. °
 - Description: HP10x57
 - Dimensions: W 9.99 in, D 10.22 in, T1 0.565 in, T2 0.565 in
 - Visuals: Round, Square, Chamfer, H-Steel (selected)
- Pile Section Properties:**
 - Area: 0.11667 ft²
 - Ixx: 294. in⁴
 - Izz: 101. in⁴
 - Auto compute:
- Pile/Shaft Configuration:**
 - Pile/Shaft Length: 5. ft
 - Max. Service Pile Capacity: 100. kips
 - Max. Factored Pile Capacity: 145. kips
 - Edit Pile button

HP10x57 Structural Resistance Level 1

Factored Resistance = (6 ksi)*(0.1167 ft²)*(144 in²/ft²)*(1.45) = 146.16 k

BDM Table 6.2.6.1-1 shows (0.6)*(243 k) = 145.8 k

Edit: Pile Locations

Edit mode
 User input
 From Library

Adjust mode
 Use piles as specified
 Adjust piles for end distance
 in

Pile Pattern
 Description:

 Concentric under Footing
 Eccentric under Footing
 X-dir in Z-dir in

 X Grid dists from origin Z Grid dists from origin
 in in


Coordinates

Pile #	X, in	Z, in	Batter degrees
18	18.00	-72.00	0.00
1	78.00	-72.00	0.00
2	138.00	-72.00	0.00
3	198.00	-72.00	0.00
4	258.00	-72.00	0.00
5	318.00	-72.00	0.00
6	18.00	-24.00	0.00
7	78.00	-24.00	0.00
8	138.00	-24.00	0.00
9	198.00	-24.00	0.00
10	258.00	-24.00	0.00
11	318.00	-24.00	0.00
12	18.00	24.00	0.00
13	78.00	24.00	0.00
14	138.00	24.00	0.00
15	198.00	24.00	0.00
16	258.00	24.00	0.00
17	318.00	24.00	0.00
18	18.00	72.00	0.00
19	78.00	72.00	0.00
20	138.00	72.00	0.00
21	198.00	72.00	0.00


Enter pile coordinates. Pile batter was not entered.

Aashto Lrfd 5.13.3.2 talks about piles being out of planned position by 6" or ¼ times the pile diameter and that the center of a group of piles may be 3" from its planned position. This provision does not need to be considered for typical pier designs. [Field construction errors are a separate issue from tolerances.]

According to the Bridge Design Manual a pile battered no more than 1:4 may be assumed to carry the same vertical load as a pile driven vertically; there need be no reduction for angle of the pile.



Pile Type Library



Footing: Isolated Pile/Shaft Design

Footing Definition
 Piles Definition
 Footing Reinforcement

Footing Reinforcement

Dir.	Bar dist. in	Bar Size	Num. Bars	Hook
X	0.5	#8	20	None
Z	0.5	#8	50	None

Strut and Tie Model

Design pile reaction

Computed maximum pile reaction
 User specified maximum pile reaction

Factored kips
 Service kips
 Fatigue kips

Check for Cracking and Fatigue

This button lets you review the pile reactions.

There is not much point in entering footing reinforcement since my footing is only 1" thick and I won't be using RC-Pier for the design of the concrete footing. However, RC-Pier requires the entry in order to get the pile reactions.

ISOLATED FOOTING DESIGN

ISOLATED FOOTING DESIGN

Code: AASHTO LRFD 2007 (with Interims)

Units: US

Pier View: Upstation.

I've included some portions of RC-Pier's output for the footing.

GEOMETRY

Name : PileFtg01

Shape : Rectangular, Type : Pile/Shaft Cap

Bf(X) = 28.00 ft, Hf(Z) = 15.00 ft, Thickness(Y) = 1.00 in

Ag = 420.00 ft², Ix = 480.00 ft⁴, Iz = 1750.00 ft⁴

Footing concentric.

Columns located on the footing:

Column No. 1 at x = 0.00 ft, Rectangular 234.00 in x 36.00 in

Surcharge = 0.00 ksf

Piles: H-Steel Size: W = 9.99 in, D = 10.23 in, T1 = 0.56 in, T2 = 0.56 in

Service Capacity: 100.00 kips Factored Capacity: 145.00 kips

Piles Section Properties: Area = 0.12 ft² Ix = 294.00 in⁴ Iz = 101.00 in⁴

DESIGN PARAMETERS

f_c = 3500.00 psi f_y = 60000.00 psi

phi tens = 0.90

phi comp = 0.75 phi shear = 0.90

Tens below = 0.375 Comp Above = 0.600

E_c = 3586.6 ksi E_s = 29000.0 ksi

Crack check as per 2005 Interims

Crack control Exposure = 1.00

Concrete Type : Normal Weight.

Pile Reactions, Service										
Pile	Loc(X) ft	Loc(Z) ft	X in	Z in	comb	Ovs	P kips	Mxx kft	Mzz kft	Pile Reac. kips
1	-12.50	-1.50	18.00	-72.0	2161	1.000	-2107.08	-1933.70	3711.64	138.48*
					2314	1.000	-1994.80	1933.70	-3710.19	32.44
2	-7.50	-1.50	78.00	-72.0	2161	1.000	-2107.08	-1933.70	3711.64	127.87*
					2314	1.000	-1994.80	1933.70	-3710.19	43.04
3	-2.50	-1.50	138.00	-72.0	2163	1.000	-2184.27	-1933.70	2000.28	118.04*
					2342	1.000	-1973.80	1933.70	-3483.57	53.09
4	2.50	-1.50	198.00	-72.0	2164	1.000	-2184.27	-1933.70	-518.86	115.92*
					2341	1.000	-1973.80	1933.70	2455.39	54.56
5	7.50	-1.50	258.00	-72.0	2190	1.000	-2086.07	-1933.70	-2456.84	121.62*
					2341	1.000	-1973.80	1933.70	2455.39	47.55
6	12.50	-1.50	318.00	-72.0	2190	1.000	-2086.07	-1933.70	-2456.84	128.64*
					2341	1.000	-1973.80	1933.70	2455.39	40.53
7	-12.50	-5.50	18.00	-24.0	2182	1.000	-2086.07	-856.93	5290.85	128.28*
					2363	1.000	-1973.80	856.93	-5289.39	40.89
8	-7.50	-5.50	78.00	-24.0	2182	1.000	-2086.07	-856.93	5290.85	113.17*
					2363	1.000	-1973.80	856.93	-5289.39	56.00
9	-2.50	-5.50	138.00	-24.0	2163	1.000	-2184.27	-1933.70	2000.28	101.93*
					2342	1.000	-1973.80	1933.70	-3483.57	69.21
10	2.50	-5.50	198.00	-24.0	2164	1.000	-2184.27	-1933.70	-518.86	99.81
					2341	1.000	-1973.80	1933.70	2455.39	70.68
11	7.50	-5.50	258.00	-24.0	2246	1.000	-2086.07	-283.46	-4374.92	106.85*
					2285	1.000	-1973.80	283.46	4373.47	62.32
12	12.50	-5.50	318.00	-24.0	2365	1.000	-2086.07	856.93	-5290.84	121.14*
					2180	1.000	-1973.80	-856.93	5289.40	48.03
13	-12.50	-9.50	18.00	24.0	2182	1.000	-2086.07	-856.93	5290.85	121.14*
					2363	1.000	-1973.80	856.93	-5289.39	48.03
14	-7.50	-9.50	78.00	24.0	2287	1.000	-2086.07	283.46	4374.93	106.85*
					2244	1.000	-1973.80	-283.46	-4373.47	62.32
15	-2.50	-9.50	138.00	24.0	2317	1.000	-2184.27	1933.70	518.86	99.81
					2188	1.000	-1973.80	-1933.70	-2455.39	70.68
16	2.50	-9.50	198.00	24.0	2318	1.000	-2184.27	1933.70	-2000.28	101.93*
					2187	1.000	-1973.80	-1933.70	3483.57	69.21
17	7.50	-9.50	258.00	24.0	2365	1.000	-2086.07	856.93	-5290.84	113.17*
					2180	1.000	-1973.80	-856.93	5289.40	56.00
18	12.50	-9.50	318.00	24.0	2365	1.000	-2086.07	856.93	-5290.84	128.28*
					2180	1.000	-1973.80	-856.93	5289.40	40.89
19	-12.50	-13.50	18.00	72.0	2343	1.000	-2086.07	1933.70	2456.85	128.64*
					2188	1.000	-1973.80	-1933.70	-2455.39	40.53
20	-7.50	-13.50	78.00	72.0	2343	1.000	-2086.07	1933.70	2456.85	121.62*
					2188	1.000	-1973.80	-1933.70	-2455.39	47.55
21	-2.50	-13.50	138.00	72.0	2317	1.000	-2184.27	1933.70	518.86	115.92*
					2188	1.000	-1973.80	-1933.70	-2455.39	54.56
22	2.50	-13.50	198.00	72.0	2318	1.000	-2184.27	1933.70	-2000.28	118.04*
					2187	1.000	-1973.80	-1933.70	3483.57	53.09
23	7.50	-13.50	258.00	72.0	2316	1.000	-2107.08	1933.70	-3711.64	127.87*
					2159	1.000	-1994.80	-1933.70	3710.19	43.04
24	12.50	-13.50	318.00	72.0	2316	1.000	-2107.08	1933.70	-3711.64	138.48*
					2159	1.000	-1994.80	-1933.70	3710.19	32.44

Not interested in the Service capacity of the piles at this time.

Pile Reactions, Factored										
Pile	Loc(X) ft	Loc(Z) ft	X in	Z in	comb	Ovs	P kips	Mxx kft	Mzz kft	Pile Reac. kips
1	-12.50	-1.50	18.0	-72.0	3	—	-2878.04	-1112.24	6251.57	178.48*
							219	-1903.26	1112.24	20.76
2	-7.50	-1.50	78.0	-72.0	3	—	-2878.04	-1112.24	6251.57	160.61*
							2090	-1835.90	1812.73	35.48
3	-2.50	-1.50	138.0	-72.0	371	—	-2869.97	-1812.73	1975.42	145.06*
							349	-1510.50	2535.73	34.08
4	2.50	-1.50	198.0	-72.0	372	—	-2869.97	-1812.73	-1425.42	144.28
							349	-1510.50	2535.73	28.40
5	7.50	-1.50	258.0	-72.0	398	—	-2737.75	-1812.73	-4037.92	154.04*
							349	-1510.50	2535.73	22.72
6	12.50	-1.50	318.0	-72.0	398	—	-2737.75	-1812.73	-4037.92	165.57*
							349	-1510.50	2535.73	17.03
7	-12.50	-5.50	18.0	-24.0	3	—	-2878.04	-1112.24	6251.57	169.21*
							2139	-1807.89	480.22	29.23
8	-7.50	-5.50	78.0	-24.0	3	—	-2878.04	-1112.24	6251.57	151.35*
							2139	-1807.89	480.22	46.87
9	-2.50	-5.50	138.0	-24.0	5	—	-3013.12	-1112.24	3256.69	134.83
							349	-1510.50	2535.73	55.21
10	2.50	-5.50	198.0	-24.0	6	—	-3013.12	-1112.24	-1151.81	131.83
							349	-1510.50	2535.73	49.53
11	7.50	-5.50	258.0	-24.0	11	—	-2878.04	-287.12	-5105.73	143.00
							341	-1510.50	1710.61	43.18
12	12.50	-5.50	318.0	-24.0	25	—	-2878.04	1112.24	-6251.56	159.94*
							1956	-1807.89	-480.22	33.24
13	-12.50	-9.50	18.0	24.0	3	—	-2878.04	-1112.24	6251.57	159.94*
							2139	-1807.89	480.22	33.24
14	-7.50	-9.50	78.0	24.0	17	—	-2878.04	287.12	5105.74	143.00
							351	-1510.50	-1710.61	43.18
15	-2.50	-9.50	138.0	24.0	26	—	-3013.12	1112.24	1151.81	131.83
							343	-1510.50	-2535.73	49.53
16	2.50	-9.50	198.0	24.0	27	—	-3013.12	1112.24	-3256.69	134.83
							343	-1510.50	-2535.73	55.21
17	7.50	-9.50	258.0	24.0	25	—	-2878.04	1112.24	-6251.56	151.35*
							1956	-1807.89	-480.22	46.87
18	12.50	-9.50	318.0	24.0	25	—	-2878.04	1112.24	-6251.56	169.21*
							1956	-1807.89	-480.22	29.23
19	-12.50	-13.50	18.0	72.0	551	—	-2737.75	1812.73	4037.93	165.57*
							343	-1510.50	-2535.73	17.03
20	-7.50	-13.50	78.0	72.0	551	—	-2737.75	1812.73	4037.93	154.04*
							343	-1510.50	-2535.73	22.72
21	-2.50	-13.50	138.0	72.0	525	—	-2869.97	1812.73	1425.42	144.28
							343	-1510.50	-2535.73	28.40
22	2.50	-13.50	198.0	72.0	526	—	-2869.97	1812.73	-1975.42	145.06*
							343	-1510.50	-2535.73	34.08
23	7.50	-13.50	258.0	72.0	25	—	-2878.04	1112.24	-6251.56	160.61*
							1935	-1835.90	-1812.73	35.48
24	12.50	-13.50	318.0	72.0	25	—	-2878.04	1112.24	-6251.56	178.48*
							197	-1903.26	-1112.24	20.76

This is greater than the factored resistance of 145.80 k. So, I should modify my pile arrangement or add more piling. I won't do that at this time.

Footing Design : Notes

* Service Force in pile is greater than service pile capacity.

* Factored Force in pile is greater than factored pile capacity.

Only max. force in piles is considered for design.

Pile coordinates X and Z are from the most left edge of the footing.

Plong= Lateral load in longitudinal direction at the top of pile, Kips.

Php= Available resisting horizontal component due to batter= batter * Vertical pile reaction, Kips.

Plong-Php= Remaining lateral force required to resist by pile.

Note that the maximum factored pile reaction is still 178.48 kips in this table. This is because the footing and fill weight were input as DC1 and EV1 loads rather than entered on the footing tab.

Max. Pile Reaction Used in Design: (without selfweight and surcharge)

Factored pile reaction	178.48 kips
Service pile reaction	138.48 kips

Reinforcement Schedule

Dir	Quantity	Size	Bar dist in	As total in ²	Spacing in	Hook
X	20	#8	0.50	15.80	9.11	None
Z	50	#8	0.50	39.50	6.71	None

I've included the rest of the footing output, but I'm not really interested in the concrete footing design portion since I entered a 1" thick footing. Footing design is typically done using a spreadsheet.

Flexure

Dir	Loc	d in	Mmax kft	Comb	CL	Asb_req in ²	Asb_prv in ²	Asb_eff in ²	Ast_req in ²	Ast_prv in ²	Ast_eff in ²
X	-9.75	-2.00	1963.2	25	T	0.00	0.00	0.00	0.14	15.80	15.80
X	9.75	-2.00	1963.2	25	T	0.00	0.00	0.00	0.14	15.80	15.80
Z	-1.50	-2.00	5354.3	25	T	0.00	0.00	0.00	0.25	39.50	39.50
Z	1.50	-2.00	5354.3	25	T	0.00	0.00	0.00	0.25	39.50	39.50

Flexure Note

CL: Section classification as per LRFD 2006 interims for provided reinforcement.

C = Compression controlled, I = In-Transition, T = Tension controlled.

Required reinforcement is based on phi for tension controlled sections..

Cracking check as per AASHTO LRFD 2007 with Interims (2005)

Cracking/Fatigue

Dir	Loc	d	Cracking Mmax	Cracking Comb	Cracking fs	Cracking Sr _q	Cracking Spr	Fatigue Mmax	Fatigue Comb	Fatigue fs	Fatigue ratio fs
	ft	in	kft		ksi	in	in	kft		ksi	
X	-9.75	-2.00	1523.3	2161	0.00	180.0	0.0	0.0	0	0.00	0.00
X	9.75	-2.00	1523.3	2161	0.00	180.0	0.0	0.0	0	0.00	0.00
Z	-1.50	-2.00	4154.3	2161	0.00	336.0	0.0	0.0	0	0.00	0.00
Z	1.50	-2.00	4154.3	2161	0.00	336.0	0.0	0.0	0	0.00	0.00

One Way Shear (Simplified Method)

Col	Dir	Dist ft	Comb	dv in	Vu kips	phi*Vc kips
1	X	-9.81	25	0.72	713.9*	13.8
	X	9.81	25	0.72	713.9*	13.8
	Z	-1.56	25	0.72	2141.7*	25.8
	Z	1.56	25	0.72	2141.7*	25.8

One Way Shear Note

* Shear resistance is less than applied shear force. You may increase the footing depth or provide stirrups.

Two Way Shear

#	Bo ft	Ao ft^2	Comb	Avg. dv in	Vu kips	phi*Vc kips
Columns						
1	45.24	59.85	25	0.72	4263.4*	54.2
Piles - max						
1	3.57	0.80	25	0.72	178.5*	6.5
Piles - min						
1	3.57	0.80	25	0.72	178.5*	6.5

Two Way Shear Note

* Shear resistance is less than applied punching force.

TWO WAY SHEAR IN FOOTING IS NOT DESIGNED AND STIRRUPS ARE NOT CONSIDERED.

Spreadsheet for Footing Design

Application to Design Pile Footings

Developed on 10/16/2006
Last Updated on 8/30/2010

DOT refers to the Iowa Department of Transportation.
OBS refers to the Iowa DOT Office of Bridges and Structures

Disclaimer: This software is intended for use by Iowa DOT personnel and consultants working for the OBS in their development of projects for the Iowa DOT. Any other use is at the sole discretion of the user. The Iowa DOT makes the software available "AS IS" and assumes no liability nor makes any warranty of any kind, including warranties of noninfringement, fitness or merchantability whether expressed or implied, to the accuracy or functionality of this software. By downloading or using this file, you are agreeing to this disclaimer.

The OBS will only support those persons using this software in connection with Iowa DOT related business.

Please report any spreadsheet errors to the Iowa DOT OBS.

This spreadsheet was developed to aid the design of typical Iowa DOT piers. The Iowa DOT Bridge Design Manual (BDM) should be consulted for the most up-to-date policies.

Description:

The purpose of this spreadsheet is to give the user more versatility when designing pile footings for moment and shear. Thus this spreadsheet is not tied to RC-Pier.

Pile Footing Design Aashto Lrfd 5.13.3

Footing Length (X direction)	28.000	feet
Footing Width (Z direction)	15.000	feet
Footing Depth (Y direction)	4.000	feet

Column Width or Diameter (X direction)	19.500	feet
Column Depth (Z direction)	3.000	feet

Enter column depth of 0 for round columns.

Pile Diameter, dp	10	inches
-------------------	----	--------



28 Day Concrete Strength, fc	3500	psi
------------------------------	------	-----

Typically 3500 psi for piers.

Only the pile locations in the positive quadrant should be entered since the pile footing is assumed to be symmetrical. The user should include any piles located on the +X and +Z axes and the pile at the center of the footing if present.

Aashto Lrfd 5.13.3.2 makes provision for the tolerance of actual pile location. Office policy is to ignore this provision in footing design.

Pile Number	Positive x-coord (feet)	Positive z-coord (feet)
1	2.5	2
2	7.5	2
3	12.5	2
4	2.5	6
5	7.5	6
6	12.5	6
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		



Total Number of Footing Piles	24	
Sx, Pile Section Modulus	80.000	ft
Sz, Pile Section Modulus	140.000	ft

The "Maximum Factored Pile Load, P_{u_m} " was taken directly from RC-Pier. The "Maximum Factored Average Pile Load, P_{u_a} " may be found by going to the Analysis tab in RC-Pier (see below).

User Loads for Footing Design		
Factored Pile Resistance, $R_r = \phi R_n$	145.800	kips
Maximum Factored Pile Load, P_{u_m}	178.480	kips
Maximum Factored Average Pile Load, P_{u_a}	125.550	kips

Used for:
One-way (beam) shear
Flexure reinforcement
Two-way (punching) shear

Note: The user can, according to office policy, deduct the factored buoyant weight of the footing from the pile loads for flexure and shear design. Be sure to deduct only the portion of the load going to one pile. Soil load may not be deducted.

Memb	Node	Fx	Fy(Max/Min)	Fz	Mx	My	Mz
1	1	25.47 61.51	3013 1511	30.9 77.96	1112 2536	1.964e-005 2.847e-005	-3257 -3410

Flexural Capacity Check

Aashto Lfrd 5.7.3.2 and 5.13.3.4

Design Flexural R/I Parallel to X-axis (M _x moments)		
Clearance to Flexural R/I from Bottom of Footing	14.000	in
Number of Bars Required for R/I parallel to X-axis	20	
Flexural R/I Bar Size for bars parallel to X-axis	8	
Bar Diameter for # 8	1.000	in
Bar Area for # 8	0.790	in ²
Total Bar Area	15.800	in ²
Effective Depth for bars parallel to X-axis, d _x or ds _x	33.500	in

Note: d_x corresponds with design for M_x

Flexure Phi Factor, φ	0.900	
Factored Applied Moment, Mu _x	1963.280	k*ft
Depth of Equivalent Stress Block, a	1.770	in
Factored Flexural Resistance, Mr _x = φMn _x	2318.916	k*ft
Is Mu _x <= Mr _x ?	Yes	

Design Flexural R/I Parallel to Z-axis (M _y moments)		
Clearance to Flexural R/I from Bottom of Footing	13.000	in
Number of Bars Required for R/I parallel to Z-axis	50	
Flexural R/I Bar Size for bars parallel to Z-axis	8	
Bar Diameter for # 8	1.000	in
Bar Area for # 8	0.790	in ²
Total Bar Area	39.500	in ²
Effective Depth for bars parallel to Z-axis, d _y or ds _y	34.500	in

Note: d_y corresponds with design for M_y

Flexure Phi Factor, φ	0.900	
Factored Applied Moment, Mu _y	5354.400	k*ft
Depth of Equivalent Stress Block, a	2.371	in
Factored Flexural Resistance, Mr _y = φMn _y	5921.657	k*ft
Is Mu _y <= Mr _y ?	Yes	

Minimum Reinforcement Check

Aashto Lfrd 5.7.3.3.2 and 5.4.2.6

Enter: 1 if de + 2" is to be used to calculate M _{cr} 2 if the footing depth is to be used to calculate M _{cr}	1	If 1, then de + 2" is used to calculate M _{cr} ; otherwise, the footing depth is used.
Modulus of Rupture, f _r	0.692	ksi

Section Modulus of Concrete Footing, S _z	21.879	ft ³
120% of the Cracking Moment, 1.2*M _{crz}	2617.060	k*ft
Is 1.2*M _{crz} <= Mr _z ?	No	

Section Modulus of Concrete Footing, S _x	43.175	ft ³
120% of the Cracking Moment, 1.2*M _{crx}	5164.277	k*ft
Is 1.2*M _{crx} <= Mr _x ?	Yes	

--- OR ---

--- OR ---

As required	13.320	in ²
Is As prov'd >= 1.33*As req'd ?	No	

As required	35.591	in ²
Is As prov'd >= 1.33*As req'd ?	No	

Maximum Reinforcement Check

Aashto Lfrd 5.5.4.2, 5.7.2.1, and 5.7.3.3

Stress Block Factor, β ₁	0.850	
Location of Neutral Axis, c	2.083	in
Net Tensile Strain in the Extreme Tension Steel, ε _s	0.045	in/in
Is Section Tension Controlled? ε _s >= 0.005	Yes	
Is Section Compression Controlled? ε _s <= 0.002	No	
Is Section in Transition? 0.005 > ε _s > 0.002	No	
Flexure Phi Factor, φ, for Design	0.900	

Stress Block Factor, β ₁	0.850	
Location of Neutral Axis, c	2.789	in
Net Tensile Strain in the Extreme Tension Steel, ε _s	0.034	in/in
Is Section Tension Controlled? ε _s >= 0.005	Yes	
Is Section Compression Controlled? ε _s <= 0.002	No	
Is Section in Transition? 0.005 > ε _s > 0.002	No	
Flexure Phi Factor, φ, for Design	0.900	

NOTE: If section is in Transition, then the user must adjust the Flexural Phi Factor, φ, in cell G60 or O60.
If section is Compression Controlled, then do not use this spreadsheet, but the user must do a strain compatibility analysis.

Is Flexural R/I Adequate? **NO, More R/I is Required.**

Is Flexural R/I Adequate? **YES, Flexural R/I is Adequate.**

As indicated earlier the number of piles is not adequate to resist the maximum pile load. Additionally the existing footing reinforcement is not adequate. Remember that this pier was originally designed based on Aashto Standard Specifications.

Crack Control: Flexure R/I Aashto Lrfd 5.7.3.4.

The requirements of Aashto Lrfd 5.13.3.5 should be included. Spacing should also comply with Aashto Lrfd 5.10.3.1 and 5.10.3.2. If uplift is present; then, as a minimum, add #5 bars at 12" to the top of the footing in both directions.

Enter: 1 if $d_e + 2"$ is to be used to calculate cover
2 if the footing depth is to be used to calculate cover **1** If 1, then $d_e + 2"$ is to be used to calculate cover; otherwise, the footing depth is used.

Exposure Factor, γ_e	1.000
Concrete Cover Thickness to R/I Center, d_c	2.000 in
β_s	1.085
Maximum Service Pile Load, P_{s_m}	138.480 kips
Positive Service M_z	1523.280 k*ft
See Aashto Lrfd 5.4.2.4 and 5.7.1 for E_c and n	
Reinforcement Ratio, ρ	0.00262
Concrete Modulus of Elasticity, E_c	3586.616 ksi
Modular Ratio, n	8.000
Factor for Distance to Neutral Axis, k	0.185
Reinforcement Stress at Service Level	36.803 ksi

Max. Spacing of Bot Layer of Pos. Flex. R/I, s 13.526 in

Crack Control: Skin R/I Aashto Lrfd 5.7.3.4

Is Skin R/I Required? (Is $d_e = d_s > 3.00'$?)	No
Area of Skin R/I Required per Face, Ask	0.000 in ² per ft
Max Spacing of Skin R/I Required	5.583 in

Exposure Factor, γ_e	1.000
Concrete Cover Thickness to R/I Center, d_c	2.000 in
β_s	1.083
Maximum Service Pile Load, P_{s_m}	138.480 kips
Positive Service M_z	4154.400 k*ft
See Aashto Lrfd 5.4.2.4 and 5.7.1 for E_c and n	
Reinforcement Ratio, ρ	0.00341
Concrete Modulus of Elasticity, E_c	3586.616 ksi
Modular Ratio, n	8.000
Factor for Distance to Neutral Axis, k	0.208
Reinforcement Stress at Service Level	39.305 ksi

Max. Spacing of Bot Layer of Pos. Flex. R/I, s 12.447 in

Crack Control: Skin R/I Aashto Lrfd 5.7.3.4

Is Skin R/I Required? (Is $d_e = d_s > 3.00'$?)	No
Area of Skin R/I Required per Face, Ask	0.000 in ² per ft
Max Spacing of Skin R/I Required	5.750 in

Shrinkage and Temp. R/I and Structural Mass Concrete Aashto Lrfd 5.10.8

Area of Skin R/I Required per Face, Ask	0.411 in ² per ft
Max Spacing of Skin R/I Required	12.000 in

Area of Skin R/I Required per Face, Ask	0.455 in ² per ft
Max Spacing of Skin R/I Required	12.000 in

Fatigue in R/I Aashto Lrfd 5.5.3

Office policy is to neglect checking fatigue.

Shear Capacity Check Aashto Lrfd 5.8.1.4, 5.13.3.6 and 5.8.3

Enter 1 to check $d_v = 0.72 \cdot h$. Enter 2 to exclude it.	2
Calculated Effective Shear Depth, d_v	32.615 in
User Entry for Effective Shear Depth, d_v	32.615 in

See Aashto Lrfd 5.8.2.9.

One Way Shear or Beam Shear Parallel to Z-axis	
Distance from Column Center to Critical Section	12.468 ft
Point of 0 Shear to Equivalent Column Face	3.167 ft
Distance of $3 \cdot d_v$	8.154 ft
Is Point of 0 Shear to Equivalent Column Face $< 3 \cdot d_v$?	YES
If the above is YES then Aashto Lrfd 5.8.3.4.1 may be applied with $\beta = 2.00$.	
Factor for Tens Trans Diagonally Crack'd Concr, β	2.000
Aashto Lrfd 5.8.3.3 and 5.8.3.4	

One Way Shear or Beam Shear Parallel to X-axis	
Distance from Column Center to Critical Section	4.218 ft
Point of 0 Shear to Equivalent Column Face	4.917 ft
Distance of $3 \cdot d_v$	8.154 ft
Is Point of 0 Shear to Equivalent Column Face $< 3 \cdot d_v$?	YES
If the above is YES then Aashto Lrfd 5.8.3.4.1 may be applied with $\beta = 2.00$.	
Factor for Tens Trans Diagonally Crack'd Concr, β	2.000
Aashto Lrfd 5.8.3.3 and 5.8.3.4	

Factored Applied Shear, V_{u_x}	314.053 k
Factored Shear Resistance, $V_{r_x} = \phi V_{n_x} = \phi V_{c_x}$	624.717 k

Factored Applied Shear, V_{u_z}	874.800 k
Factored Shear Resistance, $V_{r_z} = \phi V_{n_z} = \phi V_{c_z}$	1166.139 k

Is Beam Shear OK? $V_{u_x} \leq V_{r_x}$ YES.

Is Beam Shear OK? $V_{u_z} \leq V_{r_z}$ YES.

Two Way Shear or Punching Shear	
Distance from Column Center to Critical Section	11.109 ft
Distance from Column Center to Critical Section	2.859 ft
Perimeter of the Critical Section, b_o	55.872 ft
Ratio of Long Side to Short Side, β_c	6.500


Parallel to Z-axis
Parallel to X-axis


Factored Applied Shear, V_{u_x}	2008.800 k
Factored Shear Resistance, $V_{r_x} = \phi V_{n_x} = \phi V_{c_x}$	3033.283 k

Is Punching Shear OK? $V_{u_x} \leq V_{r_x}$ YES.

Case 2 Loading for Footing Design


RC-Pier screen captures for Case 2 loading for the footing will be provided below. I'm only going to show the differences from the Case 1 loading. The only differences include the WA and WS loadings and the removal of the EV1 load. For this example the maximum pile load for Case 2 will be different from Case 1. The maximum pile load for Case 1 and 2 are 178.48 k and 154.79 k, respectively.





All the loads from Case 1 (except for EV1) apply to Case 2. The differences between the two cases have to do with:

- 1.) The EV1 load on the footing was eliminated.
- 2.) The magnitude and the point of application of the WA buoyancy loads and the inclusion of a stream flow load.
- 3.) The point of application of the WS load on the column changes.



WA1

The buoyancy includes the entire submerged footing and the submerged portion of the column (excluding the 4.0' column extension).
 $[(28')*(15')*(4')]*(0.0624 \text{ kcf}) + [(19.5')*(3')*(13.78')]*(0.0624 \text{ kcf}) = 155.135 \text{ k}$
This load is placed just above the bottom of the column so that it will be reflected in the analysis results.

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	Y	155.1350	0.0010	0.0000	0.0000	kips
1	Trapezoidal	X	0.0000	0.1176	0.2510	0.5229	klf

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	Units

Strain Load

Unit:

+ Expansion - Contraction

Name:

Description:

Factors: Multiplier for Loads:

Auto Generation:

Import Loads:

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

The fractional location of the stream loading on the column is based on the 4' column extension.

The water loads that affect the footing design for Case 2 are the buoyancy and stream loads on the column. So, Case 2 is different from Case 1 in that there is a stream flow load and the depth of buoyancy has increased.

The spreadsheet that was setup to calculate WA loads will not generate standardized text files in order to import the loads.

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)
1	1	X	-3.8990
1	1	Y	-2.1450
1	1	Z	3.9670
1	2	X	-3.8990
1	2	Y	0.0000
1	2	Z	3.9670
1	3	X	-3.8990
1	3	Y	0.0000
1	3	Z	3.9670
1	4	X	-3.8990
1	4	Y	0.0000

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	UDL	X	-0.1200	0.5230	0.0000	0.8530	
1	UDL	Z	0.7800	0.5230	0.0000	0.8530	

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L
Force	X	0.0000	-0.9800	0.5000	0.0000	0.0000
UDL	Z	0.0000	0.2450	0.0000	0.0000	1.0000

Strain Load

Unit: 0

+ Expansion - Contraction

Name: WS1

Description:

Factors: Multiplier for Loads: 1

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

There are 8 WS cases (4 cases with uplift and 4 cases without), but I will only show the first one.

Remember that the reversible feature for wind loads was turned off in the library.

Wind loads can be auto-generated, but generating simplified wind loads requires a few tricks and some editing of the load results.

The wind loads above were imported from text file "WSLoadsCase2NoUplift001.txt" which was generated from the in-house spreadsheet for wind loads.

The only difference for Case 2 from Case 1 is the point of application of the wind loads on the column. The water elevation from Case 2 is higher than the fill elevation for Case 1.

```


Bearing Loads
1, 1, X, -3.899
1, 1, Y, -2.145
1, 1, Z, 3.967
1, 2, X, -3.899
1, 2, Y, 0
1, 2, Z, 3.967
1, 3, X, -3.899
1, 3, Y, 0
1, 3, Z, 3.967
1, 4, X, -3.899
1, 4, Y, 0
1, 4, Z, 3.967
1, 5, X, -3.899
1, 5, Y, 0
1, 5, Z, 3.967
1, 6, X, -3.899
1, 6, Y, 2.145
1, 6, Z, 3.967
Cap Loads
Force, X, 0, -0.98, 0.5
UDL, Z, 0.245, 0, 1
Column Loads
1, UDL, X, -0.12, 0.523, 0.853
1, UDL, Z, 0.78, 0.523, 0.853
    
```


Case 3 Loading for Footing Design

RC-Pier screen captures for Case 3 loading for the footing will be provided below. I'm only going to show the differences from the Case 1 loading. The only differences include:

- 1.) The Load Group is Extreme Event 2.
- 2.) Changes to the WA loadings.
- 3.) All wind loading can be eliminated since it is not part of Extreme Event 2.
- 4.) Ice loading is added.
- 5.) EV1 is eliminated because soil is assumed to be scoured away.

For this example the maximum pile load for Case 1 and 3 are 178.48 k and 114.46 k, respectively.





The DC, DW, LL, TU, and BR loads for Case 3 are the same as those for Case 1. The WA load for Case 3 has been modified from Case 1. The WS and WL loads have been eliminated since Extreme Event 2 does not include those loads. The IC loads were added for Case 3. The EV load was omitted.

WA1

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	Y	136.1890	0.0010	0.0000	0.0000	kips
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units

Strain Load

Unit:

+ Expansion - Contraction

Name:

Description:

Factors: Multiplier for Loads:

Auto Generation:

Import Loads:

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

The water loads that affect the column and cap design for Case 3 are the buoyancy on the column. Case 3 is different from Case 1 in that the depth of buoyancy has increased.

The spreadsheet that was setup to calculate WA loads will not generate standardized text files in order to import the loads.

IC1

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	X	158.0350	0.3703	0.0000	0.0000	kips
1	Force	Z	23.7050	0.3703	0.0000	0.0000	kips
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L

Strain Load

Unit: 0.

+ Expansion - Contraction

Name: IC1

Description:

Factors: Multiplier for Loads: 1.

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

There are a total of 4 load cases for ice. The two cases shown on this page differ only in that the direction of Z ice load is reversed.

The spreadsheet that was setup to calculate IC loads will not generate standardized text files in order to import the loads.

IC2

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	X	158.0350	0.3703	0.0000	0.0000	kips
1	Force	Z	-23.7050	0.3703	0.0000	0.0000	kips
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units

Strain Load

Unit: 0.

+ Expansion - Contraction

Name: IC2

Description:

Factors: Multiplier for Loads: 1.

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

IC3

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	X	79.0170	0.3703	0.0000	0.0000	kips
1	Force	Z	53.2980	0.3703	0.0000	0.0000	kips
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units

Strain Load

Unit: 0.

+ Expansion - Contraction

Name: IC3

Description:

Factors: Multiplier for Loads: 1.

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

The two cases shown on this page differ only in that the direction of Z ice load is reversed.

IC4

Loads: Load data

Bearing / Girder loads

Bearing Line	Bearing Point#	Dir	Load (kips)

Column Loads / Settlement

Col Nr	Load Type	Dir	Mag1	y1/L	Mag2	y2/L	Units
1	Force	X	79.0170	0.3703	0.0000	0.0000	kips
1	Force	Z	-53.2980	0.3703	0.0000	0.0000	kips
*							

Cap Loads

Load Type	Dir	Arm (ft)	Mag1	x1/L	Mag2	x2/L	Units

Strain Load

Unit: 0.

+ Expansion - Contraction

Name: IC4

Description:

Factors: Multiplier for Loads: 1.

Auto Generation: Generate

Import Loads: Import

Note: Vertically downward loads be added as negative loads in Y direction.

OK Cancel

LETTING DATE
07-18-06

BRIDGE NEW - PPCB
NHSN-034-8(105)--2R-51

JEFFERSON COUNTY

JEFFERSON COUNTY - DESIGN NO. 1203

CONVENTIONAL SIGNS	
	DIVIDED HIGHWAY
	PAVED ROAD
	BITUMINOUS ROAD
	GRAVEL ROAD
	EARTH ROAD
	INTERSTATE HIGHWAY
	UNITED STATES HIGHWAY
	STATE HIGHWAY
	COUNTY HIGHWAY
	RAILROAD
	PIPE LINE
	AIRPORT
	HYDROLOGY
	BRIDGE
	STATE BOUNDARY
	COUNTY BOUNDARY
	CORPORATE LIMIT LINE
	TOWNSHIP LINE
	SECTION LINE

Iowa Department of Transportation
Highway Division

PLANS OF PROPOSED IMPROVEMENTS ON THE
PRIMARY ROAD SYSTEM
JEFFERSON COUNTY
BRIDGE NEW - PPCB
RELOCATED US 34 (FAIRFIELD BYPASS)
OVER UNNAMED CREEK

THE IOWA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2001, PLUS APPLICABLE GENERAL SUPPLEMENTAL SPECIFICATIONS, DEVELOPMENTAL SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS SHALL APPLY TO CONSTRUCTION WORK ON THIS PROJECT.

VALUE ENGINEERING SAVES. REFER TO THE GENERAL NOTES IN THESE PLANS.

TOTAL SHEETS	45
PROJECT NUMBER	NHSN-034-8(105)--2R-51
R.O.W. PROJECT NUMBER	
PROJECT IDENTIFICATION NUMBER	94-51-034-030-03


INDEX OF SHEETS	
NO.	DESCRIPTION
1	TITLE SHEET
2	ESTIMATE SHEET DESIGN NO. 1203
2-33	DESIGN NO. 1203
SPS.01-SP5.06	SOIL PROFILE SHEETS
C.01	ESTIMATE SHEET FOR ROADWAY
B.01-D.02	ROADWAY SHEETS
1A	REVISION SHEET ADDED

ENGLISH STANDARD BRIDGE PLANS		
STANDARD	ISSUED	REVISED

REVISIONS	
	SEE REVISION SHEET

STANDARD ROAD PLANS	
STANDARD ROAD PLANS ARE LISTED ON SHEET	C.01

DESIGN DATA RURAL	
2004 AADT	4090 V.P.D.
2024 AADT	5810 V.P.D.
202 DHV	V.P.H.
TRUCKS	19 %
Total Design ESALS	



LOCATION MAP


INDEX OF SEALS		
SHEET NO.	NAME	TYPE
1	GORDON L. PORT	STRUCTURAL DESIGN
SPS.01	MICHAEL D. RINGLER	GEOTECHNICAL DESIGN
D.01	RICHARD M. VOELKER	ROADWAY DESIGN

STRUCTURAL DESIGN	
I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.	
Signature <i>Gordon L. Port</i>	Date 04-27-06
My license renewal date is December 31, 2006.	
Pages or sheets covered by this seal: SHEETS 1 THRU 33 OF 45	

PROJECT DIRECTORY NAME: 51034030A94

LISTING OF PROJECT REVISIONS

DATE	SHEET NUMBER	DESCRIPTION OF REVISIONS	DATE	SHEET NUMBER	DESCRIPTION OF REVISIONS
07-20-06	1A OF 45	REVISION SHEET ADDED.			
07-20-06	2 OF 45	QUANTITIES CHANGED. REASON : INCORRECT.			
07-20-06	7 OF 45	QUANTITY CHANGED. REASON : INCORRECT.			
07-20-06	14 OF 45	NUMBER OF DRAINS CHANGED. REASON : INCORRECT.			

STRUCTURAL DESIGN	
I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.	
	Signature <u><i>Gordon L. Port</i></u> Date <u>07-20-06</u> Printed or Typed Name <u>Gordon L. Port</u>
My license renewal date is December 31, <u>2006</u>	
Pages or sheets covered by this seal: <u>SHEETS 1, 1A, 2, 7, 14 OF 45</u>	

JEFFERSON COUNTY
DESIGN NO. 1203
REVISION SHEET
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION

ESTIMATED BRIDGE QUANTITIES BOTH BRIDGES

ITEM NO.	ITEM CODE	ITEM DESCRIPTION	UNIT	WESTBOUND BRIDGE	EASTBOUND BRIDGE	TOTAL	AS BUILT QUANTITY
1	2402-2720000	EXCAVATION, CL 20	CY	460	470	930	
2	2402-2721000	EXCAVATION, CL 21	CY	305	300	605	
3	2403-0100010	STRUCT CONC (BRIDGE)	CY	725.0	730.6	1,456.6	
4	2404-7775000	REINFORC STEEL	LB	96,529 43,654	44,263	141,792 87,917	
5	2404-7775005	REINFORC STEEL, EPOXY COATED	LB	96,529	96,529	193,058	
6	2407-0580460	BEAM, PPC, LXD60	EACH	6	6	12	
7	2407-0580470	BEAM, PPC, LXD70	EACH	6	6	12	
8	2407-0580490	BEAM, PPC, LXD90	EACH	6	6	12	
9	2408-7800000	STRUCTURAL STEEL	LB	7,106	7,106	14,212	
10	2414-6424110	CONC BARRIER RAIL	LF	500	500	1,000	
11	2501-5425057	PILE, DRIVE STEEL BEAR, HP 10X57	LF	300 1,860	300 1,910	600 3,770	
12	2501-5550057	PILE, FURN STEEL BEAR, HP 10X57	LF	300 1,860	300 1,910	600 3,770	
13	2501-6335010	PREDBORED HOLE	LF	200	200	400	
14	2526-8285000	CONSTRUCTION SURVEY	LS			1	
15	2533-4980005	MOBILIZATION	LS			1	

- ITEM NO. 3** ESTIMATE REFERENCE INFORMATION
 INCLUDES FURNISHING AND PLACING SUBDRAIN (INCLUDING EXCAVATION), IN GRANULAR BACKFILL POROUS BACKFILL AND SUBDRAIN OUTLETS AT ABUTMENTS. INCLUDES ALL PREFORMED EXPANSION JOINT FILLER REQUIRED. INCLUDES FURNISHING AND PLACING ENGINEERING FABRIC, MACADAM STONE, 4"x6" TREATED DIMBERS, 2" DIAMETER STEEL PINS (OR REBARS) AND ALL REQUIRED EXCAVATING, SHAPING AND COMPACTING FOR BRIDGE WING ARMORING. INCLUDES FURNISHING AND PLACING (INCLUDING EXCAVATION) MACADAM STONE AND ENGINEERING FABRIC FOR THE DECK DRAIN SPLASH BASINS. INCLUDES FURNISHING AND PLACING 3" PVC PIPE AND EXPANDING FOAM.
- 6, 7 & 8** INCLUDES ABUTMENT BEARING MATERIAL AND COIL RODS. INCLUDES LAMINATED BEARING PADS WITH ANCHORED CURVED SOLE PLATES AT PIER 1 AND PLAIN TAPERED NEOPRENE PADS AT PIER 2. GRADATION OF COARSE AGGREGATES FOR PRESTRESSED CONCRETE BRIDGE UNITS SHALL MEET THE REQUIREMENTS OF SECTION 4115 CLASS III DURABILITY. GRADATION OF THE COARSE AGGREGATE SHALL MEET THE REQUIREMENTS OF SECTION 2407.02A.
- 9** INCLUDES 24 DRAINS AT 106 LBS. PER DRAIN. INCLUDES 1403 LBS. STRUCTURAL STEEL FOR PINTLE PLATES @ PIER 1.
- 10** INCLUDES 496.0 LIN. FT. OF 2" RIGID STEEL CONDUIT IN NORTH BARRIER RAIL OF WESTBOUND BRIDGE AND SOUTH BARRIER OF EASTBOUND BRIDGE. INCLUDES MATERIAL AND LABOR ASSOCIATED WITH PROVIDING AND INSTALLING RIGID STEEL CONDUIT, JUNCTION BOXES AND FITTINGS. IF PLACEMENT OF CONCRETE IS DONE BY THE SLIP FORMING METHOD, CLASS BR CONCRETE IS REQUIRED. CAST IN PLACE BARRIER RAILS SHALL USE CLASS C MIX. PRICE BID FOR THIS ITEM SHALL INCLUDE THE COST OF CAST-IN-PLACE FORMS IF REQUIRED FOR PLACEMENT OF THE CONCRETE.

THESE BRIDGE PLANS LABEL ALL REINFORCING STEEL WITH ENGLISH NOTATION (50# IS 3/8 INCH DIAMETER BAR). ENGLISH REINFORCING STEEL RECEIVED IN THE FIELD MAY DISPLAY THE FOLLOWING "BAR DESIGNATION". THE "BAR DESIGNATION" IS THE STAMPED IMPRESSION ON THE REINFORCING BARS, AND IS EQUIVALENT TO THE BAR DIAMETER IN MILLIMETERS.

ENGLISH SIZE	BAR DESIGNATION
3	10
4	13
5	16
6	19
7	22
8	25
9	29
10	32
11	36

SPECIFICATIONS:

DESIGN: AASHTO SERIES OF 1996.
 CONSTRUCTION: IOWA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2001, PLUS APPLICABLE GENERAL SUPPLEMENTAL SPECIFICATIONS, DEVELOPMENTAL SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS FOR CONSTRUCTION SURVEY AND SPECIAL PROVISIONS SHALL APPLY TO CONSTRUCTION WORK ON THIS PROJECT.

DESIGN STRESSES:

DESIGN STRESSES FOR THE FOLLOWING MATERIALS ARE IN ACCORDANCE WITH THE AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, SERIES OF 1996.
 REINFORCING STEEL IN ACCORDANCE WITH SECTION 8, GRADE 60.
 CONCRETE IN ACCORDANCE WITH SECTION 8, $f_c = 3,500$ PSI.
 PRESTRESSED CONCRETE BEAMS, SEE DESIGN SHEETS 24 THRU 27.
 STRUCTURAL STEEL IN ACCORDANCE WITH SECTION 10, ASTM A709 GRADE 36,
 PRESTRESSED CONCRETE BEAM BEARINGS SEE DESIGN SHEET 22.

NOTE:
 ROADWAY QUANTITIES SHOWN ELSEWHERE IN THESE PLANS.

NOTE:
 POLLUTION PREVENTION PLAN SHOWN ELSEWHERE IN THESE PLANS.

REVISED: 07-20-06;
 QUANTITIES CHANGED.

TRAFFIC CONTROL PLAN ON RELOCATED IOWA 34

NOTE: THIS STRUCTURE IS BEING CONSTRUCTED ON A RELOCATION AND THE ROAD WILL NOT BE OPEN TO TRAFFIC UNTIL AFTER COMPLETION OF CONSTRUCTION. REFER TO TRAFFIC CONTROL PLAN SHOWN ELSEWHERE IN THESE PLANS.

GENERAL NOTES:

IT IS THE INTENT OF THESE PLANS TO CONSTRUCT DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES AT STATION 356+70.31 (ENGLISH) ON RELOCATED U.S. 34.

THIS BRIDGE IS DESIGNED FOR HS20-44 LOADING PLUS 20 LBS. PER SQUARE FOOT OF ROADWAY FOR FUTURE WEARING SURFACE.

UTILITY COMPANIES WHOSE FACILITIES ARE SHOWN ON THE PLANS OR KNOWN TO BE WITHIN THE CONSTRUCTION LIMITS SHALL BE NOTIFIED BY THE BRIDGE CONTRACTOR OF THE STARTING DATE.

IT SHALL BE THE BRIDGE CONTRACTOR'S RESPONSIBILITY TO PROVIDE SITES FOR EXCESS EXCAVATED MATERIAL. NO PAYMENT FOR OVERHAUL WILL BE ALLOWED FOR MATERIAL HAULED TO THESE SITES.

THE APPROACH FILLS AS SHOWN ARE NOT A PART OF THIS CONTRACT, BUT ARE TO BE IN PLACE BEFORE ABUTMENT PILES ARE DRIVEN. THE BRIDGE CONTRACTOR IS TO LEVEL OFF AND SHAPE THE BERMS TO THE ELEVATIONS AND DIMENSIONS SHOWN. DRESSING OF SLOPES OUTSIDE THE BRIDGE AREA NOT DISTURBED BY THE BRIDGE CONTRACTOR SHALL BE PAID FOR AS EXTRA WORK.

EXCAVATION QUANTITIES FOR THE PIERS AND ABUTMENTS ARE BASED ON THE ASSUMPTION THAT ROADWAY FILL AND SURCHARGES WILL HAVE BEEN COMPLETED PRIOR TO STARTING CONSTRUCTION OF THE PIERS AND ABUTMENTS.

PILES SHALL NOT BE DRIVEN FOR A MINIMUM OF 60 DAYS FOLLOWING COMPLETION OF THE EAST ABUTMENT APPROACH FILLS. THE TIME PERIOD BETWEEN COMPLETION OF FILLS AND OF DRIVING PILES MAY BE CHANGED AS ORDERED BY THE ENGINEER BASED UPON REVIEW OF SETTLEMENT PLATES.

THE BRIDGE CONTRACTOR SHALL PREBORE HOLES FOR ABUTMENT PILES. HOLES SHALL BE BORED TO THE ELEVATIONS SHOWN ON THE "LONGITUDINAL SECTION ALONG CENTERLINE APPROACH ROADWAY" ON DESIGN SHEETS 2 & 3. PILES SHALL BE DRIVEN THROUGH THE HOLES TO AT LEAST THE SPECIFIED DESIGN BEARING.

THE BRIDGE CONTRACTOR IS TO INSTALL SUBDRAINS BEHIND THE ABUTMENTS, SEE DESIGN SHEET 10 FOR DETAILS.

THE BRIDGE CONTRACTOR SHALL NOTE THE STANDARD ABUTMENT DETAILS HAVE BEEN MODIFIED TO OFFSET THE ABUTMENT FOOTING FROM THE WINGWALL TO AID IN TYING THE REINFORCING STEEL BETWEEN THE FOOTING TO WINGWALL AND THE FOOTING TO BACKWALL.

GUARDRAIL IS TO BE PLACED BY OTHERS.

THE BRIDGE CONTRACTOR IS ENCOURAGED TO TAKE FULL ADVANTAGE OF SPECIFICATION 110515 -- VALUE ENGINEERING INCENTIVE PROPOSAL. A PAMPHLET AND CONCEPTUAL PROPOSAL FORM WILL BE AVAILABLE AT THE PRECONSTRUCTION CONFERENCE.

THE INFORMATION IN THE "BERM SLOPE LOCATION TABLE" PROVIDES THE LOCATION AND ELEVATION OF FOUR POINTS WHICH CAN BE USED TO LEVEL OFF AND SHAPE THE BERMS TO THEIR FINAL DIMENSIONS. THE "A" POINTS ARE LOCATED WHERE THE FINISHED GRADE OF THE BERM SLOPE (OR TOP OF SLOPE PROTECTION) MEETS THE TOP OF BERM. "A1" AND "A3" ARE LOCATED AT THE EDGE OF THE SLOPE PROTECTION. "A2" IS ALONG THE E APPROACH ROADWAY. "B" IS LOCATED AT THE POINT WHERE THE EXTENSION OF THE BERM SLOPE ALONG E APPROACH ROADWAY INTERSECTS WITH THE TOP OF PAVEMENT AT THE E APPROACH ROADWAY.


ALL BATTERED PILES SHALL BE TRIMMED TO A HORIZONTAL LINE TO AID IN THE PLACEMENT OF REINFORCING.

TRANSVERSE GROOVING OR TYPING IN THE PLASTIC CONCRETE OF THE BRIDGE DECK (AND BRIDGE APPROACH SECTIONS) IS NOT ALLOWED. LONGITUDINAL GROOVES WILL BE CUT IN THE HARDENED CONCRETE USING A MECHANICAL CUTTING DEVICE. LONGITUDINAL GROOVING WILL NOT BE A PART OF THIS CONTRACT, BUT WILL BE DONE BY OTHERS PRIOR TO OPENING THE BRIDGE TO TRAFFIC.

CONCRETE BARRIER RAILS PLACED USING THE SLIPFORM METHOD WILL REQUIRE THE USE OF A CLASS BR CONCRETE IN ACCORDANCE WITH ARTICLE 2513.03B OF THE STANDARD SPECIFICATIONS. CAST-IN-PLACE BARRIER RAILS SHALL USE CLASS C MIX. CLASS D CONCRETE IS NOT PERMITTED FOR CONCRETE BARRIER RAILS (CAST-IN-PLACE OR SLIPFORMED METHOD).


THIS BRIDGE HAS BEEN CONVERTED FROM METRIC TO ENGLISH FOR DESIGN AND CONSTRUCTION. METRIC VALUES OF STATIONS AND ELEVATIONS WERE DIVIDED BY THE CONVERSION FACTOR 0.3048 TO OBTAIN ENGLISH VALUES. THE ROAD PLANS AND SURVEY REMAINED IN METRIC.

DESIGN FOR 32° SKEW (L.A.)
**DUAL 223'-0" x 40'-0" PRETENSIONED
 PRESTRESSED CONCRETE BEAM BRIDGES**
 70'-9" & 60'-9" END SPANS 31'-6" INTERIOR SPAN
NOTES AND QUANTITIES
 STA. 356+70.31 (E OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 1 OF 32 FILE NO. 29488 DESIGN NO. 1203




LONGITUDINAL SECTION ALONG CENTERLINE APPROACH ROADWAY - WESTBOUND ROADWAY

BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.



PROPOSED GRADE (RELOCATED U.S. 34)



NOTES:
ALL DIMENSIONS IN FEET UNLESS OTHERWISE NOTED OR SHOWN.
ALL STATIONS AND ELEVATIONS ARE IN FEET (UNLESS OTHERWISE SHOWN).
THIS PLAN IS NOT TO SCALE.

NOTE:
THIS BRIDGE HAS BEEN CONVERTED FROM METRIC TO ENGLISH FOR DESIGN AND CONSTRUCTION. METRIC VALUES OF STATIONS AND ELEVATIONS WERE DIVIDED BY THE CONVERSION FACTOR 0.3048 TO OBTAIN ENGLISH VALUES. THE ROAD PLANS AND SURVEY HAVE REMAINED IN METRIC.

HYDRAULIC DATA

DRAINAGE AREA = 3.75 sq mi
STREAM SLOPE = 17.424 Ft/mi
Q50 = 4308.4 cfs
FREEBOARD = 18.37 ft
MAX BACKWATER DEPTH = .689 ft
NATURAL STAGE AT BRIDGE = 675.49
Q100 = 5155.94 cfs
MAX BACKWATER DEPTH = .98 ft
NATURAL STAGE AT BRIDGE = 676.12
CALCULATED SCOUR = 6.23 ft

LOCATION

U.S. 34 OVER UNNAMED CREEK
T-71 NLR-10W
SECTION 2/3
LIBERTY TWP.
JEFFERSON COUNTY
FHWA NO. 609850 (EB)
FHWA NO. 609855 (WB)

TRAFFIC ESTIMATE


(RELOCATED U.S. 34)
2004: 4,090 VPD
2024: 5,810 VPD
19% TRUCKS

SITUATION PLAN

NOTE: SEE DESIGN SHEET 3 FOR EASTBOUND BRIDGE.


DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
SITUATION PLAN - WESTBOUND BRIDGE
 STA. 356+70.31 (OFF. RELOC. U.S.34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 2 OF 32 FILE NO. 29488 DESIGN NO. 1203

BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.



PROPOSED GRADE
(RELOCATED U.S. 34)

PROPOSED DUAL 223'-0" x 40' PRETENSIONED
PRESTRESSED CONCRETE BEAM BRIDGES
STA. 356+70.31 ☐ OFFICE RELOCATED US 34 (ENGLISH)
STA. 108+72.310 ☐ OFFICE RELOCATED US 34 (METRIC)



TYPICAL APPROACH SECTION

NOTE:
ALL DIMENSIONS IN FEET UNLESS OTHERWISE NOTED OR SHOWN.
ALL STATIONS AND ELEVATIONS ARE IN FEET (UNLESS OTHERWISE SHOWN).
THIS PLAN IS NOT TO SCALE.

NOTE:
THIS BRIDGE HAS BEEN CONVERTED FROM METRIC TO ENGLISH FOR DESIGN AND CONSTRUCTION. METRIC VALUES OF STATIONS AND ELEVATIONS WERE DIVIDED BY THE CONVERSION FACTOR 0.3048 TO OBTAIN ENGLISH VALUES. THE ROAD PLANS AND SURVEY HAVE REMAINED IN METRIC.

HYDRAULIC DATA

DRAINAGE AREA = 3.75 sq mi
STREAM SLOPE = 17.424 ft/mi
Q50 = 4308.4 cfs
FREEBOARD = 18.37 ft
MAX BACKWATER DEPTH = .689 ft
NATURAL STAGE AT BRIDGE = 675.49
Q100 = 5155.94 cfs
MAX BACKWATER DEPTH = .98 ft
NATURAL STAGE AT BRIDGE = 676.12
CALCULATED SCOUR = 6.23 ft

LOCATION


U.S. 34 OVER UNNAMED CREEK
T-71 N, R-10W
SECTION 2/3
LIBERTY TWP.
JEFFERSON COUNTY
FHWA NO. 609850 (EB)
FHWA NO. 609855 (WB)

TRAFFIC ESTIMATE

(RELOCATED U.S. 34)
2004: 4,090 VPD
2024: 5,810 VPD
19% TRUCKS

SITUATION PLAN


NOTE: SEE DESIGN SHEET 2 FOR WESTBOUND BRIDGE.



LONGITUDINAL SECTION ALONG APPROACH ROADWAY - EASTBOUND ROADWAY

DESIGN FOR 32° SKEW (L.A.)
**DUAL 223'-0" x 40'-0" PRETENSIONED
PRESTRESSED CONCRETE BEAM BRIDGES**
70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
SITUATION PLAN - EASTBOUND BRIDGE
STA. 356+70.31 ☐ OFF. RELOC. U.S.34 MAY, 2006
JEFFERSON COUNTY
IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. 3 OF 32 FILE NO. 29488 DESIGN NO. 1203


METRIC BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 103+43.85, 44.479 m LT. ELEV. 223.240.
 ENGLISH BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.
 222'-11 1/8" ϕ - ϕ ABUTMENT BEARINGS



STAKING DIAGRAM


WESTBOUND BRIDGE				EASTBOUND BRIDGE							
ENGLISH BERM SLOPE LOCATION TABLE				METRIC BERM SLOPE LOCATION TABLE							
STATION	OFFSET*	ELEVATION	STATION	OFFSET*	ELEVATION	STATION	OFFSET*	ELEVATION			
WEST ABUTMENT				WEST ABUTMENT				WEST ABUTMENT			
A1	356+95.73	72.51	664.11	A1	356+35.86	72.51	663.71	A1	108+80.059	22.101	202.421
A2	356+79.33	45.93	664.11	A2	356+21.95	45.93	663.71	A2	108+75.060	13.999	202.421
A3	356+65.42	23.35	664.11	A3	356+05.54	23.35	663.71	A3	108+70.820	7.117	202.421
B	355+69.05	45.93	701.89	B	355+14.27	45.93	703.09	B	108+40.07	13.999	213.936
EAST ABUTMENT				EAST ABUTMENT				EAST ABUTMENT			
A1	357+36.35	72.51	664.11	A1	356+76.48	72.51	663.71	A1	108+92.439	22.101	202.421
A2	357+19.95	45.93	664.11	A2	356+62.53	45.93	663.71	A2	108+87.441	13.999	202.421
A3	357+06.04	23.35	664.11	A3	356+46.16	23.35	663.71	A3	108+83.201	7.117	202.421
B	358+26.55	45.93	697.48	B	357+70.92	45.93	698.17	B	109+19.27	13.999	212.592

* OFFSET FROM ϕ U.S. 34 OFFICE RELOCATION





NOTE : THESE BRIDGE HAVE BEEN CONVERTED FROM METRIC TO ENGLISH FOR DESIGN AND CONSTRUCTION. METRIC VALUES OF STATIONS AND ELEVATIONS WERE DIVIDED BY THE CONVERSION FACTOR 0.3048 TO OBTAIN ENGLISH VALUES.

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
STAKING DIAGRAM
 STA. 356+70.31 (ϕ OFF. RELOC. U.S.34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 4 OF 32 FILE NO. 29488 DESIGN NO. 1203






BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.

CONCRETE PLACEMENT PIER 1 - WESTBOUND BRIDGE		
LOCATION	UNIT	QUANTITY
FOOTING	CU. YDS.	62.2
STEM	CU. YDS.	53.8
CAP & STEPS	CU. YDS.	41.8
TOTAL - CU.YDS.		157.8



NOTE: SEE DESIGN SHEET 9 FOR FOOTING PLAN AND OTHER PIER DETAILS.



TOTAL ESTIMATED QUANTITIES PIER 1 - WESTBOUND BRIDGE

ITEM	UNITS	QUANTITY
STRUCTURAL CONCRETE	CU.YDS.	157.8
REINFORCING STEEL	LBS.	22,003
HPI0x57 STEEL FURNISH	24 @ 20'	LIN.FT. 480
BEARING PILING DRIVE	24 @ 20'	LIN.FT. 480
CLASS 20 EXCAVATION	CU.YDS.	150
CLASS 21 EXCAVATION	CU.YDS.	155

DESIGN FOR 32° SKEW (L.A.)

DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES

70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN

WESTBOUND BRIDGE - PIER 1 DETAILS


STA. 356+70.31 (C. OFF. RELOC. ILS.34) MAY, 2006

JEFFERSON COUNTY

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION

DESIGN SHEET NO. 5 OF 32 FILE NO. 29488 DESIGN NO. 1203


BENCH MARK: 20' - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.




PIER CAP PLAN

CONCRETE PLACEMENT PIER 2 - WESTBOUND BRIDGE


LOCATION	UNIT	QUANTITY
FOOTING	CUL. YDS.	62.2
STEM	CUL. YDS.	50.5
CAP & STEPS	CUL. YDS.	41.5
TOTAL - CUL.YDS.		154.2




ELEVATION VIEW (LOOKING EAST)



SECTION THRU STEM



END ELEVATION



SECTION A-A

SECTION B-B


NOTE: SEE DESIGN SHEET 9 FOR FOOTING PLAN AND OTHER PIER DETAILS.

TOTAL ESTIMATED QUANTITIES PIER 2 - WESTBOUND BRIDGE

ITEM	UNITS	QUANTITY
STRUCTURAL CONCRETE	CUL.YDS.	154.2
REINFORCING STEEL	LBS.	21,651
1/2" x 57 STEEL FURNISH	24 @ 20' LIN.FT.	480
BEARING PILING DRIVE	24 @ 20' LIN.FT.	480
CLASS 20 EXCAVATION	CUL.YDS.	150
CLASS 21 EXCAVATION	CUL.YDS.	150



DESIGN FOR 32' SKEW (L.A.)
 DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
WESTBOUND BRIDGE - PIER 2 DETAILS
 STA. 356+70.31 (E OFF. RELOC. U.S.34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 6 OF 32 FILE NO. 29988 DESIGN NO. 1203

REVISED : 07-20-06 ; QUANTITY CHANGED.






BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.

CONCRETE PLACEMENT PIER I - EASTBOUND BRIDGE		
LOCATION	UNIT	QUANTITY
FOOTING	CU. YDS.	62.2
STEM	CU. YDS.	57.0
CAP & STEPS	CU. YDS.	41.4
TOTAL - CU.YDS.		160.6




NOTE: SEE DESIGN SHEET 9 FOR FOOTING PLAN AND OTHER PIER DETAILS.



TOTAL ESTIMATED QUANTITIES PIER I - EASTBOUND BRIDGE

ITEM	UNITS	QUANTITY
STRUCTURAL CONCRETE	CU.YDS.	160.6
REINFORCING STEEL	LBS.	22,411
HP10x57 STEEL FURNISH	24 @ 20' LIN.FT.	480
BEARING PILING DRIVE	24 @ 20' LIN.FT.	480
CLASS 20 EXCAVATION	CU.YDS.	155
CLASS 21 EXCAVATION	CU.YDS.	150



DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
EASTBOUND BRIDGE - PIER I DETAILS
 STA. 356+70.31 (± OFF. REL. TO U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 7 OF 32 FILE NO. 29488 DESIGN NO. 1203






BENCH MARK #20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.

CONCRETE PLACEMENT PIER 2 - EASTBOUND BRIDGE

LOCATION	UNIT	QUANTITY
FOOTING	CU. YDS.	62.2
STEM	CU. YDS.	53.8
CAP & STEPS	CU. YDS.	41.2
TOTAL - CU.YDS.		157.2



NOTE: SEE DESIGN SHEET 9 FOR FOOTING PLAN AND OTHER PIER DETAILS.



TOTAL ESTIMATED QUANTITIES PIER 2 - EASTBOUND BRIDGE

ITEM	UNITS	QUANTITY
STRUCTURAL CONCRETE	CU. YDS.	157.2
REINFORCING STEEL	LBS.	21,852
HPI0x57 STEEL BEARING PILING	FURNISH 24 @ 20' DRIVE 24 @ 20'	LIN.FT. 480
CLASS 20 EXCAVATION	CU. YDS.	155
CLASS 21 EXCAVATION	CU. YDS.	150

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
EASTBOUND BRIDGE - PIER 2 DETAILS
 STA. 356+70.31 (± OFF. REL. OC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 8 OF 32 FILE NO. 29488 DESIGN NO. 1203

REINF. BAR LIST - EASTBOUND PIER 1					
BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
11a1	CAP, LONGIT., TOP	▬	20	48'-8	5171
7a2	CAP, LONGIT., SIDES	▬	6	48'-8	597
7a3	CAP, LONGIT., SIDES	▬	2	44'-8	183
7a4	CAP, LONGIT., SIDES	▬	2	36'-9	150
7a5	CAP, LONGIT., SIDES	▬	2	28'-10	118
6b1	CAP, LONGIT., BOTTOM	▬	4	26'-2	157
5c1	CAP HOOPS	□	28	18'-5	538
5c2	CAP HOOPS, CANTILEVER	□	32	VARIABLES	591
5c3	CAP HOOPS, CANTILEVER	□	48	VARIABLES	730
10d1	FOOTING TO STEM DOWELS	L	46	10'-7	2095
10d2	STEM, VERTICAL	▬	46	30'-0	5938
4e1	STEM HOOPS	□	54	28'-0	1010
4e2	STEM TIES AT ENDS	D	54	13'-6	487
5f1	FOOTING, TRANSV. - TOP	▬	28	14'-8	428
5f2	FOOTING, LONGIT. - TOP	▬	15	27'-8	433
8g1	FOOTING, TRANSV. - BOTTOM	▬	50	14'-8	1958
8g2	FOOTING, LONGIT. - BOTTOM	▬	20	27'-8	1477
5m1	CAP, STEPS, LONGIT.	▬	16	3'-0	50
8m2	CAP, STEPS, LONGIT.	▬	4	11'-7	124
5n1	CAP, STEPS, TRANSV.	▬	26	6'-6	176
REINFORCING STEEL TOTAL - (LBS.)					22,411

REINF. BAR LIST - EASTBOUND PIER 2					
BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
11a1	CAP, LONGIT., TOP	▬	20	48'-8	5171
7a2	CAP, LONGIT., SIDES	▬	6	48'-8	597
7a3	CAP, LONGIT., SIDES	▬	2	44'-8	183
7a4	CAP, LONGIT., SIDES	▬	2	36'-9	150
7a5	CAP, LONGIT., SIDES	▬	2	28'-10	118
6b1	CAP, LONGIT., BOTTOM	▬	4	26'-2	157
5c1	CAP HOOPS	□	28	18'-5	538
5c2	CAP HOOPS, CANTILEVER	□	32	VARIABLES	591
5c3	CAP HOOPS, CANTILEVER	□	48	VARIABLES	730
10d1	FOOTING TO STEM DOWELS	L	46	10'-7	2095
10d2	STEM, VERTICAL	▬	46	28'-6	5641
4e1	STEM HOOPS	□	50	28'-0	935
4e2	STEM TIES AT ENDS	D	50	13'-6	451
5f1	FOOTING, TRANSV. - TOP	▬	28	14'-8	428
5f2	FOOTING, LONGIT. - TOP	▬	15	27'-8	433
8g1	FOOTING, TRANSV. - BOTTOM	▬	50	14'-8	1958
8g2	FOOTING, LONGIT. - BOTTOM	▬	20	27'-8	1477
5m1	CAP, STEPS, LONGIT.	▬	20	3'-0	63
5n1	CAP, STEPS, TRANSV.	▬	20	6'-6	136
REINFORCING STEEL TOTAL - (LBS.)					21,852

REINF. BAR LIST - WESTBOUND PIER 1					
BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
11a1	CAP, LONGIT., TOP	▬	20	48'-8	5171
7a2	CAP, LONGIT., SIDES	▬	6	48'-8	597
7a3	CAP, LONGIT., SIDES	▬	2	44'-8	183
7a4	CAP, LONGIT., SIDES	▬	2	36'-9	150
7a5	CAP, LONGIT., SIDES	▬	2	28'-10	118
6b1	CAP, LONGIT., BOTTOM	▬	4	26'-2	157
5c1	CAP HOOPS	□	29	18'-5	538
5c2	CAP HOOPS, CANTILEVER	□	48	VARIABLES	730
5c3	CAP HOOPS, CANTILEVER	□	48	VARIABLES	730
10d1	FOOTING TO STEM DOWELS	L	46	10'-7	2095
10d2	STEM, VERTICAL	▬	46	28'-6	5641
4e1	STEM HOOPS	□	50	28'-0	935
4e2	STEM TIES AT ENDS	D	50	13'-6	451
5f1	FOOTING, TRANSV. - TOP	▬	28	14'-8	428
5f2	FOOTING, LONGIT. - TOP	▬	15	27'-8	433
8g1	FOOTING, TRANSV. - BOTTOM	▬	50	14'-8	1958
8g2	FOOTING, LONGIT. - BOTTOM	▬	20	27'-8	1477
5m1	CAP, STEPS, LONGIT.	▬	16	3'-0	50
8m2	CAP, STEPS, LONGIT.	▬	4	11'-7	124
5n1	CAP, STEPS, TRANSV.	▬	26	6'-6	176
REINFORCING STEEL TOTAL - (LBS.)					22,003

REINF. BAR LIST - WESTBOUND PIER 2					
BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
11a1	CAP, LONGIT., TOP	▬	20	48'-8	5171
7a2	CAP, LONGIT., SIDES	▬	6	48'-8	597
7a3	CAP, LONGIT., SIDES	▬	2	44'-8	183
7a4	CAP, LONGIT., SIDES	▬	2	36'-9	150
7a5	CAP, LONGIT., SIDES	▬	2	28'-10	118
6b1	CAP, LONGIT., BOTTOM	▬	4	26'-2	157
5c1	CAP HOOPS	□	28	18'-5	538
5c2	CAP HOOPS, CANTILEVER	□	32	VARIABLES	591
5c3	CAP HOOPS, CANTILEVER	□	48	VARIABLES	730
10d1	FOOTING TO STEM DOWELS	L	46	10'-7	2095
10d2	STEM, VERTICAL	▬	46	27'-0	5344
4e1	STEM HOOPS	□	48	28'-0	898
4e2	STEM TIES AT ENDS	D	48	13'-6	433
5f1	FOOTING, TRANSV. - TOP	▬	28	14'-8	428
5f2	FOOTING, LONGIT. - TOP	▬	15	27'-8	433
8g1	FOOTING, TRANSV. - BOTTOM	▬	50	14'-8	1958
8g2	FOOTING, LONGIT. - BOTTOM	▬	20	27'-8	1477
5m1	CAP, STEPS, LONGIT.	▬	16	3'-0	50
8m2	CAP, STEPS, LONGIT.	▬	4	11'-7	124
5n1	CAP, STEPS, TRANSV.	▬	26	6'-6	176
REINFORCING STEEL TOTAL - (LBS.)					21,651


PIER NOTES :

MINIMUM CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR IS TO BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN

CONSTRUCTION JOINTS ARE TO BE FORMED WITH A 3 x 10 x 16'-0 DRESSED AND BEVELED STRIP.

THE DESIGN BEARING FOR THE PIER PILES IS 45 TONS.

ALL BATTERED PILES SHALL BE TRIMMED TO A HORIZONTAL LINE TO AID IN THE PLACEMENT OF REINFORCING.




PILE PLAN

(TYPICAL FOR ALL PIERS)

NOTE : DIMENSIONS SHOWN ARE AT BOTTOM OF FOOTING. BATTER PILES 1:4 IN THE DIRECTION SHOWN.

24 - HP10x57 STEEL BEARING PILING REQUIRED AT EACH PIER.

BENT BAR DETAILS




NOTE : ALL DIMENSIONS ARE OUT TO OUT. D = PIN DIAMETER.

TOTAL ESTIMATED PIER QUANTITIES			
ITEM	UNITS	WESTBOUND BRIDGE	EASTBOUND BRIDGE
STRUCTURAL CONCRETE	CU.YDS	312.0	317.8
REINFORCING STEEL	LBS.	43,627	44,263
HP10x57 STEEL	LIN.FT.	960	960
BEARING PILING DRIVE	LIN.FT.	960	960
CLASS 20 EXCAVATION	CU.YDS	300	310
CLASS 21 EXCAVATION	CU.YDS	305	300

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0 x 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9 & 60'-9 END SPANS 91'-6 INTERIOR SPAN
PIER DETAILS
 STA. 356+70.31 (OFF. RELOC. U.S.34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 9 OF 32 FILE NO. 29488 DESIGN NO. 1203


BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.



PART REAR ELEVATION AT ABUTMENT (WINGS NOT SHOWN)

NOTE:
10 - HP10 x 57 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.


NOTE: BARRIER RAIL NOT SHOWN IN DETAILS.




PART SECTION B-B

NOTE:
THE SPIRAL AT THE TOP OF EACH PILE TO BE 7 TURNS OF NO. 2 BAR, 21" DIAMETER, 3" PITCH WITH 2 - 1/2" x 1/2" x 1/2" SPACERS PUNCHED TO HOLD SPIRAL.

NOTE:
PLUG 3" PVC PIPE WITH EXPANDING FOAM PRIOR TO BACKFILLING BEHIND ABUTMENTS.



PART SECTION



PART SECTION A - A


NOTE:
SHIFT 8g1 BARS IN F.F. AS NECESSARY TO MISS BEAMS. PLACE 8g3 BARS PARALLEL TO LONGIT. STEEL.

* NOTE:
SEE DESIGN SHEET 27 FOR DETAILS OF BARRIER RAIL. REINFORCING BARS 5c3 AND 5c4 ARE INCLUDED IN SUPERSTRUCTURE QUANTITIES.


SPACING FOR:
35 - 8g1 BACK FACE
31 - 8g1 FRONT FACE
31 - 8g3 BACK FACE
32 - 5k1 & 5k2 BACK FACE

ABUTMENT NOTES:

MINIMUM CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR IS TO BE 2" UNLESS OTHERWISE NOTED OR SHOWN.
IF NECESSARY TO PREVENT DAMAGE TO THE END OF THE BRIDGE DECK OR BACKWALL FROM CONSTRUCTION EQUIPMENT, AN APPROPRIATE METHOD OF PROTECTION APPROVED BY THE ENGINEER SHALL BE PROVIDED BY THE BRIDGE CONTRACTOR AT NO EXTRA COST TO THE STATE.



PART SECTION C-C



ABUTMENT EXCAVATION DETAILS


DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
ABUTMENT DETAILS
STA. 356+70.31 (E. OFF. RELOC. ILS.34) MAY, 2006
JEFFERSON COUNTY
IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. 10 OF 32 FILE NO. 29488 DESIGN NO. 1203

REVISED 12-04 - SIZE AND DIMENSIONS OF PAVING NOTCH CHANGED. TEMPORARY PAVING NOTCH REMOVED. ENGLISH INTEGRAL BRIDGES.DGN 2088 - THIS SHEET REDRAWN 9-8-88

DESIGN TEAM EDS/GJK/DLB	"C" OR "D" BEAMS - INTEGRAL ABUT. DETAILS - (L.A.) 15°01' - 30° SKEW	STANDARD SHEET 2088	JEFFERSON COUNTY	PROJECT NUMBER NHSN-034-8(105)-2R-51	SHEET NUMBER 11
-------------------------	--	---------------------	------------------	--------------------------------------	-----------------

27-APR-2006 07:08 dbackou W:\Projects\51034030A94\BRF\Ina\51034105.1203.brg 511203s010 \\NTP\PRTSVR2\BrgTlf


BENCH MARK: 20" - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE.
ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 692.415.




WEST ABUTMENT EAST ABUTMENT

WESTBOUND BRIDGE - ABUTMENT PILE PLAN

NOTES:
10 - HP10 x 57 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.
THE DESIGN BEARING FOR THE ABUTMENT PILES IS 47 TONS.




REAR ELEVATION - WEST ABUTMENT WESTBOUND BRIDGE



REAR ELEVATION - EAST ABUTMENT WESTBOUND BRIDGE

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
WESTBOUND BRIDGE ABUT. DETAILS
STA. 356+70.31 (C. OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. 11 OF 32 FILE NO. 29488 DESIGN NO. 1203

BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE
ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.




WEST ABUTMENT

EAST ABUTMENT


EASTBOUND BRIDGE - ABUTMENT PILE PLAN

NOTES:
10 - HP10 x 57 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.

THE DESIGN BEARING FOR THE ABUTMENT PILES IS 45 TONS.




REAR ELEVATION - WEST ABUTMENT
EASTBOUND BRIDGE



REAR ELEVATION - EAST ABUTMENT
EASTBOUND BRIDGE

DESIGN FOR 32° SKEW (L.A.)
**DUAL 223'-0" x 40'-0" PRETENSIONED
PRESTRESSED CONCRETE BEAM BRIDGES**
70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
EASTBOUND BRIDGE ABUT. DETAILS
STA. 356+70.31 (C. OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. 12 OF 32 FILE NO. 29488 DESIGN NO. 1203

SLAB AREA = 24.99 SQ. FT.
 SLAB AREA DOES NOT INCLUDE THE NOMINAL 1/2 INCH HAUNCH.




FOR DETAILS OF RAIL AND RAIL REINFORCING SEE STANDARD BARRIER RAIL SHEET.

HALF SECTION NEAR ABUTMENT


HALF SECTION NEAR PIER NO. 2

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET 23.

- (A)-(F) WESTBOUND BRIDGE - LOOKING EAST
- (G)-(L) EASTBOUND BRIDGE - LOOKING WEST




INTERIOR BEAMS



DRAIN DETAILS


NOTE: DRAINS ARE TO BE GALVANIZED. DRAINS REQUIRED. SEE "SITUATION PLAN" ON DESIGN SHEET 2 FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "STRUCTURAL STEEL". WEIGHT (106 LBS./DRAIN) IS BASED ON ROLLED THIRF. (LENGTH = 5'-5")



EXTERIOR BEAMS

TYPICAL SLAB AND HAUNCH DETAIL

* FOR SLAB THICKNESS OVER BEAMS SEE * SLAB THICKNESS DETAILS * ON DESIGN SHEET NO. 17 AND 18.



PART SECTION NEAR PIER NO. 1

NOTE: SOLE PLATE AND PINTLE PLATES NOT SHOWN. SEE DESIGN SHEET 22.

SUPERSTRUCTURE NOTES:

- THE FLOOR SLAB AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
- THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE FLOOR SLAB.
- COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
- ALL BEAMS ARE TO BE SET VERTICAL.
- FORMS FOR THE SLAB AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
- CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
- ALL SLAB AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
- TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2" CLEAR BELOW TOP OF SLAB. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF SLAB.
- TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL EPOXY COATED METAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0" CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF EPOXY COATED METAL BAR HIGH CHAIRS OR SLAB BOLSTERS SPACED 4'-0" APART.
- COST OF BEARING MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "PRETENSIONED PRESTRESSED CONCRETE BEAMS".

DESIGN FOR 32° SKEW (L.A.)

DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES

10'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN

SUPERSTRUCTURE DETAILS

STA. 356+70.31 (C. OFF. RELOC. U.S.34) MAY, 2006

JEFFERSON COUNTY


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION

DESIGN SHEET NO. 13 OF 32 FILE NO. 29488 DESIGN NO. 1203


REVISED: 07-20-06; NUMBER OF DRAINS CHANGED.

REVISED DRAWING - FOOTING EXTENDED 1'-0" TO ACCOMMODATE C AND D BEAMS. NOTE ADDED TO ADJUST FOR A AND B BEAMS. 110' & 115' B2 BARS ADDED. ENGLISH INTEGRAL WEARING SURFACE - THIS SHEET REDRAWN 9-8-18

DESIGN TEAM EDS/GJR/DLB	40' ROWY, PPCB (ALL BEAMS - INTEGRAL ABUT.) CROSS SECTION	STANDARD SHEET 4383 MODIFIED	JEFFERSON COUNTY	PROJECT NUMBER NPSN-034-8105)-2R-51	SHEET NUMBER 14
-------------------------	---	------------------------------	------------------	-------------------------------------	-----------------




PART LONGITUDINAL SECTION NEAR GUTTER
(FOR DETAILS OF INTERMEDIATE DIAPHRAGM SEE DESIGN SHEET 23)



PART END VIEW AT ABUTMENT




PART SECTION C-C




PART PLAN

(WESTBOUND BRIDGE SHOWN, EASTBOUND BRIDGE SIMILAR.)



PART SECTION AT PIER NO. 1
EXPANSION PIER

PART SECTION AT PIER NO. 2
FIXED PIER




DETAIL "C"

TABLE OF WINGWALL ELEVATIONS

LOCATION	DIM "C"	ELEV. A	ELEV. B	ELEV. C
WESTBOUND N.W. CORNER	7 3/4	700.70	700.88	701.04
WESTBOUND S.W. CORNER	6 1/2	701.33	701.51	701.67
WESTBOUND N.E. CORNER	17'-0 3/8	697.08	696.99	696.92
WESTBOUND S.E. CORNER	17'-0 3/8	697.46	697.36	697.28
EASTBOUND N.W. CORNER	7 1/2	702.10	702.28	702.43
EASTBOUND S.W. CORNER	7	702.57	702.75	702.90
EASTBOUND N.E. CORNER	17'-1 1/4	697.93	697.81	697.71
EASTBOUND S.E. CORNER	17'-1 1/4	698.21	698.09	697.98


NOTE :
CONDUIT AND JUNCTION BOXES TO BE PLACED IN NORTH RAIL OF WESTBOUND BRIDGE AND PLACED IN SOUTH RAIL OF EASTBOUND BRIDGE.



SECTION A-A

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
SUPERSTRUCTURE DETAILS
 STA. 356+70.31 (± OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 14 OF 32 FILE NO. 29488 DESIGN NO. 1203


REVISED 07-05 - 3" PVC PIPE ADDED TO WING EXTENSIONS AND NOTE. ENGLISH INTEGRAL BRIDGES.DGN 4510 - THIS SHEET REDRAWN 9-8-88



CONCRETE PLACEMENT DIAGRAM AND LONGITUDINAL REINFORCING LAYOUT

NOTE:
 ROADWAY SLAB SHALL BE PLACED IN SECTIONS AND IN SEQUENCE INDICATED. ALTERNATE PROCEDURES FOR PLACING SLAB CONCRETE MAY BE SUBMITTED FOR APPROVAL TOGETHER WITH A STATEMENT OF THE PROPOSED METHOD AND EVIDENCE THAT THE CONTRACTOR POSSESSES THE NECESSARY EQUIPMENT AND FACILITIES TO ACCOMPLISH THE REQUIRED RESULT.


* BARS SHALL BE CENTERED OVER PIER



TRANSVERSE SLAB CONSTRUCTION JOINT

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0 x 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9 & 60'-9 END SPANS 91'-6 INTERIOR SPAN
SUPERSTRUCTURE DETAILS
 STA. 356+70.31 (CL. OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 15 OF 32 FILE NO. 29488 DESIGN NO. 1203

BENT BAR DETAILS



NOTE: ALL DIMENSIONS ARE OUT TO OUT. D= PIN DIAMETER.

REINFORCING BAR LIST - EPOXY COATED
(ONE SUPERSTRUCTURE AND TWO ABUTMENTS)

BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
6a1	SLAB TRANSV. TOP & BOT.		483	42'-10"	31,074
6a2	SLAB TRANSV. TOP ENDS		60	VARIES	1,895
6a3	SLAB TRANSV. BOT. ENDS		60	VARIES	1,945
5b1	SLAB LONGITUDINAL, TOP & BOT.		582	39'-5"	23,927
8b2	SLAB LONGITUDINAL @ PIER 1		92	22'-6"	5,527
5d1	PIER DIAPH. ENDS		12	3'-8"	46
5d2	PIER & ABUT. DIAPH. LONGIT.		90	7'-10"	735
5d3	PIER & ABUT. DIAPH. LONGIT.		30	6'-4"	198
5d4	PIER DIAPH. LONGIT.		10	10'-10"	113
5d5	ABUT. DIAPH. ENDS		12	5'-7"	70
5d6	ABUT. DIAPH. LONGIT. B.F.		16	26'-2"	437
5d7	PAVING NOTCH LONGIT.		8	26'-6"	221
5d8	ABUT. DIAPH. WING EXT. LONGIT.		48	11'-0"	551
5e1	PIER DIAPH. HOOPS - PIER 2		20	12'-10"	268
5e2	PIER DIAPH. TIES ENDS		4	2'-8"	11
5e3	PIER DIAPH. TIES		40	3'-5"	143
5e4	PIER DIAPH. HOOPS ENDS - PIER 2		2	12'-1"	25
5e5	PIER DIAPH. HOOPS - PIER 1		20	12'-6"	261
5e6	PIER DIAPH. HOOPS ENDS - PIER 1		2	11'-9"	25
8f1	ABUT. FOOTING LONGIT.		36	27'-6"	2,643
8f3	ABUT. EXTENSION LONGIT.		16	10'-4"	441
8f4	ABUT. EXTENSION LONGIT.		8	7'-9"	166
8f5	ABUT. EXTENSION LONGIT.		8	9'-1"	194
8g1	ABUT. VERT.		132	8'-6"	2,996
8g3	ABUT. DIAPH. VERT. B.F.		62	16'-6"	2,731
6g4	ABUT. DIAPH. WING EXT. VERT.		40	7'-3"	436
5h1	ABUT. WING HORIZ.		56	6'-8"	389
5h2	ABUT. TO WING ANCHOR		8	4'-7"	38
5j1	TOP OF SLAB TRANSV. (AT RAIL)		536	6'-3"	3,494
5k1	PAVING NOTCH TRANSV.		64	4'-9"	317
5k2	PAVING NOTCH TRANSV.		64	3'-5"	228
5p1	ABUTMENT HOOPS		148	10'-6"	1,621
5p2	ABUT. EXTENSION HOOPS		24	10'-8"	267
6p3	ABUT. BOT. AT PILES		32	6'-8"	320
5p4	ABUT. HOOPS AT ENDS		8	11'-6"	96
5s1	WING VERT.		56	VARIES	263
4t1	UNDER BEAMS AT ABUTMENTS		12	4'-9"	38
#2	PILE SPIRAL		20	38'-6"	129
	SPIRAL SPACERS, L 7/8 x 7/8 x 1/8 x 0.70		40	1'-10"	51
BARRIER RAIL - SEE DESIGN SHT. NO. 29					12,209
REINFORCING STEEL (EPOXY COATED) - TOTAL (LBS.)					96,529

CONCRETE PLACEMENT QUANTITIES - C.Y.
(ONE SUPERSTRUCTURE AND TWO ABUTMENTS)

SECTION	TOTAL
SECTION 1 - SLAB, ABUT. DIAPH., WINGWALLS	99.9
SECTION 2 - SLAB	76.3
SECTION 3 - SLAB, ABUT. DIAPH., WINGWALLS	88.6
SECTION 4 - SLAB, PIER DIAPH.	44.8
SECTION 5 - SLAB, PIER DIAPH.	45.6
WEST ABUTMENT FOOTING	26.4
EAST ABUTMENT FOOTING	25.6
ABUT. WINGS 4 AT 1.7 C.U.YS. EACH	6.8
TOTAL C.Y.	414.0


ESTIMATED QUANTITIES - SUPERSTRUCTURE
(ONE SUPERSTRUCTURE AND TWO ABUTMENTS)

ITEM	UNIT	QUANTITY
STRUCTURAL CONCRETE (BRIDGE)	C.U.YD.	414.0
STRUCTURAL STEEL	LBS.	7106
REINFORCING STEEL EPOXY COATED	LBS.	96,529
PRETENSIONED PRESTRESSED CONCRETE BEAMS LXD60	EACH	6
PRETENSIONED PRESTRESSED CONCRETE BEAMS LXD70	EACH	6
PRETENSIONED PRESTRESSED CONCRETE BEAMS LXD90	EACH	6
CLASS 20 EXCAVATION	C.U.YD.	160
HP10X51 STEEL FURNISH 10 @ 40' W. A. & 10 @ 50' E.A.	L.F.	900
BEARING PILING DRIVE 10 @ 40' W. A. & 10 @ 50' E.A.	L.F.	900
PREBORED HOLES 20 @ 10'	L.F.	200

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
SUPERSTRUCTURE DETAILS-WESTWOLD BRIDGE
 STA. 356+70.31 (E. OFF. REL. OC. ILLS.34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 16 OF 32 FILE NO. 29488 DESIGN NO. 1203

HE52 -S01 THIS SHEET ISSUED 7-7-27-02.

BENT BAR DETAILS



NOTE: ALL DIMENSIONS ARE OUT TO OUT. D= PIN DIAMETER.

REINFORCING BAR LIST - EPOXY COATED
(ONE SUPERSTRUCTURE AND TWO ABUTMENTS)

BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
6a1	SLAB TRANSV. TOP & BOT.		483	42'-10	31,074
6a2	SLAB TRANSV. TOP ENDS		60	VARIES	1,895
6a3	SLAB TRANSV. BOT. ENDS		60	VARIES	1,945
5b1	SLAB LONGITUDINAL, TOP & BOT.		582	39'-5	23,927
5b2	SLAB LONGITUDINAL @ PIER 1		92	22'-6	5,527
5d1	PIER DIAPH. ENDS		12	3'-8	46
5d2	PIER & ABUT. DIAPH. LONGIT.		90	7'-10	735
5d3	PIER & ABUT. DIAPH. LONGIT.		30	6'-4	198
5d4	PIER DIAPH. LONGIT.		10	10'-10	113
5d5	ABUT. DIAPH. ENDS		12	5'-7	70
5d6	ABUT. DIAPH. LONGIT. B.F.		16	26'-2	437
5d7	PAVING NOTCH LONGIT.		8	26'-6	221
5d8	ABUT. DIAPH. WING EXT. LONGIT.		48	11'-0	551
5e1	PIER DIAPH. HOOPS - PIER 2		20	12'-10	268
5e2	PIER DIAPH. TIES ENDS		4	2'-8	11
5e3	PIER DIAPH. TIES		40	3'-5	143
5e4	PIER DIAPH. HOOPS ENDS - PIER 2		2	12'-1	25
5e5	PIER DIAPH. HOOPS - PIER 1		20	12'-6	261
5e6	PIER DIAPH. HOOPS ENDS - PIER 1		2	11'-9	25
8f1	ABUT. FOOTING LONGIT.		36	27'-6	2,643
8f3	ABUT. EXTENSION LONGIT.		16	10'-4	441
8f4	ABUT. EXTENSION LONGIT.		8	7'-9	166
8f5	ABUT. EXTENSION LONGIT.		8	9'-1	194
8g1	ABUT. VERT.		132	8'-6	2,996
8g3	ABUT. DIAPH. VERT. B.F.		62	16'-6	2,731
6g4	ABUT. DIAPH. WING EXT. VERT.		40	7'-3	436
5h1	ABUT. WING HORIZ.		56	6'-8	389
5h2	ABUT. TO WING ANCHOR		8	4'-7	38
5j1	TOP OF SLAB TRANSV. (AT RAIL)		536	6'-3	3,494
5k1	PAVING NOTCH TRANSV.		64	4'-9	317
5k2	PAVING NOTCH TRANSV.		64	3'-5	228
5p1	ABUTMENT HOOPS		148	10'-6	1,621
5p2	ABUT. EXTENSION HOOPS		24	10'-8	267
6p3	ABUT. BOT. AT PILES		32	6'-8	320
5p4	ABUT. HOOPS AT ENDS		8	11'-6	96
5s1	WING VERT.		56	VARIES	263
4t1	UNDER BEAMS AT ABUTMENTS		12	4'-9	38
#2	PILE SPIRAL		20	38'-6	129
	SPIRAL SPACERS, L 7/8 x 7/8 x 1/8 x 0.70		40	1'-10	51
BARRIER RAIL - SEE DESIGN SHT. NO. 29					12,209
REINFORCING STEEL (EPOXY COATED) - TOTAL (LBS.)					96,529

CONCRETE PLACEMENT QUANTITIES - C.Y.
(ONE SUPERSTRUCTURE AND TWO ABUTMENTS)

SECTION	TOTAL
SECTION 1 - SLAB, ABUT. DIAPH., WINGWALLS	99.8
SECTION 2 - SLAB	76.3
SECTION 3 - SLAB, ABUT. DIAPH., WINGWALLS	88.6
SECTION 4 - SLAB, PIER DIAPH.	44.8
SECTION 5 - SLAB, PIER DIAPH.	45.5
WEST ABUTMENT FOOTING	25.8
EAST ABUTMENT FOOTING	25.2
ABUT. WINGS 4 AT 1.7 C.U.YS. EACH	6.8
TOTAL C.Y.	412.8

ESTIMATED QUANTITIES - SUPERSTRUCTURE
(ONE SUPERSTRUCTURE AND TWO ABUTMENTS)

ITEM	UNIT	QUANTITY
STRUCTURAL CONCRETE (BRIDGE)	C.U.YD.	412.8
STRUCTURAL STEEL	LBS.	7106
REINFORCING STEEL EPOXY COATED	LBS.	96,529
PRETENSIONED PRESTRESSED CONCRETE BEAMS LXD60	EACH	6
PRETENSIONED PRESTRESSED CONCRETE BEAMS LXD70	EACH	6
PRETENSIONED PRESTRESSED CONCRETE BEAMS LXD90	EACH	6
CLASS 20 EXCAVATION	C.U.YD.	160
HP10X51 STEEL FURNISH 10 @ 45' W. A. ; 10 @ 50' E.A.	L.F.	950
BEARING PILING DRIVE 10 @ 45' W. A. ; 10 @ 50' E.A.	L.F.	950
PREBORED HOLES 20 @ 10'	L.F.	200

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0 x 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9 & 60'-9 END SPANS 91'-6 INTERIOR SPAN
SUPERSTRUCTURE DETAILS-EASTWARD BRIDGE
 STA. 356+70.31 (E. OFF. REL. OC. ILS.34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 17 OF 32 FILE NO. 29488 DESIGN NO. 1203

HE52 -S01 THIS SHEET ISSUED 7-7-27-02.






TABLE OF TOP OF SLAB ELEVATIONS - WESTBOUND BRIDGE

LOCATION	ℓ W. ABUT. BRG.								ℓ PIER NO. 1 BEARINGS										ℓ PIER NO. 2 BEARINGS						ℓ E. ABUT. BRG.		
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24		25	26
GUTTER LINE	700.74	700.55	700.37	700.19	700.01	699.83	699.66	699.50	699.33	699.31	699.14	698.98	698.83	698.67	698.53	698.38	698.24	698.11	697.97	697.84	697.82	697.68	697.55	697.42	697.30	697.18	697.06
BEAM LINE A	700.79	700.60	700.42	700.24	700.06	699.88	699.71	699.54	699.38	699.35	699.19	699.03	698.87	698.72	698.57	698.43	698.29	698.15	698.02	697.89	697.87	697.73	697.59	697.46	697.34	697.22	697.10
BEAM LINE B	701.04	700.85	700.66	700.48	700.30	700.12	699.95	699.78	699.61	699.59	699.42	699.26	699.10	698.95	698.80	698.65	698.51	698.37	698.23	698.10	698.08	697.94	697.80	697.67	697.54	697.42	697.31
BEAM LINE C	701.29	701.10	700.91	700.72	700.54	700.36	700.19	700.02	699.85	699.82	699.65	699.49	699.33	699.17	699.02	698.87	698.73	698.59	698.45	698.32	698.29	698.15	698.01	697.88	697.75	697.63	697.51
ℓ APPROACH ROADWAY	701.45	701.26	701.07	700.88	700.70	700.52	700.34	700.17	700.00	699.97	699.80	699.64	699.48	699.32	699.17	699.02	698.87	698.73	698.59	698.45	698.43	698.29	698.15	698.01	697.88	697.75	697.63
BEAM LINE D	701.47	701.28	701.09	700.90	700.72	700.54	700.36	700.19	700.02	699.99	699.82	699.65	699.49	699.33	699.18	699.03	698.88	698.74	698.60	698.46	698.44	698.30	698.15	698.02	697.89	697.76	697.64
BEAM LINE E	701.43	701.23	701.04	700.85	700.67	700.48	700.31	700.13	699.96	699.93	699.76	699.59	699.43	699.27	699.11	698.96	698.81	698.66	698.52	698.38	698.36	698.22	698.07	697.93	697.80	697.67	697.55
BEAM LINE F	701.38	701.19	700.99	700.80	700.62	700.43	700.25	700.07	699.90	699.87	699.70	699.53	699.36	699.20	699.04	698.89	698.74	698.59	698.45	698.31	698.28	698.13	697.99	697.85	697.71	697.58	697.46
GUTTER LINE	701.37	701.18	700.99	700.79	700.61	700.42	700.24	700.06	699.89	699.86	699.69	699.52	699.35	699.19	699.03	698.87	698.72	698.57	698.43	698.29	698.27	698.12	697.97	697.83	697.70	697.57	697.44



NOTE: THE SLAB THICKNESS (T) AT BEAMS IS BASED ON THE ANTICIPATED BEAM CAMBER AND DEFLECTIONS. THESE VALUES ARE USED BY THE DESIGNER TO SET BEAM ELEVATIONS AND ESTIMATE CONCRETE QUANTITIES. REFER TO HAUNCH DATA DETAIL SHEET FOR ADDITIONAL INFORMATION TO AID THE CONTRACTOR IN SETTING THE FIELD HAUNCHES REQUIRED FOR CONSTRUCTION.

DESIGN FOR 32° SKEW (L.A.)

**DUAL 223'-0" x 40'-0" PRETENSIONED
PRESTRESSED CONCRETE BEAM BRIDGES**

70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN

SUPERSTRUCTURE DETAILS - WESTBOUND

STA. 356+70.31 (ℓ OFF. RELOC. U.S. 34) MAY, 2006

JEFFERSON COUNTY

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION

DESIGN SHEET NO. 18 OF 32 FILE NO. 29488 DESIGN NO. 1203

BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.






TABLE OF TOP OF SLAB ELEVATIONS - EASTBOUND BRIDGE

LOCATION	ϕ W. ABUT. BRG.								ϕ PIER NO. 1 BEARINGS										ϕ PIER NO. 2 BEARINGS						ϕ E. ABUT. BRG.		
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
GUTTER LINE	702.14	701.94	701.75	701.56	701.37	701.17	700.98	700.79	700.60	700.57	700.38	700.20	700.02	699.84	699.66	699.49	699.33	699.17	699.01	698.85	698.83	698.66	698.50	698.34	698.19	698.04	697.90
BEAM LINE G	702.19	701.99	701.80	701.61	701.42	701.23	701.03	700.84	700.65	700.62	700.43	700.25	700.06	699.89	699.71	699.54	699.38	699.21	699.05	698.90	698.87	698.71	698.54	698.39	698.23	698.09	697.94
BEAM LINE H	702.44	702.24	702.05	701.86	701.67	701.47	701.28	701.09	700.90	700.87	700.68	700.49	700.31	700.13	699.95	699.78	699.61	699.44	699.28	699.13	699.10	698.93	698.77	698.61	698.45	698.30	698.16
BEAM LINE I	702.68	702.49	702.30	702.11	701.92	701.72	701.53	701.34	701.15	701.11	700.92	700.73	700.55	700.36	700.19	700.01	699.84	699.68	699.51	699.35	699.33	699.16	698.99	698.83	698.67	698.52	698.37
ϕ APPROACH ROADWAY	702.71	702.52	702.33	702.14	701.94	701.75	701.56	701.37	701.18	701.14	700.95	700.76	700.57	700.39	700.21	700.04	699.87	699.70	699.54	699.38	699.35	699.18	699.01	698.85	698.69	698.54	698.39
BEAM LINE J	702.71	702.51	702.32	702.13	701.94	701.75	701.55	701.36	701.17	701.14	700.94	700.75	700.56	700.38	700.20	700.02	699.85	699.68	699.52	699.36	699.33	699.16	698.99	698.82	698.66	698.51	698.36
BEAM LINE K	702.66	702.47	702.28	702.08	701.89	701.70	701.51	701.32	701.12	701.09	700.89	700.70	700.51	700.32	700.14	699.96	699.79	699.62	699.45	699.29	699.26	699.09	698.92	698.75	698.59	698.43	698.28
BEAM LINE L	702.61	702.42	702.23	702.04	701.85	701.65	701.46	701.27	701.08	701.04	700.85	700.65	700.46	700.27	700.09	699.91	699.73	699.56	699.39	699.23	699.20	699.02	698.85	698.68	698.51	698.36	698.20
GUTTER LINE	702.60	702.41	702.22	702.03	701.84	701.64	701.45	701.26	701.07	701.03	700.84	700.64	700.45	700.26	700.08	699.90	699.72	699.55	699.38	699.21	699.18	699.01	698.83	698.66	698.50	698.34	698.19



SLAB THICKNESS DETAILS

NOTE: THE SLAB THICKNESS (T) AT BEAMS IS BASED ON THE ANTICIPATED BEAM CAMBER AND DEFLECTIONS. THESE VALUES ARE USED BY THE DESIGNER TO SET BEAM ELEVATIONS AND ESTIMATE CONCRETE QUANTITIES. REFER TO HAUNCH DATA DETAIL SHEET FOR ADDITIONAL INFORMATION TO AID THE CONTRACTOR IN SETTING THE FIELD HAUNCHES REQUIRED FOR CONSTRUCTION.

DESIGN FOR 32° SKEW (L.A.)

DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES

70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN

SUPERSTRUCTURE DETAILS - EASTBOUND

STA. 356+70.31 (ϕ OFF. RELOC. U.S. 34) MAY, 2006

JEFFERSON COUNTY

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION

DESIGN SHEET NO. 19 OF 32 FILE NO. 29488 DESIGN NO. 1203

BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE
ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.


TABLE OF BEAM LINE HAUNCH ELEVATIONS - WESTBOUND BRIDGE (SEE NOTE 1)																											
	W. ABUT. BEARING								PIER #1 BEARINGS									PIER #2 BEARINGS						E. ABUT. BEARING			
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
BEAM LINE A	700.12	699.95	699.78	699.61	699.43	699.26	699.08	698.90	698.71	698.69	698.56	698.43	698.30	698.16	698.01	697.86	697.71	697.55	697.39	697.22	697.20	697.07	696.95	696.82	696.69	696.57	696.44
BEAM LINE B	700.37	700.20	700.03	699.85	699.67	699.50	699.31	699.13	698.95	698.92	698.79	698.66	698.52	698.38	698.24	698.09	697.93	697.77	697.60	697.43	697.41	697.28	697.16	697.03	696.90	696.77	696.64
BEAM LINE C	700.62	700.45	700.27	700.10	699.92	699.74	699.55	699.37	699.18	699.15	699.03	698.89	698.75	698.61	698.46	698.31	698.15	697.99	697.82	697.65	697.63	697.50	697.37	697.24	697.10	696.97	696.84
BEAM LINE D	700.80	700.63	700.45	700.27	700.09	699.91	699.72	699.54	699.35	699.32	699.19	699.06	698.91	698.77	698.62	698.46	698.30	698.14	697.97	697.80	697.77	697.64	697.51	697.38	697.24	697.11	696.97
BEAM LINE E	700.76	700.58	700.41	700.22	700.04	699.86	699.67	699.48	699.29	699.26	699.13	698.99	698.85	698.70	698.55	698.39	698.23	698.07	697.89	697.72	697.70	697.56	697.43	697.29	697.16	697.02	696.88
BEAM LINE F	700.71	700.54	700.36	700.18	699.99	699.80	699.62	699.43	699.23	699.20	699.07	698.93	698.79	698.64	698.48	698.32	698.16	697.99	697.82	697.64	697.62	697.48	697.34	697.21	697.07	696.93	696.79

MISCELLANEOUS DATA TABLE

	BEAM LINE	W. ABUT. BEARING								PIER #1 BEARINGS									PIER #2 BEARINGS						E. ABUT. BEARING			
		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23		24	25	26
ANTICIPATED DEFLECTION DUE TO SLAB (in.)	ALL	0	1/4	3/8	1/2	1/2	1/2	3/8	1/4	0	0	1/2	3/8	1/8	1/4	3/8	1/4	1/8	3/8	1/2	0	0	3/8	1/4	5/8	1/4	3/8	0
CROSS SLOPE ADJUSTMENTS	A, B, C, E, F																	+2/16, -3/16										
	D																	+1/16, -1/8										
ALLOWABLE FIELD HAUNCH	MAX.																	2										
	MIN.																	-5/16										

NOTE 1 :
TO CALCULATE FIELD HAUNCHES REQUIRED AT EACH LOCATION, SURVEY THE BEAM TOPS CONSISTENT WITH THE SPACINGS SHOWN ON THE "TOP OF SLAB ELEVATIONS LAYOUT" ON DESIGN SHEET 18. SUBTRACT THE SURVEYED BEAM SHOT FROM THE "BEAM LINE HAUNCH ELEVATION". THIS VALUE WILL BE THE HAUNCH NEEDED (SEE "FIELD HAUNCH" IN HAUNCH DETAIL). THE "BEAM LINE HAUNCH ELEVATION" INCLUDES ADJUSTMENTS FOR SLAB THICKNESSES AND ANTICIPATED DEFLECTIONS. NO ADDITIONAL CALCULATIONS ARE REQUIRED. IF THE FIELD HAUNCH EXCEEDS THE MAXIMUMS AND MINIMUMS INDICATED IN THE MISCELLANEOUS DATA TABLE, ADJUSTMENTS TO THE GRADE OR ADDITIONAL HAUNCH REINFORCEMENT WILL BE REQUIRED.

NOTE :
HAUNCH LOCATIONS ARE AT THE SAME LOCATION AS THE ENCIRCLED LETTERS AND NUMBERS SHOWN ON DESIGN SHEET 18.



NOTE:
BRIDGE SEAT ELEVATIONS ARE SET BASED ON THEORETICAL CAMBER AND BEAM DEFLECTIONS. THESE BRIDGE SEATS WILL PROVIDE A THEORETICAL BEAM HAUNCH WITHIN DESIGN PARAMETERS. ACTUAL HAUNCHES ARE DETERMINED USING SURVEYED TOP OF BEAM ELEVATIONS AND "BEAM LINE HAUNCH ELEVATION" DATA. ALLOWABLE MAXIMUM AND MINIMUM "FIELD HAUNCH" VALUES ARE GIVEN IN THE "MISCELLANEOUS DATA" TABLE. "CROSS SLOPE ADJUSTMENT" VALUES FROM THE "MISCELLANEOUS DATA" TABLE WILL AID THE CONTRACTOR IN DETERMINING ACTUAL FORMED HAUNCH DIMENSIONS AT THE EDGES OF THE TOP FLANGE.

DESIGN FOR 32° SKEW (L.A.)
**DUAL 223'-0" x 40'-0" PRETENSIONED
 PRESTRESSED CONCRETE BEAM BRIDGES**
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
HAUNCH DATA DETAILS - WESTBOUND
 STA. 356+70.31 (E. OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 20 OF 32 FILE NO. 29488 DESIGN NO. 1203

BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE
ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.


TABLE OF BEAM LINE HAUNCH ELEVATIONS - EASTBOUND BRIDGE (SEE NOTE 1)																											
	W. ABUT. BEARING								PIER #1 BEARINGS										PIER #2 BEARINGS						E. ABUT. BEARING		
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24		25	26
BEAM LINE G	701.52	701.35	701.17	700.99	700.80	700.60	700.40	700.20	699.99	699.95	699.81	699.65	699.49	699.33	699.16	699.09	699.81	698.62	698.43	698.23	698.21	698.05	697.90	697.75	697.59	697.43	697.28
BEAM LINE H	701.77	701.60	701.42	701.24	701.05	700.85	700.65	700.44	700.23	700.20	700.05	700.90	699.74	699.57	699.40	699.22	699.04	698.85	698.66	698.46	698.43	698.28	698.12	697.97	697.81	697.65	697.49
BEAM LINE I	702.02	701.85	701.67	701.48	701.30	701.10	700.90	700.69	700.48	700.45	700.30	700.14	699.98	699.81	699.63	699.46	699.27	699.08	698.89	698.69	698.66	698.50	698.35	698.19	698.03	697.87	697.70
BEAM LINE J	702.04	701.87	701.69	701.51	701.32	701.12	700.92	700.72	700.50	700.47	700.32	700.16	699.99	699.82	699.65	699.47	699.28	699.09	698.89	698.69	698.66	698.50	698.34	698.18	698.02	697.86	697.69
BEAM LINE K	701.99	701.82	701.64	701.46	701.27	701.08	700.88	700.67	700.46	700.42	700.27	700.11	699.94	699.77	699.59	699.41	699.22	699.03	698.83	698.62	698.60	698.43	698.27	698.11	697.94	697.78	697.61
BEAM LINE L	701.95	701.78	701.60	701.41	701.23	701.03	700.83	700.62	700.41	700.38	700.22	700.06	699.89	699.72	699.54	699.35	699.16	698.97	698.76	698.56	698.53	698.37	698.20	698.04	697.87	697.70	697.54

MISCELLANEOUS DATA TABLE

	BEAM LINE	W. ABUT. BEARING								PIER #1 BEARINGS										PIER #2 BEARINGS						E. ABUT. BEARING		
		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24		25	26
ANTICIPATED DEFLECTION DUE TO SLAB (in.)	ALL	0	1/4	7/16	1/2	9/16	1/2	7/16	1/4	0	0	1/2	7/8	1 1/16	1 5/16	1 3/8	1 5/16	1 3/16	7/8	1/2	0	0	3/16	1/4	5/16	1/4	3/16	0
CROSS SLOPE ADJUSTMENTS	L, K, J, H, G																											
	I														+ 3/16 - 3/16													
ALLOWABLE FIELD HAUNCH	MAX.														2													
	MIN.														- 5/16													


NOTE 1:
TO CALCULATE FIELD HAUNCHES REQUIRED AT EACH LOCATION, SURVEY THE BEAM TOPS CONSISTENT WITH THE SPACINGS SHOWN ON THE "TOP OF SLAB ELEVATIONS LAYOUT" ON DESIGN SHEET 19. SUBTRACT THE SURVEYED BEAM SHOT FROM THE "BEAM LINE HAUNCH ELEVATION". THIS VALUE WILL BE THE HAUNCH NEEDED (SEE "FIELD HAUNCH" IN HAUNCH DETAIL). THE "BEAM LINE HAUNCH ELEVATION" INCLUDES ADJUSTMENTS FOR SLAB THICKNESSES AND ANTICIPATED DEFLECTIONS. NO ADDITIONAL CALCULATIONS ARE REQUIRED. IF THE FIELD HAUNCH EXCEEDS THE MAXIMUMS AND MINIMUMS INDICATED IN THE MISCELLANEOUS DATA TABLE, ADJUSTMENTS TO THE GRADE OR ADDITIONAL HAUNCH REINFORCEMENT WILL BE REQUIRED.

NOTE:
HAUNCH LOCATIONS ARE AT THE SAME LOCATION AS THE ENCIRCLED LETTERS AND NUMBERS SHOWN ON DESIGN SHEET 19.




NOTE:
BRIDGE SEAT ELEVATIONS ARE SET BASED ON THEORETICAL CAMBER AND BEAM DEFLECTIONS. THESE BRIDGE SEATS WILL PROVIDE A THEORETICAL BEAM HAUNCH WITHIN DESIGN PARAMETERS. ACTUAL HAUNCHES ARE DETERMINED USING SURVEYED TOP OF BEAM ELEVATIONS AND "BEAM LINE HAUNCH ELEVATION" DATA. ALLOWABLE MAXIMUM AND MINIMUM "FIELD HAUNCH" VALUES ARE GIVEN IN THE "MISCELLANEOUS DATA" TABLE. "CROSS SLOPE ADJUSTMENT" VALUES FROM THE "MISCELLANEOUS DATA" TABLE WILL AID THE CONTRACTOR IN DETERMINING ACTUAL FORMED HAUNCH DIMENSIONS AT THE EDGES OF THE TOP FLANGE.



DESIGN FOR 32° SKEW (L.A.)
**DUAL 223'-0 x 40'-0 PRETENSIONED
 PRESTRESSED CONCRETE BEAM BRIDGES**
 70'-9 & 60'-9 END SPANS 91'-6 INTERIOR SPAN
HAUNCH DATA DETAILS - EASTBOUND
 STA. 356+70.31 (± OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 21 OF 32 FILE NO. 29488 DESIGN NO. 1203




PART ELEVATION (LOOKING NORTH)




PINTLE DETAIL




FIXED PIER 2




LAMINATED NEOPRENE PADS



PLAN OF PINTLE PLATE




DETAIL C



SECTION B-B

(DIAPHRAGM CONCRETE NOT SHOWN)




PART PLAN


SECTION B-B

1" THICK STRIPS OF PREFORMED EXPANSION JOINT FILLER AROUND BEARINGS, FACE OF STEPS, SIDES AND ENDS OF KEYWAYS.

TOP OF PIER DETAILS
FIXED PIER NO. 2



PART SECTION A-A
SHOWING ORIENTATION OF PAD TAPER
(LOOKING NORTH)



SOLE PLATE LOCATIONS

EXPANSION PIER BEARING NOTES:

- SURFACES MARKED "V" SHALL BE FINISHED ANSI 250.
- PINTLE PLATES ARE A PART OF THE SUPERSTRUCTURE "STRUCTURAL STEEL QUANTITY".
- COSTS OF ANCHORED CURVED SOLE PLATES AND NEOPRENE PADS ARE TO BE INCLUDED IN THE PRICE BID FOR "PRETENSIONED PRESTRESSED CONCRETE BEAMS".
- THE SOLE PLATES AND PINTLE PLATES SHALL BE GALVANIZED. ALL WELDING SHALL BE COMPLETED PRIOR TO GALVANIZING. THE SURFACE OF THE PINTLE PLATE IN CONTACT WITH THE LAMINATED NEOPRENE PADS SHALL BE FREE OF PROJECTIONS DUE TO THE GALVANIZING.
- SOLE PLATES ARE TO BE SET IN FORMS WHEN BEAMS ARE CAST AND THE BOTTOM OF BEAMS FORMED OUT AS SHOWN TO EXCLUDE CONCRETE.
- SOLE PLATES SHALL COMPLY WITH ONE OF THE FOLLOWING :
 - ASTM A 852
 - ASTM A 514 GRADE B
 - ASTM A 709 GRADE TO W

EXPANSION PIER 1

DESIGN FOR 32° SKEW (L.A.)

DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES

70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN

PIER BEARING DETAILS


STA. 356+70.31 (E. OFF. RELOC. U.S. 34) MAY, 2006

JEFFERSON COUNTY


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION

DESIGN SHEET NO. 22 OF 32 FILE NO. 29488 DESIGN NO. 1203

REVISED 03-03 - 1" DRAIN HOLE ADDED TO PINTLE DETAIL. ENGLISHBEAMS.DGN 4541A - THIS SHEET ISSUED 5-23-91



SECTION SHOWING INTERMEDIATE DIAPHRAGM




SECTION A-A

INTERMEDIATE DIAPHRAGM BOLT LOCATIONS

LXD60	28'-2 1/2"	4'-7 1/2"	28'-2 1/2"
LXD70	33'-2 1/2"	4'-7 1/2"	33'-2 1/2"
LXD90	43'-2 1/2"	4'-7 1/2"	43'-2 1/2"

NOTES:
 ALL DIAPHRAGM MATERIALS, INCLUDING BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED.
 SHOP DRAWINGS OF THE STEEL DIAPHRAGMS SHOWING LAYOUT AND DETAILS OF THE DIAPHRAGMS SHALL BE SUBMITTED FOR APPROVAL.
 ALL COSTS FOR FURNISHING AND INSTALLING STEEL INTERMEDIATE DIAPHRAGMS SHALL BE INCLUDED IN THE PRICE BID FOR STRUCTURAL STEEL.
 THE 1 1/2" Ø HOLES FOR THE 3/4" Ø H.T.S. BOLTS SHALL BE CAST INTO THE WEB. DRILLING IS NOT ALLOWED.
 THE 3/4" Ø H.T.S. BOLTS THROUGH THE WEB SHALL HAVE A THREAD LENGTH OF 3" MIN. AND 4" MAX. AND SHALL MEET THE REQUIREMENTS OF ASTM A449.
 ALL BOLTS ARE TO BE TIGHTENED PRIOR TO PLACING BRIDGE FLOOR CONCRETE WITH THE FOLLOWING EXCEPTION: BOLTS IN DIAPHRAGMS LOCATED UNDER LONGITUDINAL BRIDGE FLOOR CONSTRUCTION JOINTS SHALL NOT BE TIGHTENED UNTIL STAGE TWO OF THE BRIDGE FLOOR HAS BEEN PLACED.



ABUTMENT PIER NO. 1 PIER NO. 2
 BEAM COIL TIE LOCATIONS

INTERMEDIATE DIAPHRAGM STRUCTURAL STEEL

ONE CONNECTION DETAIL "D"

2 - 3/4" Ø x LENGTH H.T.S. BOLTS WITH NUTS AND WASHERS				
WEB THICKNESS	LENGTH OF H.T.S. BOLTS	WEIGHT PER DETAIL "D"	NUMBER OF DETAIL "D"	
7"	10"	4.66 LB	30	140
1 - BACKING L 4 x 3/8 x 1'-3 1/4" = 6.5 LB				
1 - L 6 x 4 x 1/2 x 1'-3 1/4" = 20.6 LB				

ONE C15 x 33.9 DIAPHRAGM

BEAM SPACING	7'-4 1/8"
WEB THICKNESS	6'-6 3/8"
	UNIT WEIGHT (LB)
	221.5


DIAPHRAGM WEIGHTS

UNIT WEIGHT	NUMBER OF DIAPHRAGMS	
221.5 LB	15	3323


DIAPHRAGM CONNECTION BOLTS

8 - 3/4" Ø x 0'-2 1/2" H.T.S. BOLTS WITH NUTS AND WASHERS, PER UNIT DIAPHRAGM	NUMBER OF DIAPHRAGMS	
10.3 LB	15	155

WESTBOUND BRIDGE INTERMEDIATE DIAPHRAGM STRUCTURAL STEEL (TOTAL LB) =	4431
EASTBOUND BRIDGE INTERMEDIATE DIAPHRAGM STRUCTURAL STEEL (TOTAL LB) =	4431




DETAIL D



SECTION B-B

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
STEEL INTERMEDIATE DIAPHRAGM DETAILS
 STA. 356+70.31 (E. OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 23 OF 32 FILE NO. 29488 DESIGN NO. 1203

DESIGN 09-03 - MINOR WASHER SIZE CHANGED. CHANGE TO NOTES ABOUT BOLT REQUIREMENTS. SEAL END OF BEAM AT STUD ABUTMENTS. ENGLISH@BEANS.DGN 1036 - THIS SHEET ISSUED 9-8-88



LXD BEAM DATA																	
BEAM	SPAN LENGTH	L-E BEARING	OVERALL BEAM LENGTH (L)	STRAIGHT STRAND SIZE	NO. OF STRANDS (DEFLECTED)	TOTAL INITIAL PRESTRESS KIPS	HOLD DOWN FORCE-KIPS	CAMBER (in.)		DEFLECTION (in.)		PERMISSIBLE SPACING		WEIGHT (TONS)		CONCRETE (G.C.P.)	REINFORCING STEEL (LBS.)
								AT RELEASE	AFTER LOSSES	IMMEDIATE (ELASTIC) Δ _i	TIME (PLASTIC) Δ _p	HS20 LOADING	STEEL DIAPHR.	STEEL DIAPHR.	STEEL DIAPHR.		
LXD60	60'-0"	61'-0"	13'-0"	1/2"	19	570	—	0.20	0.34	0.24	0.06	7'-6"	20.3	10.0	623		
LXD70	70'-0"	71'-0"	14'-0"	1/2"	14	600	24.6	0.58	1.02	0.43	0.11	7'-6"	23.6	11.7	902		
LXD90	90'-0"	91'-0"	17'-0"	1/2"	20	867	27.7	1.24	2.17	1.16	0.29	7'-6"	30.4	15.0	1227		

THE TOP STRAIGHT STRANDS OF BEAMS LXD60 ARE TO BE CUT WITH 1'-0" PROJECTIONS AND SHOP BENT UP. THE TOP AND BOTTOM DEFLECTED STRANDS OF BEAMS LXD70 AND LXD90 ARE TO BE CUT WITH 1'-0" PROJECTIONS AND SHOP BENT UP OR DOWN AS SHOWN. THE REMAINING TOP STRANDS ARE TO BE CUT WITH 0'-5" PROJECTIONS. FOUR BOTTOM STRANDS ARE TO BE CUT WITH 1'-0" PROJECTIONS AND SHOP BENT AS SHOWN. THE REMAINING BOTTOM STRANDS SHALL BE CUT OFF REASONABLY FLUSH WITH THE CONCRETE.



- NOTES:**
- DEFLECTIONS AT MID-SPAN DUE TO WEIGHT OF SLAB AND DIAPHRAGM. THE DEFLECTIONS SHOWN ARE FOR A SLAB WEIGHT OF 760 #/FT. (8" SLAB AND 7'-6" BEAM SPACING) AND ONE CONCRETE DIAPHRAGM (3191 #) OR ONE STEEL DIAPHRAGM (285 #) AT 1/2 OF SPAN. FOR DIFFERENT SLAB AND DIAPHRAGM WEIGHTS, DEFLECTIONS WILL BE DIRECTLY PROPORTIONAL.
 - DEFLECTIONS DUE TO THE COMBINED EFFECT OF CREEP DUE TO WEIGHT OF SLAB AND SHRINKAGE OF SLAB.
 - TOTAL BEAM DEFLECTIONS AT 1/2 OF SPAN, Δ_T, DUE TO WEIGHT OF SLAB AND DIAPHRAGMS FOR DETAILING PURPOSE:
 - (A) Δ_T = Δ₁ + Δ₂ FOR SIMPLE SPAN.
 - (B) Δ_T = Δ₁ + 3/4 Δ₂ FOR END SPANS OF CONTINUOUS BRIDGE.
 - (C) Δ_T = Δ₁ + 1/2 Δ₂ FOR INTERIOR SPANS OF CONTINUOUS BRIDGE.
 - TOTAL INITIAL PRESTRESS FOR LXD60 AND LXD70 IS BASED ON 72,664% F's, AND FOR LXD90 ON 75% F's. F's = 270 ksi AND A_s = 0.153 sq. in.

LIFTING LOOP DETAIL

TWO LIFTING LOOPS

1'-3" 1'-6" 1'-2" 4'-3" 1'-8"

TWO 1/2" 270K STRANDS THREADED THROUGH EACH PIPE SLEEVE BENT AS SHOWN AFTER THREADING. ALTERNATE LIFTING DEVICES MAY BE SUBMITTED FOR APPROVAL.



SECTION A-A SHOWING PLACEMENT OF STIRRUPS NEAR END OF BEAM

DESIGN STRESSES:

DESIGN STRESSES FOR THE FOLLOWING MATERIALS ARE TO BE IN ACCORDANCE WITH A.A.S.H.T.O. STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, SERIES OF 1989:

- REINFORCING STEEL IN ACCORDANCE WITH SECTION 9, GRADE 60. CONCRETE IN ACCORDANCE WITH SECTION 9, f'_c = 5000 psi.
- PRESTRESSING STEEL IN ACCORDANCE WITH SECTION 9, f'_s = 270,000 psi.

- NOTES (CONTINUED):**
- Holes must be cast in the web to accommodate the steel diaphragm attachments as detailed on the steel diaphragm detail sheet.
 - If sole plate is required for bearing, sole plate is to be set in forms when beam is cast and formed out below to exclude concrete as detailed on the bearing sheet.
 - DESIGN FOR 32° SKEW (L.A.)


SPECIFICATIONS:

CONSTRUCTION: STANDARD SPECIFICATIONS OF THE IOWA DEPARTMENT OF TRANSPORTATION, CURRENT SERIES, WITH CURRENT APPLICABLE SPECIAL PROVISIONS AND SUPPLEMENTAL SPECIFICATIONS.

DESIGN: A.A.S.H.T.O., SERIES OF 1989, WITH MINOR MODIFICATIONS.

REINFORCING BAR LIST

BEAM	SPAN	BAR	SHAPE	LXD60		LXD70		LXD90	
				NO.	LENGTH	NO.	LENGTH	NO.	LENGTH
4a1	—	—	—	2	4'-0"	2	4'-0"	2	18'-0"
a2	—	—	—	—	—	5/4	24'-4"	5/4	30'-10"
a3	—	—	—	—	—	5/2	27'-0"	7/2	34'-0"
AA 4b1	—	—	—	51	10'-4"	57	10'-4"	74	10'-4"
5b2	—	—	—	8	8'-8"	10	8'-8"	12	8'-8"
5b3	—	—	—	8	4'-4"	12	4'-4"	20	4'-4"
3c	—	—	—	51	2'-1"	57	2'-1"	74	2'-1"
3d	—	—	—	51	5'-7"	57	5'-7"	74	5'-7"
3e	—	—	—	12	2'-3"	14	2'-3"	14	2'-3"



DESIGN FOR 32° SKEW (L.A.)

DUAL 223'-0 x 40'-0 PRESTRESSED CONCRETE BEAM BRIDGES

70'-9 & 60'-9 END SPANS 91'-6 INTERIOR SPAN

LXD BEAM DETAILS

STA. 356+70.31 (E. OFF. RELOC. U.S. 34) MAY, 2006



JEFFERSON COUNTY

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION

DESIGN SHEET NO. 24 OF 32 FILE NO. 29488 DESIGN NO. 1203


REVISED 05-04 - BARS 4b1 CHANGED TO EPOXY COATED. ENGLISH BEAMS-DON 4630 - THIS SHEET ISSUED 06-01-90

REVISED 05-04 - BARS 4b1 CHANGED TO EPOXY COATED. ENGLISH BEAMS.DGN 4632 - THIS SHEET ISSUED 06-01-90



TYPICAL "LXD" BEAM CROSS SECTION

AREA = 638.75 in.²
 Y_b = 24.37 in.
 I = 214,974 in.⁴





BEAM LXD60

* KEEP
 AA EPOXY COATED BARS

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
LXD60 BEAM DETAILS
 STA. 356+70.31 (E. OFF. RELOC. ILS.34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 25 OF 32 FILE NO. 29488 DESIGN NO. 1203

DESIGN TEAM	EDS/GJK/DLB	LXD BEAMS	STANDARD SHEET 4632	JEFFERSON COUNTY	PROJECT NUMBER NHSN-034-8(105)--2R-51	SHEET NUMBER 26
-------------	-------------	-----------	---------------------	------------------	---------------------------------------	-----------------

NOTE: DIMENSIONS FOR THE LOCATION OF THE DEFLECTED STRANDS ARE AT \bar{C} BEAM AND END OF BEAM.



BEAM LXD70

- DEFLECTED STRANDS
- * KEEP
- Δ DIMENSIONS AT END OF BEAM
- $\Delta\Delta$ EPOXY COATED BARS



DESIGN FOR 32° SKEW (L.A.)
**DUAL 223'-0" x 40'-0" PRETENSIONED
 PRESTRESSED CONCRETE BEAM BRIDGES**
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
LXD70 BEAM DETAILS
 STA. 356+70.31 (\bar{C} OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 26 OF 32 FILE NO. 29488 DESIGN NO. 1203

REVISED 05-04 - BARS 4b1 CHANGED TO EPOXY COATED.
 ENGLISH BEAMS.DGN 4633 - THIS SHEET ISSUED 06-01-90

DESIGN TEAM EDS/GJK/DLB	LXD BEAMS	STANDARD SHEET 4633	JEFFERSON COUNTY	PROJECT NUMBER NNSN-034-8(105)-2R-51	SHEET NUMBER 27
-------------------------	-----------	---------------------	------------------	--------------------------------------	-----------------


27-APR-2006 07:14 dbackou W:\Projects\51034030A\94\BRF\Ina\51034105_1203.brg 511203s026 \\NTPPRTSVR2\BrgTl.f

NOTE: DIMENSIONS FOR THE LOCATION OF THE DEFLECTED STRANDS ARE AT \bar{C} BEAM AND END OF BEAM.



TYPICAL "LXD" BEAM CROSS SECTION

AREA = 638.75 in.²
 $Y_b = 24.37$ in.
 $I = 214,974$ in.⁴



REVISED 05-04 - BARS 4a1 CHANGED TO EPOXY COATED, ENGLISH BEAMS.DGN 4634 - THIS SHEET ISSUED 06-01-90

- DEFLECTED STRANDS
- * KEEP
- △ DIMENSIONS AT END OF BEAM
- △△ EPOXY COATED BARS

DESIGN FOR 32° SKEW (L.A.)

**DUAL 223'-0" x 40'-0" PRETENSIONED
 PRESTRESSED CONCRETE BEAM BRIDGES**

70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN

LXD90 BEAM DETAILS


STA. 356+70.31 (C. OFF. RELOC. U.S. 34) MAY, 2006

JEFFERSON COUNTY


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION

DESIGN SHEET NO. 27 OF 32 FILE NO. 29488 DESIGN NO. 1203


DESIGN TEAM EDS/GJK/DLB	LXD BEAMS	STANDARD SHEET 4634	JEFFERSON COUNTY	PROJECT NUMBER NNSN-034-8(105)-2R-51	SHEET NUMBER 28
-------------------------	-----------	---------------------	------------------	--------------------------------------	-----------------



PART PLAN VIEW




PART VIEW E-E




PART ELEVATION VIEW


PROVIDE 5 HOLES FORMED WITH 1" PLASTIC CONDUIT. COST TO BE INCLUDED IN PRICE BID FOR CONCRETE BARRIER RAILING.




PART VIEW F-F




VIEW A-A



SECTION B-B



SECTION C-C



SECTION D-D

NOTE: CONSTRUCTION JOINT BETWEEN TOP OF WING AND BARRIER RAIL IS ROUGHENED CONCRETE.


NOTE: THE 10" RADIUS AND 1 1/2" RADIUS ARE TYPICAL AND SHALL BE USED WHEN CONSTRUCTING THE CORNERS FOR VIEW A-A, SECTION B-B, SECTION C-C AND SECTION D-D.

NOTE: THE 5c1, 6 - 5c2, 5c5-13, 2 - 5d2, 2 - 5d3 AND 4#1 BARS ARE TO BE PLACED WITH THE ABUTMENT WING FOOTING. THE DETAILS FOR PLACEMENT ARE SHOWN ON THE SUPERSTRUCTURE DETAIL SHEET.

NOTE: DASHED LINES BELOW THE TOP OF WING ARE THE ABUTMENT WING REINFORCING STEEL. SEE SUPERSTRUCTURE DETAIL SHEETS FOR PLACEMENT.


EPOXY REINFORCING STEEL - ONE END SECTION							
BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT		
5c1	VERTICAL, RAIL TO WING FOOTING	U	34	2'-10"	100		
5c2	VERTICAL AT NOSE, RAIL TO WING FOOTING	U	12	2'-9"	34		
5c3	VERTICAL	U	17	6'-1"	108		
5c5-13	VERTICAL	U	9	VARIABLES	35		
5d1	HORIZONTAL	—	7	6'-8"	49		
5d2	HORIZONTAL	—	9	6'-9"	63		
5d3	HORIZONTAL	—	3	3'-5"	11		
4#1	WING FOOTING TIE BARS	U	10	VARIABLES	13		
(INCLUDE WITH BARRIER RAIL REINFORCING)						TOTAL WEIGHT (LBS.)	413

CONCRETE PLACEMENT SUMMARY	
SECTION	TOTAL
BARRIER RAIL ONE END SECTION	0.62 CU. YD.




DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
END SECTION DETAILS - WEST & EAST BOUND
 STA. 356+70.31 (± OFF. RELOC. ILS.34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 28 OF 32 FILE NO. 29488 DESIGN NO. 1203

CORRECTIONS 06-03 - MINOR CHANGES TO NOTES. ENGLISH@KRALBRIDGES.DGN 1017 - THIS SHEET ISSUED 09-01




ELEVATION OF BARRIER RAIL LAYOUT



BARRIER RAIL JOINT DETAILS


NOTE: ALL DIMENSIONS ARE MEASURED ALONG GRADE.

NOTE: CONDUIT AND JUNCTION BOXES TO BE PLACED IN NORTH RAIL OF WESTBOUND BRIDGE AND PLACED IN SOUTH RAIL OF EASTBOUND BRIDGE.



PART SECTION C-C

* DENOTES THE MAXIMUM VALUE FOR THIS DIMENSION, THIS DIMENSION MAY VARY DUE TO CONSTRUCTION INACCURACIES.



PART SECTION F-F

BARRIER RAIL NOTES:
 MINIMUM CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR IS TO BE 2" UNLESS OTHERWISE NOTED OR SHOWN.
 THE PERMISSIBLE CONSTRUCTION JOINTS ARE TO BE PLACED BETWEEN VERTICAL BARS AT 4 MINIMUM SPACING OF 20 FEET. CONSTRUCTION JOINT CONTACT SURFACES ARE TO BE COATED WITH AN APPROVED BOND BREAKER. COST OF THE JOINT SEALER AND BOND BREAKER SHALL BE CONSIDERED INCIDENTAL TO OTHER CONSTRUCTION.
 ALL BARRIER RAIL REINFORCING STEEL IS TO BE EPOXY COATED.
 THE CONCRETE BARRIER RAIL IS TO BE BID ON A LINEAL FOOT BASIS. THE NUMBER OF LINEAL FEET OF BARRIER RAIL INSTALLED WILL BE PAID FOR AT THE CONTRACT PRICE PER LINEAL FOOT BASED ON PLAN QUANTITIES. PRICE BID FOR CONCRETE BARRIER RAILING SHALL BE FULL COMPENSATION FOR FURNISHING ALL MATERIAL, EXCLUDING REINFORCING STEEL, AND ALL OF THE EQUIPMENT AND LABOR REQUIRED TO ERECT THE RAIL IN ACCORDANCE WITH THESE PLANS AND CURRENT SPECIFICATIONS. IF CONDUIT IS REQUIRED IN THIS PLAN THE RIGID STEEL CONDUIT, JUNCTION BOXES AND FITTINGS INCLUDING LABOR AND ANY ADDITIONAL WORK TO DO THE INSTALLATION IS CONSIDERED INCIDENTAL TO THE COST OF THE RAILING.
 ALL BARRIER RAIL REINFORCING STEEL IS TO BE INCLUDED WITH THE SUPERSTRUCTURE REINFORCING STEEL.
 THE JOINT SEALER SHALL BE LIGHT GRAY NONSAG LATEX CAULKING SEALER MARKETED FOR OUTDOOR USE. NO TESTING OR CERTIFICATION IS REQUIRED.
 TOP OF THE BARRIER RAIL IS TO BE PARALLEL TO THE THEORETICAL \bar{x} GRADE.
 CROSS SECTIONAL AREA OF THE STANDARD SECTION OF THE BARRIER RAIL = 2.84 SQUARE FEET.

REINFORCING BAR LIST - F-SHAPE BARRIER RAIL
 (ONE BRIDGE WITH WING EXTENSIONS - TWO RAILS)


SECTION	BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
STD. SECT.	5c1	VERTICAL	A	472	5'-11"	2,913
	5c2	VERTICAL	B	452	6'-0"	2,829
	5c3	VERTICAL	C	20	2'-10"	89
	5c14	VERTICAL	D	20	3'-10"	80
EPOXY COATED	5d1	LONGITUDINAL	E	126	35'-7"	4,676
	BARRIER RAIL END SECTIONS 4 @ 413					1,652
(INCLUDE WITH SUPERSTRUCTURE REINFORCING) TOTAL (LB)						12,209

CONCRETE PLACEMENT SUMMARY
 (ONE BRIDGE WITH WING EXTENSIONS - TWO RAILS)

SECTION	TOTAL
STANDARD SECTION 472 FT. AT 0.1052 C.Y. PER FT.	49.7
BARRIER RAIL END SECTIONS 4 AT 0.62 C.Y.	2.5
TOTAL C.Y.	52.2

CONCRETE BARRIER RAIL QUANTITIES


ITEM	UNIT	QUANTITY
CONCRETE BARRIER RAILING	L.F.	500



ALL DIMENSIONS ARE OUT TO OUT, D = PIN DIAMETER.


DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
BARRIER RAIL DETAILS
 STA. 356+70.31 (E. OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 29 OF 32 FILE NO. 29488 DESIGN NO. 1203

REVISION 09-03 - JUNCTION BOX DETAILS CHANGED. ANCHOR BOLTS TO BE GALVANIZED. CONDUIT USED FOR LIGHT POLE CHANGED FROM 1" TO 2". ANCHOR PLATE CHANGED TO 3" SLOT.
 HE1030A1S01 KHST1030A1S01-LEP; THIS SHEET REDRAWN, DEVICED:ZHAOR200,0041ARCH,TAPE NO. 15 DATE 9-8-88)



BOSS FOR	HOLE	FOR CONDUIT SIZE
5 THREADS	C	2" RIGID STEEL
NONE	E	1/2" COPPER PIPE


NOTE:
THE GROUNDING BUTTONS ARE TO BE BLIND DRILLED AND TAPPED FOR 3/8" x 0'-0 1/2" BOLTS.




RM-37, TYPE I JUNCTION BOX
 WATERTIGHT, CAST IRON - FLUSH MOUNT
 (SEE STANDARD ROAD PLAN RM-37 FOR ADDITIONAL DETAILS)

LIGHTING NOTES:
 SEE RM-37 STANDARD ROAD PLAN FOR ADDITIONAL INFORMATION ON JUNCTION BOXES.
 CONSTRUCTION SHALL CONFORM TO THE CURRENT IOWA D.O.T. STANDARD AND SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS.
 CONDUIT INSTALLATION SHALL COMPLY WITH THE ARTICLE "ELECTRICAL DUCTS", SECTION 2523.
 ALL 1" ENTRANCE HOLES IN JUNCTION BOXES SHALL BE DRILLED AND TAPPED FOR THE SPECIFIED CONDUIT SIZE. ALL OTHER HOLES SHALL HAVE A CONCRETE - TIGHT SLIP FIT. CONDUIT ENDS SHALL NOT PROTRUDE INTO JUNCTION BOX MORE THAN 1/4". DRAIN PIPE END SHALL BE FLUSH WITH INSIDE SURFACE OF BOX. GROUNDING BUTTONS SHALL BE LOCATED APPROXIMATELY 3" FROM THE INSIDE SURFACE OF THE BOX WALL, AND NOT CLOSER THAN 3" TO THE EDGE OF ANY HOLE IN THE BOX FLOOR. HOLES FOR DRAIN PIPE SHALL BE PLACED IN THE LOW CORNER OF THE BOX, WITH A MINIMUM CLEARANCE OF 1" BETWEEN THE EDGE OF THE HOLE AND THE INSIDE SURFACE OF THE BOX WALL. TYPICAL DETAILS ARE SHOWN ON THIS SHEET.
 THE RIGID STEEL CONDUIT, JUNCTION BOXES AND FITTINGS INCLUDING LABOR AND ANY ADDITIONAL WORK TO DO THE INSTALLATION IS CONSIDERED INCIDENTAL TO THE COST OF THE RAILING.


CONDUIT LENGTH	
2" RIGID STEEL CONDUIT - WESTBOUND BRIDGE	248.0 LIN. FT.
2" RIGID STEEL CONDUIT - EASTBOUND BRIDGE	248.0 LIN. FT.



WESTBOUND EXTERIOR ELEVATION - NORTH BARRIER RAIL - LOOKING SOUTH
 EASTBOUND EXTERIOR ELEVATION - SOUTH BARRIER RAIL - LOOKING NORTH




NOTE:
 CONDUIT AND JUNCTION BOXES TO BE PLACED IN NORTH RAIL OF WESTBOUND BRIDGE AND PLACED IN SOUTH RAIL OF EASTBOUND BRIDGE.




PART PLAN

DESIGN FOR 32° SKEW (L.A.)
DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
LIGHTING DETAILS
 STA. 356+70.31 (E. OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 30 OF 32 FILE NO. 29488 DESIGN NO. 1203

BENCH MARK: 20 - 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE
ROAD EAST OF CP#89, STA. 339+36.52, 145.93 LT. ELEV. 732.415.



SECTION A-A
NOTE: SPECIAL BACKFILL MAY BE SUBSTITUTED FOR GRANULAR BACKFILL.
GRANULAR BACKFILL DETAILS




PART SITUATION PLAN
SHOWING SUBDRAIN LOCATION.

SUBDRAIN NOTES:

THIS PLAN SHEET SHOWS DETAILS FOR PLACING ALL SUBDRAINS AND SUBDRAIN OUTLETS REQUIRED FOR THIS STRUCTURE.
THE SUBDRAINS SHALL BE 4" IN DIAMETER AND MEET THE REQUIREMENTS OF SECTION 4143.01 B OF THE CURRENT I.D.O.T. STANDARD SPECIFICATION. THE SUBDRAIN OUTLET SHALL CONSIST OF A 6'-0" LENGTH OF PIPE WITH A REMOVABLE RODENT GUARD AS DETAILED ON THIS SHEET.
THE COST OF FURNISHING AND PLACING SUBDRAIN (INCLUDING EXCAVATION), GRANULAR BACKFILL, POROUS BACKFILL, AND SUBDRAIN OUTLET IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)". NO EXTRA PAYMENT WILL BE MADE.
THE DIMENSIONS SHOWN FOR THE PROPOSED SUBDRAINS ARE BASED ON THE PROPOSED GRADING LAYOUT OF BRIDGE BERMS. THE DIMENSIONS SHOWN ARE FOR ESTIMATING ONLY. REQUIRED LENGTHS AND GENERAL LOCATIONS OF SUBDRAINS ARE SUBJECT TO CHANGE DUE TO FIELD ADJUSTMENTS OF THE GRADING LAYOUT.

SUBDRAIN OUTLET ELEVATIONS

LOCATION		ELEVATION
WESTBOUND BRIDGE	WEST ABUTMENT	691.75
	EAST ABUTMENT	688.10
EASTBOUND BRIDGE	WEST ABUTMENT	693.18
	EAST ABUTMENT	688.94



TYPICAL SECTION OF SUBDRAIN OUTLET
REMOVABLE RODENT GUARD DETAILS
OUTLET DETAILS

DESIGN FOR 32° SKEW (L.A.)
**DUAL 223'-0" x 40'-0" PRETENSIONED
PRESTRESSED CONCRETE BEAM BRIDGES**
70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
SUBDRAIN DETAILS
STA. 356+70.31 (E. OFF. RELOC. U.S. 34) MAY, 2006
JEFFERSON COUNTY
IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. 31 OF 32 FILE NO. 29488 DESIGN NO. 1203

ENGLISHFORSI.OPEPROTECTONBRIDGES.DGN 1007C - THIS SHEET ISSUED 06-02 FOR WATER CROSSINGS.

GENERAL NOTES:

MACADAM STONE SHALL BE PLACED ALONG THE SIDE OF THE WING AND ABUTMENT FOOTING AS SHOWN IN DETAIL "A". THIS IS TYPICAL AT EACH CORNER OF THE BRIDGE UNLESS OTHERWISE NOTED IN THE PLANS. THE MACADAM STONE AT THESE LOCATIONS SHALL BE UNDERLAYED WITH ENGINEERING FABRIC MEETING THE REQUIREMENTS OF 4196.01C.


THE MACADAM STONE SHALL MEET THE REQUIREMENTS OF 4122.02, COARSE MATERIAL (NO CHOKER STONE IS ALLOWED).

WOOD PRESERVATIVE TREATMENT FOR THE TIMBER EDGING SHALL MEET THE REQUIREMENTS FOR GUARDRAIL POSTS, SAWED FOUR SIDES, AS SPECIFIED IN 4161.



THE MACADAM STONE SHALL BE DEPOSITED, SPREAD, CONSOLIDATED AND SHAPED BY MECHANICAL OR HAND METHODS THAT WILL PROVIDE UNIFORM 6" DEPTH AND DENSITY AND PROVIDE UNIFORM SURFACE APPEARANCE.

PAYMENT FOR THE BRIDGE WING ARMORING AND MACADAM STONE SPLASH BASINS, SHALL BE INCIDENTAL TO THE BID ITEM "STRUCTURAL CONCRETE (BRIDGE)" AND SHALL INCLUDE COSTS OF ALL MATERIAL AND LABOR TO CONSTRUCT THE WING ARMORING AND SPLASH BASINS AS SHOWN ON THESE PLANS.




MACADAM STONE SPLASH BASINS AS DETAILED ON THIS SHEET SHALL BE PLACED UNDER EACH DECK DRAIN. THE MACADAM STONE AT THESE LOCATIONS SHALL BE UNDERLAYED WITH ENGINEERING FABRIC MEETING THE REQUIREMENTS OF 4196.01C.



TOP VIEW OF WING ARMORING WITH WING EXTENSION



PROFILE VIEW OF WING ARMORING WITH WING EXTENSION



SECTION A-A

DESIGN FOR 32° SKEW (L.A.)
**DUAL 223'-0" x 40'-0" PRETENSIONED
 PRESTRESSED CONCRETE BEAM BRIDGES**
 70'-9" & 60'-9" END SPANS 91'-6" INTERIOR SPAN
BRIDGE WING ARMORING & SPLASH BASINS - WEST & EAST
 STA. 356+70.31 (± OFF. REL. 00, U.S. 34) MAY, 2006
JEFFERSON COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 32 OF 32 FILE NO. 29488 DESIGN NO. 1203


REVISED: 09-03 - DETAIL "A" CHANGED TO SECTION A-A, ENGLISH FOR PROTECTION BRIDGES, IGIN 1005A - THIS SHEET ISSUED 06-02.

CUT MOISTURE
CUT DENSITY (pcf)
PLASTIC LIMIT


21,
104,

BENCH MARK: 20' x 1" x 60" IRON PIPE NORTH OF LIBERTYVILLE
ROAD EAST OF CP#09, STA. 339+09.97, 460.814 LT. ELEV. 732.415

THIS SHEET IS INCLUDED TO SHOW
SOIL INFORMATION
DETAILS AND NOTES SHOWN ELSEWHERE
IN THESE PLANS SHALL BE USED FOR
STRUCTURE CONSTRUCTION.




705.38	Previous Grading Contract included design and installation of Intermediate Foundation Improvement (IFI) system of east abutment. After installation of IFI system of east abutment, Grading Contractor to have installed 2 feet of granular blanket over IFI system. Grading contractor also to have placed 2 feet of surcharge (overload) fill over the subgrade at the top of the embankment. Approximate outline of IFI system is shown on the plan and profile of this sheet and surcharge fill is shown on the plan view of this sheet. Design criteria for the IFI system to have included less than 0.4 inches of remaining settlement after a delay of 60 days after fill placement. Settlement magnitude and rate to be evaluated and verified by a geotechnical engineer/IFI system designer using field data from Settlement Plates installed at the indicated locations by the Grading Contractor, prior to installing abutment piles.
695.54	Previous Grading Contract included installation of Curerout and replacement procedure at the west abutment. Approximate outline of the core-out and replacement is shown on this sheet.
685.70	Intermediate Foundation Improvement system was installed at East Abutment as part of previous Grading Contract. NMSX-34-8(94)-3H-5I Core-out and replacement procedure was performed at West Abutment as part of the previous Grading Contract NMSX-34-8(94)-3H-5I. See sheets 0.08, 0.09, 0.10 and 0.11 of the Grading Contract, included as SPS sheets for this bridge, and which are included for informational purposes only, for additional information.
675.85	NMSX-34-8(94)-3H-5I Q.08 on SPS.03 NMSX-34-8(94)-3H-5I Q.09 on SPS.04 NMSX-34-8(94)-3H-5I Q.10 on SPS.05 NMSX-34-8(94)-3H-5I Q.11 on SPS.06
666.01	LOCATION JEFFERSON COUNTY 1+71 N. R. 10W SECTION 2/3 LIBERTY TWP. U.S. HWY OVER UNNAMED CREEK
656.17	SHELBY TUBE CORE DATA
646.33	BORING NO. B-690 B-690 DEPTH IN FEET 11 16 CLASSIFICATION (AASHTO) -- -- COEFF. CONSOL. sq.ft./DAY -- -- TRIAXIAL COMPRESSION UC UC COHESION - psf 1100 2820 FRICTION COEFF. -- -- MOISTURE CONTENT % 18 19 DENSITY - pcf 104 110 UC-UNCONFINED COMPRESSION (c=1/2 Qu)
636.48	GEOTECHNICAL DESIGN
626.64	I hereby certify that this plan was prepared under my supervision and that engineering decisions with regard to the design were made by me or by other duly licensed Professional engineers under the laws of the State of Iowa. <i>Michael D. Ringle</i> Aug. 22, 2005 MICHAEL D. RINGLER Printed or Typed Name My license renewal date is December 31, 2008 Pages or sheets covered by this seal: SPS.01 -- SPS.06
616.80	DESIGN FOR 32° SKEW (L.A.) DUAL 223'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE INTEGRAL ABUTMENTS TEE PIERS 70'-9", 60'-9" END SPANS 91'-6" CENTER SPAN SOILS PROFILE SHEET STA. 356+75.30 JEFFERSON COUNTY IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION DESIGN SHEET NO. 1 of 6 FILE NO. 29488 DESIGN NO. 1203
606.96	
597.11	



CUT MOISTURE
CUT DENSITY (pcf)
PLASTIC LIMIT

BENCH MARK: 20 - 1' x 60" IRON PIPE NORTH OF LIBERTYVILLE
ROAD EAST OF CP#89, STA 333+09.097, 460.814 LT ELEV 732.415



THIS SHEET IS INCLUDED TO SHOW SOIL INFORMATION. DETAILS AND NOTES SHOWN ELSEWHERE IN THESE PLANS SHALL BE USED FOR STRUCTURE CONSTRUCTION.

Previous Grading Contract included design and installation of Intermediate Foundation Improvement (IFI) system at east abutment, after installation of IFI system at west abutment. Grading Contractor to have installed 2 feet of granular blanket over IFI system. Grading contractor also to have placed 2 feet of surcharge (overload fill) over the subgrade of the top of the embankment. Approximate outline of IFI system is shown on the plan and profile of this sheet and surcharge fill is shown on the plan view of this sheet. Design criteria for the IFI system to have included less than 0.4 inches of remaining settlement after a delay of 60 days after fill placement. Settlement magnitude and rate to be evaluated and verified by a geotechnical engineer/IFI system designer using field data from Settlement Plates installed at the indicated locations by the Grading Contractor, prior to installing abutment piles.

Previous Grading Contract included installation of Core-out and replacement procedure of the core-out and replacement is shown on this sheet.

Intermediate Foundation Improvement system was installed at East abutment as part of previous Grading Contract. NMSX-34-8(94)-3H-51 Core-out and replacement procedure was performed at West Abutment as part of the previous Grading Contract NMSX-34-8(94)-3H-51. See sheets 0.08, 0.09, 0.10 and 0.11 of the Grading Contract/IFI system as SPS sheets for this bridge, and which are included for informational purposes only, for additional information.

NMSX-34-8(94)-3H-51 0.08 on SPS 03
NMSX-34-8(94)-3H-51 0.09 on SPS 04
NMSX-34-8(94)-3H-51 0.10 on SPS 05
NMSX-34-8(94)-3H-51 0.11 on SPS 06

Settlement Plate Detail
See Standard RL-6
Station 357+45, RT 69 feet
Station 358+60, LT 69 feet
Station 358+27, LT 69 feet
Station 350+07, LT 69 feet

NOTES:
ALL DIMENSIONS IN FEET UNLESS NOTED OTHERWISE
THIS PLAN NOT TO SCALE
ALL STATIONS AND ELEVATIONS SHOWN ON THIS PLAN ARE IN FEET.


CORE DEPTH (ft)	27.0-28.0	28.0-31.0	31.0-35.0	35.0-37.0
RECOVERY %	67	78	80	50
ROD %	35	66	60	50
DRY DENSITY pcf		13	6250	6800
MOISTURE CONTENT %				
COHESION psf				
UNCONFINED COMPRESSION DEPTH(ft)				

SHELBY TUBE CORE DATA


BORING NO.	B-694	B-694
DEPTH IN FEET	11	16
CLASSIFICATION [AASHTO]	A-6(15)	A-7-6(19)
COEFF. CONSOL. sq.ft./DAY	0.75	--
TRIAXIAL COMPRESSION	--	UU
COHESION - psf	--	1730
FRICTION COEFF.	--	--
MOISTURE CONTENT %	21	18
DENSITY - pcf	103	110
UU-UNCONSOLIDATED & UNDRAINED	--	--
UC-UNCONFINED COMPRESSION (e=1/2 Ou)	--	--


LOCATION
JEFFERSON COUNTY
T-71 N, R-10W
SECTION 2/3
LIBERTY TWP.
U.S. HWY. OVER UNNAMED CREEK

DESIGN FOR 32° SKEW (L.A.)
DUAL 23'-0" x 40'-0" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE
INTEGRAL ABUTMENTS TEE PIERS
70'-9" END SPANS 91'-6" CENTER SPAN
SOILS PROFILE SHEET
STA. 356+75.30
JEFFERSON COUNTY
IGWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. 2 OF 6 FILE NO. 29488 DESIGN NO. 1203




SHUCK-BRITSON 2401 GRAND AVENUE S.B.I. NO. 18797L Terracon
JEFFERSON COUNTY PROJECT NUMBER NMSX-034-8(105)-3H-51 SHEET NUMBER SPS 02





DESIGN TEAM **SNYDER & ASSOCIATES, INC.** METRIC IOWA DOT • OFFICE OF DESIGN **JEFFERSON** COUNTY PROJECT NUMBER SHEET NUMBER **SPS.04**



This sheet is included in the Unnamed Creek bridge plans for informational purposes only. This plan provides the bridge contractor with information concerning previous grading operations at both bridge abutments.

NHSX-34-8(94)-3H-51
 GRADING SHEET Q.08 on SPS.03
 GRADING SHEET Q.09 on SPS.04
 GRADING SHEET Q.10 on SPS.05
 GRADING SHEET Q.11 on SPS.06


FOR PLAN VIEW
 REFER TO SHEET Q.08.
 FOR EASTBOUND PROFILE,
 REFER TO SHEET Q.09.

SHELBY TUBE CORE DATA				
BORING NO.	B-322	B-324	B-324	B-324
DEPTH IN METERS	1.2	2.4	4.0	5.5
CLASSIFICATION (AASHTO)	--	A-4(0)	A-6(4)	--
COEFF. CONSOL. m ² /DAY	--	0.03	--	--
TRIAxIAL COMPRESSION	UC	--	Cu	UC
COHESION - KPa	256	--	10	152
FRICTION COEFF.	--	--	0.17	--
MOISTURE CONTENT %	14	21	20	15
DENSITY - kg/m ³	1870	1670	1750	1730
UU-UNCONSOLIDATED & UNDRAINED CU-CONSOLIDATED & UNDRAINED UC-UNCONFINED COMPRESSION (C=1/2 Qu)				

Core-out and granular replacement required at West Abutment of WB bridge. See Sheet Q.11 and Cross-sections for additional information.

Surcharge (Overload) required at East Abutment of WB bridge. See Sheet Q.11 and Cross-sections for additional information.

- DEFS CORE
- BLOW
- PLUGGED
- SELECT SOIL
- SELECT SAND
- SHALE
- WATER
- GRAVEL
- SILTSTONE
- SHALE
- CLAYEY SOIL
- MUCK



Core out and granular replacement required at west abutment of both WB and EB bridges. Base of core-out to be sized according to the limits (Station and Offset) shown on this sheet, and will extend 1 meter into shale. Granular Material (Gradation 4133) to be used to backfill excavation to elevation 206.5 meters. Above the granular material, backfill in the core-out to consist of Class-10 embankment fill. West edge of excavation to be sloped at a 4H:1V or flatter. Remaining sides of excavation to be sloped as needed for safety and construction purposes. Fill to be benched into slopes, as described in Section 2107.03, Standard Specification series of 2001.

This sheet is included in the Unnamed Creek bridge plans for informational purposes only. This plan provides the bridge contractor with information concerning previous grading operations at both bridge abutments.


NHSX-34-8(94)-3H-51
 GRADING SHEET Q.08 on SPS.03
 GRADING SHEET Q.09 on SPS.04
 GRADING SHEET Q.10 on SPS.05
 GRADING SHEET Q.11 on SPS.06

Grading Contract to include design and installation of Intermediate Foundation Improvement (IFI) System (by Special Provision) below embankment of East Abutments of new Bridges to carry Highway 34 over Unnamed Creek, and under North foreslope of approach embankment West of Station 109+65. Minimum design criteria for the abutment foreslope (parallel to Highway 34 centerline) and under approach berm slope after installation of the IFI System are as follows:

- * Global Stability - short-term safety factor: minimum 1.3
- * Total settlement at and within 6 meters of the bridge abutments shall be less than 125 mm
- * Total settlement shall be essentially complete (less than 0.01 meters remaining) at 60 days following embankment fill placement.
- * In the transition away from the improved zone, differential settlement shall not exceed 0.1 meters in 10 meters.
- * Each individual intermediate foundation element shall penetrate a minimum of 0.6 m into the foundation soil (shale).

After installation of Intermediate Foundation Improvement system, Grading Contractor to install Granular Blanket (Gradation 4133) over the entire footprint of the Intermediate Foundation Improvement system footprint, as shown on Sheets Q.08, Q.09, Q.10, Q.11 and the cross-sections. Granular Blanket to be 0.6 meters thick and drained by three (3) R-19A, Type 2 subdrains. Subdrains to be placed at offsets of 25 m Left, 25 m Right, and Centerline. Each subdrain will outlet through the berm via an R-19F, Type B, Pressure Release Outlet.


Approximate outlines of Intermediate Foundation Improvement system and Granular Blanket are shown in plan view on this sheet. Approximate Granular Blanket and IFI system extent and depth are shown in profile view on sheets Q.09 and Q.10 and the cross-sections.



CONTRACTOR TO PLACE EMBANKMENT FILL TO TOP OF SUBGRADE. AFTER A TIME DELAY OF 30 DAYS, SURCHARGE (OVERLOAD) TO BE PLACED AT EAST BRIDGE ABUTMENTS. TOP OF SURCHARGE (OVERLOAD) FILL AT ELEVATION 212.7 METERS. SURCHARGE (OVERLOAD) FILL TO CONSIST OF SELECT COHESIVE MATERIAL. SEE SHEETS Q.09, Q.10, Q.11 AND CROSS SECTIONS FOR ADDITIONAL INFORMATION.

SURCHARGE (OVERLOAD) COORDINATES

POINT	EASTBOUND LANE		WESTBOUND LANE	
	STATION	OFFSET	STATION	OFFSET
A	109+20	LT 20.6m	109+02	RT 8.6m
B	109+50	LT 20.6m	109+32	RT 8.6m
C	109+42	LT 8.6m	109+24	RT 20.6m
D	109+12	LT 8.6m	108+94	RT 20.6m




Settlement Plate Detail
 See Standard RL-6
 Station 108+95, RT 21 meters
 Station 109+30, RT 21 meters
 Station 109+20, LT 21 meters
 Station 109+75, LT 21 meters

FOR EASTBOUND PROFILE, REFER TO SHEET Q.09

FOR WESTBOUND PROFILE, REFER TO SHEET Q.10

Legend for symbols and materials:

- LAND LINE
- BELOW
- ENLARGED
- SELECT SOIL
- SELECT SHALE
- SHALE
- WATER
- HISTORIC
- UNSATURATED
- SANDY SOIL
- ROCK




5104
10-21-03

**TYPICAL CROSS SECTION
GRADING FOR DELAYED PAVING PROJECTS
4-LANE DIVIDED ROADWAY**

- Notes:
- ① Refer to Detail Project Plan and Cross Sections for specific locations of foreslope changes.
 - ② Median Ditch is measured from Profile Grade at the centerline of construction. Design depth of median ditch.

Location		A	B	MW	Z	M	BW	Slope
Road Identification	Station to Station	Feet	Feet	Feet	Inches	Feet	Feet	FS
U.S. 34	87+00.000 (M) 111+75.000 (M)	32.15	27.89	68.24	16.5	3.93	15.42	3

FOR INFORMATION ONLY




3220
PROOFED

- Notes:
- Normal section shown may be modified appropriately in areas of super-elevated curves or other locations specifically designated by the Engineer.
 - ① Mainline pavement type and thickness set to be determined. Bridge approach pavement shall be 12"OC.
 - ② Shoulders shall be constructed by others.

**TYPICAL CROSS SECTION
4-LANE DIVIDED ROADWAY
PRELIMINARY**

LOCATION		MW	M	J	E	SHOULDER TYPE
ROAD IDENTIFICATION	STATION TO STATION	Feet	Feet	Feet	Feet	
U.S. 34	354+44.48 358+96.12	68.24	3.93	6	8	GRANULAR

Design No: 1203
File No: 29488



I hereby certify that this Engineer's Document was prepared by me or under my direct personal supervision and that I am a duly Licensed Professional Engineer under the Laws of the State of Iowa.

Richard M. Voelker, P.E. Date: *11/21/06*

License Number: 13853
My License Renewal Date is December 31, 2006

Pages or sheets covered by this seal:
B.01, C.01-C.03, D.01-D.02

ESTIMATED ROADWAY QUANTITIES

100-0A
10-28-97

Item No.	Item Code	Item	Unit	Total	As Bult Quan.
1	2122-5190501	PAVED SHOULDER, PCC (PAVED SHOULDER FOR BRIDGE END DRAIN)	SY	31.11	
2	2301-0690200	BRIDGE APPROACH, RK-20	SY	1,155.47	
3	2499-0695040	BRIDGE END DRAIN, RF-40	EACH	4.00	
4	2519-3300139	FIELD FENCE, TYPE 39	STA	9.12	
5	2602-0000020	SILT FENCE	LF	200.00	
6	2602-0000060	REMOVAL OF SILT FENCE	LF	1,240.00	
7	2602-0000090	CLEAN OUT OF SILT FENCE	LF	1,240.00	

ESTIMATE REFERENCE INFORMATION

100-4A
10-29-02

Item No.	Item Code	Description
1	2122-5190501	PAVED SHOULDER, PCC (PAVED SHOULDER FOR BRIDGE END DRAIN) Refer to Tab 104-8A, Sheet C.02, for locations.
2	2301-0690200	BRIDGE APPROACH, RK-20 Refer to Tab. 112-6, Sheet C.02, for further information.
4	2519-3300139	FIELD FENCE, TYPE 39 Refer to Tab. 1077-7A, Sheet C.02, for locations
5	2602-0000020	SILT FENCE Silt Fence was installed at bridge abutments during the grading project, and should be in place at the beginning of the bridge project. Item is for replacements as necessary.

STANDARD ROAD PLANS

105-4
12-03-96

The following Standard Road Plans shall be considered applicable to construction work on this project.

NUMBER	DATE	NUMBER	DATE	NUMBER	DATE
RC-8A	4-15-03	RH-50	4-18-06	RK-20(2)	4-18-06
RC-8B(1)	4-18-06	RH-51	4-20-04	RK-20(3)	10-18-05
RC-8B(2)	4-18-06	RH-52	10-18-05	RK-21	10-18-05
RC-9B	4-15-03	RH-55(1)	4-20-04	RK-30	10-18-05
RC-17	4-18-06	RH-55(2)	4-18-06	RL-17	4-19-05
RF-19E	4-18-06	RK-20(1)	10-18-05	RM-37	4-27-99
RF-40	4-19-05			RP-2	10-3-00

01-20-84 203-1
Plan and profile sheets included in the project are for the purpose of alignment, location and specific directions for the work to be performed under this contract. Irrelevant data on these sheets is not to be considered a part of this contract.

04-00-01 203-2
During construction of this project, the contractor will be required to coordinate his operations with those of other contractors working within the same area. Other work in progress during the same period of the time will include construction of the following projects:

Project	Type of Work
NHSX-34-8(94)--3H-51	GRADING

TRAFFIC CONTROL PLAN

108-23
04-04-89

- U.S. 34 will be closed to traffic during construction.
- Traffic control devices have been installed by the grading contractor and shall remain in place through bridge construction. The bridge contractor shall be responsible for maintaining U.S. 34 closures during bridge construction. The cost of maintaining the traffic control shall be considered incidental to the project and no extra compensation will be allowed.
- Traffic control on this project will be in accordance with the RS series of Standard Road Plans as referenced. For additional complimentary information, refer to the Manual on Uniform Traffic Control Devices and current Standard and Supplementary Specifications.
- The location for storage of equipment by the Contractor during non-working hours shall be as approved by the engineer in charge of construction.
- Proposed changes in the traffic control plan shall be reviewed with the Office of Construction before changes are made.

10-29-02 213-1
It shall be the contractor's responsibility to provide waste areas or disposal sites for excess material (excavated material or broken concrete) which is not desirable to be incorporated into the work involved on this project. These areas shall not impact wetlands or "Waters Of The U.S." No payment for overhaul will be allowed for material hauled to these sites. No material shall be placed within the right-of-way, unless specifically stated in the plans.

01-20-84 204-2
All holes resulting from operations of the contractor, including removal of guardrail posts, fence posts, utility poles, or foundation studies, shall be filled and consolidated to finished grade as directed by the engineer to prevent future settlement. The voids shall be filled as soon as practical - preferably the day created and not later than the following day. Any portion of the right-of-way or project limits (including borrow areas and operation sites) disturbed by any such operations shall be restored to an acceptable condition. This operation shall be considered incidental to other bid items in project.

01-20-84 212-1
Sounding and test boring data shown on plans were accumulated for designing and estimating purposes. Their appearance on the plan does not constitute a guarantee that conditions other than those indicated will not be encountered.

01-20-84 232-5
The contractor shall not disturb desirable grass areas and desirable trees outside the construction limits. The contractor will not be permitted to park or service vehicles and equipment or use these areas for storage of materials. Storage, parking and service areas) will be subject to the approval of the resident engineer.

Design No: 1203
File No: 29488

SNYDER & ASSOCIATES

STATE OF IOWA

FISCAL YEAR

JEFFERSON

COUNTY

PROJECT NUMBER

NHSN-34-8(105)--2R-51

SHEET NUMBER

C.01

ALIGNMENT COORDINATES

NOTE: ALL INFORMATION IN THIS TABULATION IS IN METRIC UNITS

101-16
10-29-02

Name	Location	Station	Begin Spiral		Station	Begin Curve		Simple Curve PI or Master PI of SCS			End Curve			End Spiral		
			Coordinates			Coordinates		Coordinates			Coordinates			Coordinates		
			Y (Northing)	X (Easting)		Y (Northing)	X (Easting)	Station	Y (Northing)	X (Easting)	Station	Y (Northing)	X (Easting)	Station	Y (Northing)	X (Easting)
OR8-5	BYPASS CENTERLINE	94+88.588	110348.020	625995.038	95+64.588	110291.520	626045.854	98+94.016	110041.721	626260.656	101+65.024	110079.231	626587.968	103+42.024	110086.200	626663.638
OR8-6	BYPASS CENTERLINE				137+45.439	110473.730	630174.718	139+18.784	110492.747	630347.016	140+92.120	110508.775	630519.618			

SPIRAL/CIRCULAR CURVE DATA

NOTE: ALL INFORMATION IN THIS TABULATION IS IN METRIC UNITS

101-17
10-29-02

Name	Location	Δ	D	R	T	L	E	Θs	L.T.	S.T.	Ls	Ts	Es	Xc	Yc
OR8-5	BYPASS CENTERLINE	49°08'46.99"		700.000	320.089	600.436	89.712	3°06'37.23"	50.674	25.340	76.000	405.428	90.878	75.978	1.375
OR8-6	BYPASS CENTERLINE	0°59'35.40"		20,000.000	173.345	346.681	0.751								

BRIDGE APPROACH SECTION

Refer to the RK-Series Standard Road Plans.

112-5
04-19-05

Location	Bridge Station	End	Thickness Inches	Approach Pavement				Fixed or Movable Abutment F or M	Subdrain				Remarks			
				Pay Length Feet	Non-Reinf. Pavement Area Sq. Yds.	Single-Reinf. Pavement Area Sq. Yds.	Double-Reinf. Pavement Area Sq. Yds.		* Perforated Subdrain Ltn. Ft.	Subdrain Outlet		* Porous Backfill Cu. Yds.		* Class 'A' Crushed Stone Backfill Cu. Yds.	* Modified Subbase Tons	* Polymer Grid Sq. Yds.
										Station	Side					
	356+75.30 EBL	W	12	70	86.67	57.78	144.42	M	48	354+54.48	R	1.4		310.57	328.64	
	356+75.30 EBL	E	12	70	86.67	57.78	144.42	M	48	358+25.98	R	1.4		310.57	328.64	
	356+75.30 WBL	W	12	70	86.67	57.78	144.42	M	48	355+14.61	L	1.4		310.57	328.64	
	356+75.30 WBL	E	12	70	86.67	57.78	144.42	M	48	358+86.12	L	1.4		310.57	328.64	

TABULATION OF SOD OR ROCK FLUME FOR BRIDGE END DRAIN

Refer to Standard Road Plan RF-39 or RF-40

104-8A
10-21-03

Location	Bridge Station	Bridge Corner	Distance DI-1 or DI-2	Shoulder		Macadam Stone Base Material	Engineering Fabric	Sodding Squares	Class E Erosion Stone	Remarks
				Panels Required A B C or D	PCC Sq. Yds.					
	356+75.30 EBL	NE	24.92	1	13.33	13.33	8.40	0.59	29.68	18.26
	356+75.30 EBL	SE	29.92	-	-	-	0.59	123.82	84.57	
	356+75.30 WBL	NW	22.94	1	17.78	17.78	11.20	0.59	116.26	79.25
	356+75.30 WBL	SE	29.19	-	-	-	0.59	29.68	18.26	

**STAGE 1 FENCING
BY GRADING CONTRACTOR**

100-7A
MODIFIED

Div.	Location	Side	Length (Station)	Remarks
1	353+60.24, 220.41 Rt.	R	2.08	
1	357+52.73, 68.90 Rt.	R	2.50	
1	355+27.73, 25.65 Rt.	M	0.62	
1	357+77.73, 25.65 Rt.	M	0.62	
1	354+79.38, 189.14 Lt.	L	1.63	
1	358+37.87, 68.90 Lt.	L	1.67	

Design No: 1203
File No: 29488

SNYDER & ASSOCIATES

STATE OF IOWA

FISCAL YEAR

JEFFERSON

COUNTY

PROJECT NUMBER

NHSN-34-8(105)--2R-51

SHEET NUMBER

C.02

POLLUTION PREVENTION PLAN

110-12A

All contractors/subcontractors shall conduct their operations in a manner that minimizes erosion and prevents sediments from leaving the highway right-of-way. The prime contractor shall be responsible for compliance and implementation of the Pollution Prevention Plan (PPP) for their entire contract. This responsibility shall be further shared with subcontractors whose work is a source of potential pollution as defined in this PPP.

1. SITE DESCRIPTION

This Pollution Prevention Plan (PPP) is for the construction of a four lane divided highway, bridges, sideroads, entrances, recreational trail, and interchange ramps from the Cedar View Trail to Crow Creek.

This PPP covers approximately 502 acres with an estimated 213 acres being disturbed. The portion of the PPP covered by this contract has 3 acres disturbed.

The PPP is located in an area of Haig-Grundy-Clarinda, Pershing-Lindley-Rinda, Weller-Lindley, and Nodaway-Coppock soil associations. The estimated average SCS runoff curve number for this PPP after completion will be 79.

Refer to the grading plans for locations of typical slopes, ditch grades, and major structural and non-structural controls. A copy of this plan will be on file at the Resident Construction engineer's office. Runoff from this work will flow into Cedar Creek, Crow Creek and Unnamed Creek.

POTENTIAL SOURCES OF POLLUTION:

Site sources of pollution generated as a result of this work relate to silt and sediment which may be transported as a result of a storm event. However, this PPP provides conveyance for other (non project related) operations. These other operations have storm water runoff, the regulation of which is beyond the control of this PPP. Potentially this runoff can contain various pollutants related to site-specific land uses. Examples are:

Rural Agricultural Activities:

Runoff from agricultural land use can potentially contain chemicals including herbicides, pesticides, fungicides and fertilizers.

Commercial and Industrial Activities:

Runoff from commercial, industrial, and commerce land use may contain constituents associated with the specific operation. Such operations are subject to potential leaks and spills which could be commingled with run-off from the facility. Pollutants associated with commercial and industrial activities are not readily available since they are typically proprietary.

2. CONTROLS

At locations where runoff can move offsite, silt fence shall be placed along the perimeter of the areas to be disturbed prior to beginning grading, excavation or clearing and grubbing operations. Vegetation in areas not needed for construction shall be preserved. As areas reach their final grade, additional silt fences, silt basins, intercepting ditches, sod flumes, letdowns, bridge end drains, and earth dikes shall be installed as specified in the plans and/or as required by the project engineer. This will include using silt fence as ditch checks and to protect intakes. Temporary stabilizing seeding shall be completed as the disturbed areas are constructed. If construction activity is not planned to occur in a disturbed area for at least 21 days, the area shall be stabilized by temporary seeding or mulching within 14 days. Other stabilizing methods shall be used outside the seeding time period.

This work shall be done in accordance with Section 2602 of the Standard Specification. If the work involved is not applicable to any contract items, the work shall be paid for according to Article 1109.03 paragraph B.

As the work progresses, additional erosion control items may be required as determined by the contractor after field investigation. The contractor will complete the construction with the establishment of permanent perennial vegetation of all disturbed areas.

3. OTHER CONTROLS

Contractor disposal of unused construction materials and construction material wastes shall comply with applicable state and local waste disposal, sanitary sewer, or septic system regulations. In the event of a conflict with other governmental laws, rules and regulations, the more restrictive laws, rules or regulations shall apply.

APPROVED STATE OR LOCAL PLANS:

During the course of this construction, it is possible that situations will arise where unknown materials will be encountered. When such situations are encountered, they will be handled according to all Federal, state, and local regulations in effect at the time.

4. MAINTENANCE

The contractor is required to maintain all temporary erosion control measures in proper working order, including cleaning, repairing, or replacing them throughout the contract period. Cleaning of silt control devices shall begin when the features have lost 50% of their capacity.

5. INSPECTIONS

Inspections shall be made jointly by the contractor and the contracting authority every seven calendar days and after each rain event that is 1/2" or greater. The contractor shall immediately begin corrective action on all deficiencies found. The findings of this inspection shall be recorded in the project diary. This PPP may be revised based on the findings of the inspection. The contractor shall implement all revisions. All corrective actions shall be completed within 3 calendar days of the inspection.

POLLUTION PREVENTION PLAN

110-12A

6. NON-STORM DISCHARGES

This includes subsurface drains (i.e. longitudinal and standard sub-drains), slope drains and bridge end drains. The velocity of the discharge from these features may be controlled by the use of patio blocks, Class A stone or erosion stone.

Design No: 1203
File No: 29488

SNYDER & ASSOCIATES

STATE OF IOWA

FISCAL YEAR

JEFFERSON


COUNTY

PROJECT NUMBER

NHSN-34-8(105)--2R-51

SHEET NUMBER

C.03




FOR PROFILE INFORMATION REFER TO SHEET D.02

FOR INFORMATION ONLY

Design No: 1203
File No: 29499

105	+50	106	+50	107	+50	108	+50	109	+50	110	+50	111	+50	112	+50
DESIGN TEAM		SNYDER & ASSOCIATES				METRIC		IOWA DOT * OFFICE OF DESIGN		JEFFERSON		COUNTY		PROJECT NUMBER	
										NHSN-34-8(105)--2R-51		SHEET NUMBER		D.01	



DESIGN TEAM **SNYDER & ASSOCIATES** METRIC IOWA DOT • OFFICE OF DESIGN **JEFFERSON** COUNTY PROJECT NUMBER **NHSN-34-8(105)-2R-51** SHEET NUMBER **D.02**