

LOCAL AGENCY LETTING INFORMATION

CONTENTS

DATE ADDED	COUNTY/CITY	LETTING DATE	PAGE NUMBER
March 27, 2024	Jasper	April 17, 2024	2
March 29, 2024	Adair	April 22, 2024	3
April 2, 2024	Woodbury	April 22, 2024	4
April 3, 2024	Pocahontas	April 23, 2024	5
March 19, 2024	Buchanan	April 29, 2024	6
April 8, 2024	Humboldt	April 29, 2024	7
April 8, 2024	Humboldt	April 29, 2024	8
April 15, 2024	Dubuque	May 6, 2024	9
April 10, 2024	Monona	May 7, 2024	10
April 10, 2024	Linn	May 7, 2024	11
April 16, 2024	Pocahontas	May 7, 2024	12



County:	Jasper County	Project No.:	L-C050(E142S)73-50
Proposal Guarantee:	\$0.00	DBE or TSB Goal:	
Date of Letting:	4/17/2024	Time of Letting:	02:00 PM
Bid Turn-In Location:	County Engineer	Type of Project:	HMA Resurfacing with Milling
Contact Phone No.:	641-792-5862	Contact FAX No.:	641-791-7740

Specific Description of Project:

See attached plans for project details.

QUANTITY	UNIT	DESCRIPTION
0.4	MILE	CLEANING AND PREPARATION OF BASE
12	EACH	PATCHES BY COUNT (REPAIR)
4863	SY	PAVEMENT SCARIFICATION
703.8	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
45.4	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	HOT MIX ASPHALT PAVEMENT SAMPLES
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
900	SY	SUBBASE (PATCHES)
1	LS	MOBILIZATION

Date: 3/27/2024 Local Agency Official: Michael Frietsch, County Engineer



County:	Adair County	Project No.:	L-LRCBN17R73-01
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	4/22/2024	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	RCB Culvert Replacement – Single Box
Contact Phone No.:	641-743-6111	Contact FAX No.:	

Specific Description of Project:

This project involves replacing an existing timber box culvert with a reinforced concrete box culvert along Adair County 300th St. The project will also include the placement of revetment, granular surfacing, and seeding.

QUANTITY	UNIT	DESCRIPTION
234	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
558	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
40	CY	GRANULAR MATERIAL FOR BLANKET AND SUBDRAIN
99.1	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
1	LS	REMOVAL OF EXISTING STRUCTURES
810	CY	EXCAVATION, CLASS 20
62	CY	STRUCTURAL CONCRETE (RCB CULVERT)
8047	LB	REINFORCING STEEL
2	EACH	APRONS, METAL, 24 IN. DIA.
40	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.
2	EACH	SUBDRAIN OUTLET, DR-305
50	TON	REVETMENT, CLASS E
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
0.5	ACRE	MULCHING
0.5	ACRE	NATIVE GRASS SEEDING
300	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.

Date: 3/28/2024 Local Agency Official: Nick Kauffman, County Engineer



County:	Woodbury County	Project No.:	Pavement Markings 2024
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	4/22/2024	Time of Letting:	04:00 PM
Bid Turn-In Location:	620 Douglas Street Sioux City, Iowa 51101	Type of Project:	Pavement Markings
Contact Phone No.:	712-873-3215	Contact FAX No.:	712-873-3235

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
18700	STA	PAINTED PAVEMENT MARKING, WATERBORNE OR SOLVENT-BASED

Date: 4/1/2024 Local Agency Official: Mark Nahra, County Engineer



County:	Pocahontas County	Project No.:	PP-2024-76
Proposal Guarantee:	\$0.00	DBE or TSB Goal:	
Date of Letting:	4/23/2024	Time of Letting:	11:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Pavement Patching
Contact Phone No.:	712-335-3252	Contact FAX No.:	712-335-3282

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
1	LS	TRAFFIC CONTROL
50	EACH	FLAGGERS
20	EACH	PILOT CARS
165	EACH	CD JOINT ASSEMBLY
83	EACH	PATCHES, FULL-DEPTH FINISH, BY COUNT
1	LS	MOBILIZATION
600	SY	Patches, Full-Depth Finish, 7 Inch, by Area
250	SY	Patches, Full-Depth Finish, 8 Inch, by Area
850	SY	Patches, Full-Depth Finish, 10 Inch, by Area

Date: 4/2/2024 Local Agency Official: Jack Moellering, County Engineer



County:	Buchanan County	Project No.:	L73-10
Proposal Guarantee:	\$0.00	DBE or TSB Goal:	
Date of Letting:	4/29/2024	Time of Letting:	09:00 AM
Bid Turn-In Location:	Auditors Office	Type of Project:	Materials
Contact Phone No.:	319-334-6031	Contact FAX No.:	319-334-9951

Specific Description of Project:

3 90' Rail cars cut to 68' 2"

QUANTITY	UNIT	DESCRIPTION
3	EACH	railcar

Date: 3/19/2024 Local Agency Official: Brian Keierleber, County Engineer



County:	Humboldt County	Project No.:	L-C-10229073-46
Proposal Guarantee:	\$10,000.00	DBE or TSB Goal:	
Date of Letting:	4/29/2024	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Box Culverts
Contact Phone No.:	515-332-2366	Contact FAX No.:	515-332-5142

Specific Description of Project:

Tied With: LC-171507

QUANTITY	UNIT	DESCRIPTION
1	LS	REMOVAL OF EXISTING BRIDGE
338	CY	EXCAVATION, CLASS 20
1034	CY	EXCAVATION, CLASS 24
60	LF	PRECAST CONCRETE BOX CULVERT, 10 FT. X 10 FT.
2	EACH	PRECAST CONCRETE BOX CULVERT STRAIGHT END SECTION, 10 FT. X 10 FT.
260	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 15 IN. DIA.
68	SY	ENGINEERING FABRIC
50	TON	REVETMENT, CLASS E
1	LS	MOBILIZATION

Date: 4/8/2024 Local Agency Official: Ben Loots, County Engineer



County:	Humboldt County	Project No.:	L-C-17150773-46
Proposal Guarantee:	\$10,000.00	DBE or TSB Goal:	
Date of Letting:	4/29/2024	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Box Culverts
Contact Phone No.:	515-332-2366	Contact FAX No.:	515-332-5142

Specific Description of Project:

Tied With: LC-102290

QUANTITY	UNIT	DESCRIPTION
1	LS	REMOVAL OF EXISTING BRIDGE
265	CY	EXCAVATION, CLASS 20
960	CY	EXCAVATION, CLASS 24
60	LF	PRECAST CONCRETE BOX CULVERT, 10 FT. X 10 FT.
2	EACH	PRECAST CONCRETE BOX CULVERT STRAIGHT END SECTION, 10 FT. X 10 FT.
10	LF	CORRUGATED PIPE CULVERT,
160	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 15 IN. DIA.
80	SY	ENGINEERING FABRIC
60	TON	REVETMENT, CLASS E
1	LS	MOBILIZATION
1	EACH	8" Field Intake
70	LF	Ag Tile, 8"

Date: 4/8/2024 Local Agency Official: Ben Loots, County Engineer



County:	Dubuque County	Project No.:	LFM-B24(05)7X-31
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	5/6/2024	Time of Letting:	09:00 AM
Bid Turn-In Location:	Dubuque County Auditor's Office	Type of Project:	Bridge or Culvert
Contact Phone No.:	563-557-7283	Contact FAX No.:	563-557-1973

Specific Description of Project:

CCS 80' 0" x 30' 0" with a 15° left ahead skew bridge replacement on Thunder Rd, approx. 1.1 miles north of the City of Holy Cross over the North Fork Maquoketa River in Section 18 of Concord Township, T90N-R1W.

QUANTITY	UNIT	DESCRIPTION
175.8	CY	STRUCTURAL CONCRETE (BRIDGE)
46638	LB	REINFORCING STEEL, EPOXY COATED
1080	LF	PILES, STEEL, HP 10 X 42
1	LS	MOBILIZATION
191	LF	CONCRETE ENCASEMENT OF STEEL H PILES, HP 10 X 42 (P10L TYPE 3)
182.2	LF	CONCRETE BARRIER RAILING
455	TON	REVETMENT, CLASS E
170	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.
91	TON	HOT MIX ASPHALT STANDARD TRAFFIC, BASE COURSE, 1/2 IN. MIX
91	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
1	LS	REMOVAL OF EXISTING BRIDGE
1032	CY	EXCAVATION, CLASS 13, CHANNEL
10.92	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
174	CY	MODIFIED SUBBASE

Date: 4/15/2024 Local Agency Official: Russell Weber, County Engineer



County:	Monona County	Project No.:	FM-C067(94)55-67
Proposal Guarantee:	\$32,000.00	DBE or TSB Goal:	
Date of Letting:	5/7/2024	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Granular Surfacing of Roadway
Contact Phone No.:	712-433-2284	Contact FAX No.:	712-433-1230

Specific Description of Project:

Monona County Desires to place Granular Surfacing Material on several Farm to Market routes in Western Monona County. Each bid item represents a segment of road that shall receive 250 tons per mile of 1.5" Road Stone. The supplied product shall be limestone meeting the gradation listed in the contract documents. All trucks shall be belly dumps or end dumps with gates and chains that can be set for uniform spreading along the designated routes. The unit price shall include all labor, materials and equipment to complete the necessary hauling to complete the project.

QUANTITY	UNIT	DESCRIPTION
1000	TON	Granular Surfacing on Road, Class D Crushed Stone
750	TON	Granular Surfacing on Road, Class D Crushed Stone
1525	TON	Granular Surfacing on Road, Class D Crushed Stone
1500	TON	Granular Surfacing on Road, Class D Crushed Stone
1125	TON	Granular Surfacing on Road, Class D Crushed Stone
1000	TON	Granular Surfacing on Road, Class D Crushed Stone
1050	TON	Granular Surfacing on Road, Class D Crushed Stone
1675	TON	Granular Surfacing on Road, Class D Crushed Stone
1175	TON	Granular Surfacing on Road, Class D Crushed Stone
1375	TON	Granular Surfacing on Road, Class D Crushed Stone
325	TON	Granular Surfacing on Road, Class D Crushed Stone
800	TON	Granular Surfacing on Road, Class D Crushed Stone
1325	TON	Granular Surfacing on Road, Class D Crushed Stone
750	TON	Granular Surfacing on Road, Class D Crushed Stone
625	TON	Granular Surfacing on Road, Class D Crushed Stone
1950	TON	Granular Surfacing on Road, Class D Crushed Stone
1875	TON	Granular Surfacing on Road, Class D Crushed Stone

Date: 4/9/2024 Local Agency Official: , County Engineer



County:	Linn County	Project No.:	LOST-CMP 2666(24)
Proposal Guarantee:	\$4,000.00	DBE or TSB Goal:	
Date of Letting:	5/7/2024	Time of Letting:	11:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Culvert Replacement
Contact Phone No.:	319-892-6400	Contact FAX No.:	319-892-6419

Specific Description of Project:

Twin CMP culvert replacement.

QUANTITY	UNIT	DESCRIPTION
160	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
84	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
13	CY	MODIFIED SUBBASE
108	TON	CHOKE STONE BASE
91	TON	GRANULAR BACKFILL
203	CY	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT
8	CY	STRUCTURAL CONCRETE (MISCELLANEOUS)
560	LB	REINFORCING STEEL
102	LF	CULVERT, CORRUGATED METAL ARCH ROADWAY PIPE, 60 IN. X 46 IN.
20	LF	SUBDRAIN, PLASTIC PIPE, 6 IN.
50	TON	REVETMENT, CLASS D
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
0.3	ACRE	MULCHING, BONDED FIBER MATRIX
0.3	ACRE	HYDRAULIC SEEDING
150	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.

Date: 4/9/2024 Local Agency Official: Brad Ketels, County Engineer



County:	Pocahontas County	Project No.:	PM-2024-76
Proposal Guarantee:	\$0.00	DBE or TSB Goal:	
Date of Letting:	5/7/2024	Time of Letting:	10:30 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Pavement Marking
Contact Phone No.:	712-335-3252	Contact FAX No.:	712-335-3282

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
12457.61	STA	PAINTED PAVEMENT MARKING, WATERBORNE OR SOLVENT-BASED
26	EACH	PAINTED SYMBOLS AND LEGENDS, WATERBORNE OR SOLVENT-BASED
1	LS	MOBILIZATION

Date: 4/16/2024 Local Agency Official: Jack Moellering, County Engineer