

LOCAL AGENCY LETTING INFORMATION

CONTENTS

DATE ADDED	COUNTY/CITY	LETTING DATE	PAGE NUMBER
May 28, 2024	Cedar	June 25, 2024	2
June 17, 2024	Dubuque	July 1, 2024	3
June 6, 2024	Woodbury	July 9, 2024	4
June 11, 2024	Sac	July 11, 2024	5
June 13, 2024	Winnebago	July 12, 2024	6
June 19, 2024	Muscatine	July 22, 2024	7
June 24, 2024	Chickasaw	July 22, 2024	9



County:	Cedar County	Project No.:	L-20230673-16
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	6/25/2024	Time of Letting:	09:30 AM
Bid Turn-In Location:	County Engineer	Type of Project:	HMA Paving
Contact Phone No.:	563-886-6102	Contact FAX No.:	

Specific Description of Project:

Hot Mix Asphalt resurfacing - 2 inch HMA mill and fill of 255th St. in Cedar Valley.

QUANTITY	UNIT	DESCRIPTION
0.3	MILE	CLEANING AND PREPARATION OF BASE
1276.8	SY	PATCHES, FULL-DEPTH REPAIR
39	EACH	PATCHES BY COUNT (REPAIR)
3250	SY	PAVEMENT SCARIFICATION
30.51	TON	HOT MIX ASPHALT MIXTURE, WEDGE, LEVELING OR STRENGTHENING COURSE
419.3	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
27	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	HOT MIX ASPHALT PAVEMENT SAMPLES
15	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
15	TON	SURFACING, DRIVEWAY, CLASS A CRUSHED STONE
0.76	STA	PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED
1	LS	TRAFFIC CONTROL
30	EACH	FLAGGERS
10	EACH	PILOT CARS
318.4	SY	SUBBASE (PATCHES)
1	LS	MOBILIZATION

Date: 5/28/2024 Local Agency Official: Robert Fangmann, County Engineer



County:	Dubuque County	Project No.:	L-B24(06)73-31
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	7/1/2024	Time of Letting:	09:00 AM
Bid Turn-In Location:	Dubuque County Auditor's Office	Type of Project:	Bridge or Culvert
Contact Phone No.:	563-557-7283	Contact FAX No.:	563-557-1973

Specific Description of Project:

CCS Bridge replacement on Olde Worthington Rd, approximately 0.79 miles south of Rockville Rd in Section 30, Dodge Township T88 N R2W.

QUANTITY	UNIT	DESCRIPTION
246.4	CY	STRUCTURAL CONCRETE (BRIDGE)
61378	LB	REINFORCING STEEL, EPOXY COATED
288	LF	CONCRETE ENCASEMENT OF STEEL H PILES, HP 10 X 42 (P10L TYPE 3)
820	LF	PILES, STEEL, HP 10 X 42
1	LS	MOBILIZATION
224.5	LF	CONCRETE BARRIER RAILING
600	TON	REVETMENT, CLASS E
1	LS	REMOVAL OF EXISTING BRIDGE
350	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
408	LF	ROCK CORE DRILLING

Date: 6/17/2024	Local Aganov O	Official: Russell Weber.	County Engineer	
Date. 0/17/2024	Local Agency C	Jiliciai. Russell Webel,	County Engineer	



County:	Woodbury County	Project No.:	L-B(J178)73-97
Proposal Guarantee:	\$37,500.00	DBE or TSB Goal:	
Date of Letting:	7/9/2024	Time of Letting:	04:30 PM
Bid Turn-In Location:	620 Douglas Street Sioux City, Iowa 51101	Type of Project:	Bridge or Culvert
Contact Phone No.:	712-873-3215	Contact FAX No.:	712-873-3235

Specific Description of Project:

Bridge Replacement in Woodbury County on Jewell Ave, over Wolf Creek, from 170th street south 0.3 miles.

QUANTITY	UNIT	DESCRIPTION
0.2	ACRE	CLEARING AND GRUBBING
111	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
1058	CY	EXCAVATION, CLASS 10, CHANNEL
186	TON	GRANULAR SURFACING ON ROAD, CRUSHED CONCRETE
1	LS	REMOVAL OF EXISTING BRIDGE
643	CY	EXCAVATION, CLASS 20
200.1	CY	STRUCTURAL CONCRETE (BRIDGE)
102	LB	REINFORCING STEEL
58841	LB	REINFORCING STEEL, EPOXY COATED
202.2	LF	CONCRETE OPEN RAILING, TL-4
236	LF	CULVERT, CORRUGATED METAL ROADWAY PIPE, 24 IN. DIA.
1825	LF	PILES, STEEL, HP 10 X 42
376	LF	CONCRETE ENCASEMENT OF STEEL H PILES, HP 10 X 42 (P10L TYPE 3)
4	EACH	STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-225
4	EACH	STEEL BEAM GUARDRAIL END ANCHOR, BOLTED
635	SY	ENGINEERING FABRIC
730	TON	REVETMENT, CLASS E
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
2	EACH	CORRUGATED METAL PIPE, DROP INLET
1	LS	REMOVAL OF CAR BODIES IN STREAM BANK
0.5	ACRE	MULCHING
0.5	ACRE	SEEDING AND FERTILIZING (RURAL)
4	EACH	STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-221

	Date: 6/6/2024	Local Agency Official: Mark Nahra, County Engir	neer
--	----------------	---	------



County:	Sac County	Project No.:	LFM-PCCP257X-81
Proposal Guarantee:	\$37,500.00	DBE or TSB Goal:	
Date of Letting:	7/11/2024	Time of Letting:	02:00 PM
Bid Turn-In Location:	County Engineer	Type of Project:	PCC Patching
Contact Phone No.:	712-662-7687	Contact FAX No.:	712-662-4746

Specific Description of Project:

Sac County PCC Patching Project on various roads within the county.

QUANTITY	UNIT	DESCRIPTION
1	LS	TRAFFIC CONTROL
75	EACH	FLAGGERS
30	EACH	PILOT CARS
2164.6	SY	PATCHES, FULL-DEPTH FINISH, BY AREA
1354.22	SY	PATCHES, FULL-DEPTH FINISH, BY AREA (50 FEET OR GREATER IN LENGTH)
133	EACH	PATCHES, FULL-DEPTH FINISH, BY COUNT
1	LS	MOBILIZATION

Date: 6/11/2024 Local Agency Official: Nick Buse, County Engineer



County:	Winnebago County	Project No.:	Winnebago County Storage Building - Forest City
Proposal Guarantee:	\$0.00	DBE or TSB Goal:	
Date of Letting:	7/12/2024	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Pre-Engineered Wood Building, including foundations, concrete floor, mechanical, and electrical
Contact Phone No.:	641-585-2905	Contact FAX No.:	641-585-2891

Specific Description of Project:

Construction of a 150' x 60' x 18' pre-engineered wood building with a 20' x 28' x 9' attached break room.

The work for the project will be accomplished under three (3) separate construction contracts including:

- 1. General Construction
- 2. Mechanical Construction, including: Plumbing, Heating, and Ventilating
 3. Electrical Construction, including: Power, Lighting, Communication, and Fire Safety

QUANTITY	UNIT	DESCRIPTION	
1	LS	General Construction	
1 LS Mechanical Construction		Mechanical Construction	
1	LS	Electrical Construction	

Local Agency Official: Scott Meinders, County Engineer



County:	Muscatine County	Project No.:	LFM-(FU-9)7X-70
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	7/22/2024	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Bridge Replacement - PPCB
Contact Phone No.:	563-263-6351	Contact FAX No.:	563-263-6358

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
0.1	ACRE	CLEARING AND GRUBBING
1416	CY	EMBANKMENT-IN-PLACE
632	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
1601	CY	EXCAVATION, CLASS 10, CHANNEL
647	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
583	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
30	TON	SURFACING, DRIVEWAY, CLASS A CRUSHED STONE
1	LS	REMOVAL OF EXISTING BRIDGE
107	CY	EXCAVATION, CLASS 20
157.9	CY	STRUCTURAL CONCRETE (BRIDGE)
38523	LB	REINFORCING STEEL, EPOXY COATED
5	EACH	BEAMS, PRETENSIONED PRESTRESSED CONCRETE, C80
1180	LB	STRUCTURAL STEEL
214	LF	CONCRETE OPEN RAILING, TL-4
80	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
450	LF	PILES, STEEL, HP 10 X 57
4	EACH	STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-201
4	EACH	STEEL BEAM GUARDRAIL END ANCHOR, BOLTED
4	EACH	STEEL BEAM GUARDRAIL FLARED END TERMINAL, LS-626
1726	SY	ENGINEERING FABRIC
1474.2	TON	REVETMENT, CLASS E
30	CY	REVETMENT, REMOVE AND REPLACE
579	LF	FENCE, FIELD
10	EACH	FIELD FENCE BRACE PANELS
581	LF	REMOVAL OF FENCE, FIELD
1	LS	CONSTRUCTION SURVEY
4	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
2.4	ACRE	MULCHING
1.2	ACRE	SEEDING AND FERTILIZING (RURAL)
408	SQ	SLOPE PROTECTION, WOOD EXCELSIOR MAT
1.2	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
135	LF	SILT FENCE
444	LF	SILT FENCE FOR DITCH CHECKS
8	EACH	SILT BASINS

444	LF	REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS
		MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
		PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
		MOBILIZATIONS, EROSION CONTROL
		MOBILIZATIONS, EMERGENCY EROSION CONTROL

Date: 6/19/2024 Local Agency Official: Bryan Horesowsky, County Engineer



County:	Chickasaw County	Project No.:	ARPA-2024-C019(01)
Proposal Guarantee:	\$37,500.00	DBE or TSB Goal:	
Date of Letting:	7/22/2024	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	PCC Paving
Contact Phone No.:	641-394-2321	Contact FAX No.:	641-394-5280

Specific Description of Project:

PCC Paving Project

QUANTITY	UNIT	DESCRIPTION
1210	CY	EXCAVATION, CLASS 10, WASTE
1	CY	EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS
1816	CY	MODIFIED SUBBASE
1819	TON	GRANULAR SHOULDERS, TYPE B
8638.8	SY	STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 8 IN.
4	EACH	RUMBLE STRIP PANEL (PCC SURFACE)
5978	LF	SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.
20	EACH	SUBDRAIN OUTLET, 500-10
9609.6	SY	REMOVAL OF PAVEMENT
45.5	SY	DRIVEWAY, P.C. CONCRETE, 6 IN.
75.7	SY	DRIVEWAY, P.C. CONCRETE, 8 IN.
42.6	SY	RAILROAD APPROACH SECTION, HMA
1	LS	CONSTRUCTION SURVEY
124.77	STA	PAINTED PAVEMENT MARKING, WATERBORNE OR SOLVENT-BASED
2	EACH	PAINTED SYMBOLS AND LEGENDS, WATERBORNE OR SOLVENT-BASED
3	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
1	LS	RAILROAD PROTECTIVE LIABILITY INSURANCE FOR DAKOTA, MINNESOTA, AND EASTERN RAILROAD CORP.

Date: 6/24/2024 Local Agency Official: Roman Lensing, County Engineer