

**LOCAL AGENCY LETTING INFORMATION**

**CONTENTS**

<b>DATE ADDED</b>	<b>COUNTY</b>	<b>LETTING DATE</b>	<b>PAGE NUMBER</b>
October 3, 2017.....	Lyon.....	October 20, 2017.....	2
October 4, 2017.....	Lyon.....	October 20, 2017.....	3
October 4, 2017.....	Lyon.....	October 20, 2017.....	4
October 4, 2017.....	Lyon.....	October 20, 2017.....	5
October 11, 2017.....	Clayton.....	October 26, 2017.....	6
October 11, 2017.....	Jones.....	October 31, 2017.....	8
October 11, 2017.....	Lyon.....	November 9, 2017.....	9
October 11, 2017.....	Lyon.....	November 9, 2017.....	10

**LOCAL AGENCY LETTING INFORMATION**

-----  
 Lyon County -- L-(20R)--73-60  
 Proposal Guarantee \$ 25000.0  
 County Engineer's Office, Rock Rapids , IA, October 20, 2017, 8:55 AM  
 320-Bridges, Replace existing pony truss bridge with a CCSB.  
 Contact # 712-472-8230 FAX # 712-472-3993

8.000	UNIT	CLEARING AND GRUBBING
224.000	LF	CONCRETE ENCASEMENT OF STEEL H PILES, HP 12 X 53 (P10A TYPE 3)
202.200	LF	CONCRETE OPEN RAILING, TL-4
1.000	LS	CONSTRUCTION SURVEY
40.000	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.
575.000	SY	ENGINEERING FABRIC
1160.000	CY	EXCAVATION, CLASS 10, CHANNEL
116.000	CY	EXCAVATION, CLASS 20
60.000	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
250.000	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
1.000	LS	MOBILIZATION
1.000		EACH MOBILIZATIONS, EMERGENCY EROSION CONTROL
1.000		EACH MOBILIZATIONS, EROSION CONTROL
0.600		ACRE MULCHING
4.000		EACH OBJECT MARKER, TYPE 3
260.000	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
1200.000	LF	PILES, STEEL, HP 10 X 42
50444.000	LB	REINFORCING STEEL
1.000	LS	REMOVAL OF EXISTING BRIDGE
345.000	TON	REVTMENT, CLASS E
2.000		EACH SAFETY CLOSURE
0.300		ACRE SEEDING AND FERTILIZING (RURAL)
240.000	LF	SILT FENCE
10.000	LF	SILT FENCE FOR DITCH CHECKS
0.300		ACRE STABILIZING CROP - SEEDING AND FERTILIZING
200.100	CY	STRUCTURAL CONCRETE (BRIDGE)
161.000	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
1.000	LS	TRAFFIC CONTROL

---

Bid Turn-in Location: County Engineer

Letting Notice request sent by:  
 Laura Sievers  
[lsievers@co.lyon.ia.us](mailto:lsievers@co.lyon.ia.us)  
 Lyon County  
 03-Oct-2017

**LOCAL AGENCY LETTING INFORMATION**

Lyon County -- L-(R70RP)--73-60

Proposal Guarantee \$ 2500.0

County Engineer's Office, Rock Rapids , IA, October 20, 2017, 8:55 AM

320-Bridge, REPLACE AN EXISTING TIMBER BRIDGE WITH A CCSB USING ROUND STEEL PIPE PILE.

Contact # 712-472-8230 FAX # 712-472-3993

222.200	LF	CONCRETE OPEN RAILING, TL-4
1.000	LS	CONSTRUCTION SURVEY
120.000	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.
840.000	SY	ENGINEERING FABRIC
700.000	CY	EXCAVATION, CLASS 10, CHANNEL
33.000	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
122.000	CY	EXCAVATION, CLASS 20
135.000	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
750.000	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
1.000	LS	MOBILIZATION
1.000		EACH MOBILIZATIONS, EMERGENCY EROSION CONTROL
1.000		EACH MOBILIZATIONS, EROSION CONTROL
1.400		ACRE MULCHING
4.000		EACH OBJECT MARKER, TYPE 3
330.000	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
450.000	LF	PILES, STEEL PIPE, 12 IN. ; 10 @ 45'
900.000	LF	PILES, STEEL PIPE, 16 IN. (P10L TYPE 1)
56971.000	LB	REINFORCING STEEL
1.000	LS	REMOVAL OF EXISTING BRIDGE
570.000	TON	REVTMENT, CLASS E
2.000		EACH SAFETY CLOSURE
0.700		ACRE SEEDING AND FERTILIZING (RURAL)
710.000	LF	SILT FENCE
40.000	LF	SILT FENCE FOR DITCH CHECKS
0.700		ACRE STABILIZING CROP - SEEDING AND FERTILIZING
229.200	CY	STRUCTURAL CONCRETE (BRIDGE)
376.000	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
1.000	LS	TRAFFIC CONTROL

---

Bid Turn-in Location: County Engineer

Letting Notice request sent by:

Laura Sievers

[lsievers@co.lyon.ia.us](mailto:lsievers@co.lyon.ia.us)

Lyon County

04-Oct-2017

**LOCAL AGENCY LETTING INFORMATION**

Lyon County -- L-(70R)--73-60

Proposal Guarantee \$ 25000.0

County Engineer's Office, Rock Rapids, IA, October 20, 2017, 8:55 AM

320-Bridges, REPLACE EXISTING TIMBER BRIDGE WITH A CCSB USING H PILE FOUNDATIONS.

Contact # 712-472-8230 FAX # 712-472-3993

196.000	LF	CONCRETE ENCASEMENT OF STEEL H PILES, HP 12 X 53 (P10L TYPE 3)
222.200	LF	CONCRETE OPEN RAILING, TL-4
1.000	LS	CONSTRUCTION SURVEY
120.000	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.
840.000	SY	ENGINEERING FABRIC
700.000	CY	EXCAVATION, CLASS 10, CHANNEL
33.000	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
122.000	CY	EXCAVATION, CLASS 20
135.000	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
750.000	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
1.000	LS	MOBILIZATION
1.000		EACH MOBILIZATIONS, EMERGENCY EROSION CONTROL
1.000		EACH MOBILIZATIONS, EROSION CONTROL
1.400		ACRE MULCHING
4.000		EACH OBJECT MARKER, TYPE 3
330.000	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
450.000	LF	PILES, STEEL, HP 10 X 42
840.000	LF	PILES, STEEL, HP 12 X 53
56971.000	LB	REINFORCING STEEL
1.000	LS	REMOVAL OF EXISTING BRIDGE
570.000	TON	REVTMENT, CLASS E
2.000		EACH SAFETY CLOSURE
7.000		ACRE SEEDING AND FERTILIZING (RURAL)
710.000	LF	SILT FENCE
40.000	LF	SILT FENCE FOR DITCH CHECKS
7.000		ACRE STABILIZING CROP - SEEDING AND FERTILIZING
229.200	CY	STRUCTURAL CONCRETE (BRIDGE)
376.000	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
1.000	LS	TRAFFIC CONTROL

---

Bid Turn-in Location: County Engineer

Letting Notice request sent by:

Laura Sievers

[lsievers@co.lyon.ia.us](mailto:lsievers@co.lyon.ia.us)

Lyon County

04-Oct-2017

**LOCAL AGENCY LETTING INFORMATION**

Lyon County -- L-(R20RP)--73-60

Proposal Guarantee \$ 25000.0

County Engineer's Office, Rock Rapids , IA, October 20, 2017, 8:55 AM

320-BRIDGE, REPLACE EXISTING PONY TRUSS BRIDGE WITH A CCSB USING ROUND STEEL PIPE PILE.

Contact # 712-472-8230 FAX # 712-472-3993

8.000	UNIT	CLEARING AND GRUBBING
202.200	LF	CONCRETE OPEN RAILING, TL-4
1.000	LS	CONSTRUCTION SURVEY
40.000	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.
575.000	SY	ENGINEERING FABRIC
1160.000	CY	EXCAVATION, CLASS 10, CHANNEL
116.000	CY	EXCAVATION, CLASS 20
60.000	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
250.000	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
1.000	LS	MOBILIZATION
1.000	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL
1.000	EACH	MOBILIZATIONS, EROSION CONTROL
0.600	ACRE	MULCHING
4.000	EACH	OBJECT MARKER, TYPE 3
260.000	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
400.000	LF	PILE, STEEL PIPE, 12 IN. ; 10 @ 40'
720.000	LF	PILES, STEEL PIPE, 16 IN. (P10L TYPE 1)
50383.000	LB	REINFORCING STEEL
1.000	LS	REMOVAL OF EXISTING BRIDGE
345.000	TON	REVTMENT, CLASS E
2.000	EACH	SAFETY CLOSURE
0.300	ACRE	SEEDING AND FERTILIZING (RURAL)
240.000	LF	SILT FENCE
10.000	LF	SILT FENCE FOR DITCH CHECKS
0.300	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
200.100	CY	STRUCTURAL CONCRETE (BRIDGE)
161.000	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
1.000	LS	TRAFFIC CONTROL

---

Bid Turn-in Location: County Engineer

Letting Notice request sent by:

Laura Sievers

[lsievers@co.lyon.ia.us](mailto:lsievers@co.lyon.ia.us)

Lyon County

04-Oct-2017

**LOCAL AGENCY LETTING INFORMATION**

A-1

NOTICE TO BIDDERS AND  
NOTICE OF PUBLIC HEARING ON PLANS, SPECIFICATIONS, FORM OF CONTRACT, AND ESTIMATED  
COST FOR CLAYTON COUNTY, IOWA  
2017 NICKEL ROAD FLOOD DAMAGE RESTORATION  
DISASTER NO. 4334

Time and Place for Filing Sealed Proposals

Sealed bids for the work comprising the improvement as stated below must be filed before 9:00 A.M. on October 26, 2017 in the office of the Clayton County Engineer, 600 Gunder Road, Elkader, Iowa 52043.

Time and Place Sealed Proposals Will be Opened and Considered

Sealed proposals will be opened and bids read and tabulated at 9:00 A.M. on October 26, 2017, at the office of the Clayton County Engineer, 600 Gunder Road, Elkader, Iowa for consideration at the County Board of Supervisors meeting at the County office building at 600 Gunder Road, Elkader, Iowa at 10:00 A.M. on October 30, 2017. Clayton County reserves the right to reject any and all bids.

Public Hearing

Clayton County, Iowa, will hold a public hearing on the proposed plans, specifications, form of contract, and estimate of cost for the 2017 Nickel Road Flood Damage Restoration, Disaster No. 4334 project in accordance with the provisions of Chapter 26, Code of Iowa, at 10:00 A.M. on the 23rd day of October, 2017, at the County office building at 600 Gunder Road, Elkader, Iowa. Said proposed plans, specifications, form of contract, and estimated cost are now on file in the office of Clayton County. At said hearing any interested person may appear and file objections thereto.

Time for Commencement and Completion of Work

Work on the improvement shall commence on or before the date specified in the written "Notice to Proceed" and the roadway shall be open to traffic by December 22, 2017 and the project completed by January 19, 2018. Liquidated damages in the amount of \$1,000.00 per calendar day will be assessed for each day that the work shall remain uncompleted after the end of the contract periods, with due allowance for extension of contract period due to conditions beyond the control of the Contractor, as approved by Clayton County.

Bid Security

Each bidder shall accompany its bid with bid security as defined in Iowa Code Section 26.8 and as specified by Clayton County. The bid security shall be 5% of the total amount of the bid.

Contract Documents

Copies of the contract documents are available from the Clayton County Engineer, 600 Gunder Road, Elkader, Iowa 52043, phone (563) 245-1782, fax (563) 245-1794. There is no plan deposit.

Preference for Iowa Products

By virtue of statutory authority, preference will be given to products and provisions grown and coal produced within the State of Iowa to the extent lawfully required under Iowa statutes.

Sales Tax

The bidder should not include sales tax in the bid. Sales tax exemption certificates will be issued in accordance with Iowa Code 423.3, subsection 80, and provided to the contractor and subcontractors for all materials purchased for incorporation in the project.

## LOCAL AGENCY LETTING INFORMATION

A-2

### Bidder Status Form

Under Iowa law, Bidders are required to submit the Bidder Status Form that follows the Bid Form in the specifications. Failure to provide the form with the bid may result in the bid being deemed nonresponsive. This may result in the bid being rejected by the Owner.

### General Nature of Public Improvement

The extent of the work involved in the 2017 Nickel Road Flood Damage Restoration, Disaster No. 4334 project consists of earthwork and granular surfacing for roadway restoration. Work also includes channel excavation, debris removal, CMP culvert pipes, and underwater and above water placement of Class E revetment.

Bid Tabulation - The bid totals will be available at and after the public bid opening. However, an itemized bid tabulation will not be publicly available until after the Owner awards the contract.

The Clayton County hereby reserves the right to reject any or all bids and to waive informalities and irregularities and award a contract as deemed to be in the best interest of the County.

This project has a Buy American Provision. All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America.

This project has Cargo Preference Act requirements which addresses required use of and documentation of the use of United States flag vessels pursuant to Pub.L.664(436.S.C.1241(b)).

This project is funded in part by the Federal Emergency Management Agency (FEMA). Under the FEMA program bidders are required to make positive efforts to solicit bids/quotes from small and minority businesses, women's business enterprises, and labor surplus area firms. Although no goal has been established, the contractor will be required to demonstrate that they have made a good faith effort in solicitation.

This Notice is given by authority of Clayton County.

**LOCAL AGENCY LETTING INFORMATION**

Jones County -- M-0718  
Proposal Guarantee \$ 5000.0  
County boardroom, Anamosa , IA, October 31, 2017, 10:00 AM  
Bridge Removal, Bridge removal over the Wapsipinicon River, 335' x 18.5' Steel Thru High Truss 2 spans; 135' x 18.5' I-Beam Approach 2 spans  
Contact # 319-462-3785 FAX # 319-462-3903

133.000 SY ENGINEERING FABRIC  
1.000 LS MOBILIZATION  
1.000 LS REMOVAL OF EXISTING BRIDGE  
175.000 TON REVETMENT, CLASS E  
80.000 TON SURFACING, DRIVEWAY, CLASS A CRUSHED STONE

---

Bid Turn-in Location: County Auditor

Letting Notice request sent by:  
Derek Snead  
[engineer@co.jones.ia.us](mailto:engineer@co.jones.ia.us)  
Jones County  
11-Oct-2017



**LOCAL AGENCY LETTING INFORMATION**

Lyon County -- L-(R4RP)--73-60

Proposal Guarantee \$ 25000.0

County Engineer's Office, Rock Rapids , IA, November 09, 2017, 8:55 AM

320-Bridge, REPLACE EXISTING TIMBER BRIDGE WITH A CCSB USING ROUND STEEL PIPE PILE FOUNDATIONS.

Contact # 712-472-8230 FAX # 712-472-3993

222.000	LF	CONCRETE OPEN RAILING, TL-4
1.000	LS	CONSTRUCTION SURVEY
1148.000	CY	EMBANKMENT-IN-PLACE
613.000	SY	ENGINEERING FABRIC
626.000	CY	EXCAVATION, CLASS 10, CHANNEL
24.000	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
121.000	CY	EXCAVATION, CLASS 20
95.000	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
372.000	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
1.000	LS	MOBILIZATION
1.000		EACH MOBILIZATIONS, EMERGENCY EROSION CONTROL
1.000		EACH MOBILIZATIONS, EROSION CONTROL
0.600		ACRE MULCHING
4.000		EACH OBJECT MARKER, TYPE 3
255.000	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
450.000	LF	PILES, STEEL PIPE, 12 IN.
900.000	LF	PILES, STEEL PIPE, 16 IN. (P10L TYPE 1)
56543.000	LB	REINFORCING STEEL
1.000	LS	REMOVAL OF EXISTING BRIDGE
264.000	TON	REVTMENT, CLASS E
2.000		EACH SAFETY CLOSURE
0.300		ACRE SEEDING AND FERTILIZING (RURAL)
360.000	LF	SILT FENCE
12.000	LF	SILT FENCE FOR DITCH CHECKS
0.300		ACRE STABILIZING CROP - SEEDING AND FERTILIZING
227.600	CY	STRUCTURAL CONCRETE (BRIDGE)
162.000	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
1.000	LS	TRAFFIC CONTROL

---

Bid Turn-in Location: County Engineer

Letting Notice request sent by:

Laura Sievers

[lsievers@co.lyon.ia.us](mailto:lsievers@co.lyon.ia.us)

Lyon County

11-Oct-2017

**LOCAL AGENCY LETTING INFORMATION**

Lyon County -- L-(4R)--73-60

Proposal Guarantee \$ 25000.0

County Engineer's Office, Rock Rapids , IA, November 09, 2017, 8:55 AM

320-Bridges, REPLACE EXISTING TIMBER BRIDGE WITH A CCSB USING H PILE FOUNDATIONS.

Contact # 712-472-8230 FAX # 712-472-3993

288.000	LF	CONCRETE ENCASEMENT OF STEEL H PILES, HP 10 X 42 (P10L TYPE 3)
222.000	LF	CONCRETE OPEN RAILING, TL-4
1.000	LS	CONSTRUCTION SURVEY
1148.000	CY	EMBANKMENT-IN-PLACE
613.000	SY	ENGINEERING FABRIC
626.000	CY	EXCAVATION, CLASS 10, CHANNEL
24.000	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
121.000	CY	EXCAVATION, CLASS 20
95.000	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
372.000	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
1.000	LS	MOBILIZATION
1.000		EACH MOBILIZATIONS, EMERGENCY EROSION CONTROL
1.000		EACH MOBILIZATIONS, EROSION CONTROL
0.600		ACRE MULCHING
4.000		EACH OBJECT MARKER, TYPE 3
255.000	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
1530.000	LF	PILES, STEEL, HP 10 X 42
56543.000	LB	REINFORCING STEEL
1.000	LS	REMOVAL OF EXISTING BRIDGE
264.000	TON	REVTMENT, CLASS E
2.000		EACH SAFETY CLOSURE
0.300		ACRE SEEDING AND FERTILIZING (RURAL)
360.000	LF	SILT FENCE
12.000	LF	SILT FENCE FOR DITCH CHECKS
0.300		ACRE STABILIZING CROP - SEEDING AND FERTILIZING
227.600	CY	STRUCTURAL CONCRETE (BRIDGE)
162.000	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
1.000	LS	TRAFFIC CONTROL

---

Bid Turn-in Location: County Engineer

Letting Notice request sent by:

Laura Sievers

[lsievers@co.lyon.ia.us](mailto:lsievers@co.lyon.ia.us)

Lyon County

11-Oct-2017