

LOCAL AGENCY LETTING INFORMATION

Adair County -- LFM-LRCBN20J--7X-01

Proposal Guarantee \$ 25000.0

County Engineer's Office, Greenfield , IA, March 12, 2018, 9:55 AM

RCB Culvert Replacement, Replacement of existing rcb culvert located approx. 140 ft. east of Hwy 25 and 130th St. intersection.

Contact # 641-743-6111 FAX # 641-743-2003

2.000	EACH APRONS, METAL, 18 IN. DIA.
44.000	LF CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
12293.000	CY EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED
1282.000	CY EXCAVATION, CLASS 10, ROADWAY AND BORROW
1704.000	CY EXCAVATION, CLASS 20
251.000	CY FLOODED BACKFILL
128.000	CY GRANULAR MATERIAL FOR BLANKET AND SUBDRAIN
641.000	CY GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
1.000	LS MOBILIZATION
1.000	EACH MOBILIZATIONS, EMERGENCY EROSION CONTROL
1.000	EACH MOBILIZATIONS, EROSION CONTROL
1.500	ACRE MULCHING
450.000	LF PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
20690.000	LB REINFORCING STEEL
1.000	LS REMOVAL OF EXISTING STRUCTURES
289.000	LF REMOVAL OF FENCE, BARBED WIRE
108.000	TON REVETMENT, CLASS D
2.000	EACH SAFETY CLOSURE
1.500	ACRE SEEDING AND FERTILIZING (RURAL)
144.000	CY STRUCTURAL CONCRETE (RCB CULVERT)
1.000	EACH TEMPORARY STREAM DIVERSION
2503.000	CY TOPSOIL, STRIP, SALVAGE AND SPREAD
1.000	LS TRAFFIC CONTROL

Bid Turn-in Location: County Engineer

Letting Notice request sent by:

Nick Kauffman

n_kauffman@windstream.net

Adair County

20-Feb-2018

