

**LOCAL AGENCY LETTING INFORMATION**

**CONTENTS**

<b>DATE ADDED</b>	<b>COUNTY/CITY</b>	<b>LETTING DATE</b>	<b>PAGE NUMBER</b>
August 21, 2019	Woodbury	September 10, 2019	2
September 4, 2019	Woodbury	September 17, 2019	3
August 29, 2019	Warren	September 27, 2019	4
August 30, 2019	Cerro Gordo	October 1, 2019	6



### BULLETIN REPORTING FORM

County:	<u>Woodbury County</u>	Project No.:	<u>LFM-CO97(D50)--73-97</u>
Proposal Guarantee:	<u>\$100,000.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>9/10/2019</u>	Time of Letting:	<u>04:30 PM</u>
Bid Turn-In Location:	<u>Office of Public Bidder Woodbury County Board of Supervisors</u>	Type of Project:	<u>Grading</u>
Contact Phone No.:	<u>712-279-6484</u>	Contact FAX No.:	<u>712-873-3235</u>

Specific Description of Project:

- **7 miles of grading with drainage structures**

QUANTITY	UNIT	DESCRIPTION
28	ACRE	CLEARING AND GRUBBING
537879	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
27993	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
11800	TON	GRANULAR SURFACING ON ROAD, CRUSHED CONCRETE
1	LS	REMOVAL OF EXISTING STRUCTURES
4414	CY	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT
2	EACH	APRONS, CONCRETE, 24 IN. DIA.
1	EACH	APRONS, CONCRETE, 30 IN. DIA.
1	EACH	APRONS, CONCRETE, 36 IN. DIA.
4	EACH	APRONS, CONCRETE, 48 IN. DIA.
1	EACH	APRONS, CONCRETE, 60 IN. DIA.
340	LF	CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.
130	LF	CULVERT, CONCRETE ROADWAY PIPE, 30 IN. DIA.
296	LF	CULVERT, CONCRETE ROADWAY PIPE, 36 IN. DIA.
482	LF	CULVERT, CONCRETE ROADWAY PIPE, 48 IN. DIA.
114	LF	CULVERT, CONCRETE ROADWAY PIPE, 60 IN. DIA.
2	EACH	APRONS, METAL, 24 IN. DIA.
2	EACH	APRONS, METAL, 36 IN. DIA.
16	EACH	APRONS, SAFETY SLOPE, 24 IN. DIA.
538	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.
120	LF	CULVERT, CORRUGATED METAL ROADWAY PIPE, 36 IN. DIA.
176	TON	EROSION STONE
3150.15	SY	REMOVAL OF PAVEMENT
6	EACH	SAFETY CLOSURE
237	EACH	FIELD FENCE BRACE PANELS
24121	LF	REMOVAL AND REINSTALLATION OF FENCE, BARBED WIRE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
7	EACH	Drop Inlets TEE Section
45.63	ACRE	MULCHING
45.63	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
26969	LF	SILT FENCE
3178	LF	SILT FENCE FOR DITCH CHECKS
1	EACH	MOBILIZATIONS, EROSION CONTROL
1	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL

Date: 8/21/2019 Local Agency Official: Mark Nahra, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



### BULLETIN REPORTING FORM

County:	<u>Woodbury County</u>	Project No.:	<u>Woodbury County PCC Patching</u>
Proposal Guarantee:	<u>\$6,250.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>9/17/2019</u>	Time of Letting:	<u>04:30 PM</u>
Bid Turn-In Location:	<u>Office of Public Bidder Woodbury County Board of Supervisors</u>	Type of Project:	<u>PCC Paving</u>
Contact Phone No.:	<u>712-898-1898</u>	Contact FAX No.:	<u>712-873-3235</u>

Specific Description of Project:

PCC Patching 8" various locations in Woodbury County

QUANTITY	UNIT	DESCRIPTION
4	LF	CURB, DOWELLED P.C. CONCRETE, AS PER PLAN
43	EACH	PATCHES BY COUNT (REPAIR)
508.08	SY	PATCHES, FULL-DEPTH REPAIR
1	LS	MOBILIZATION
1	LS	TRAFFIC CONTROL

Date: 9/4/2019 Local Agency Official: Mark Nahra, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



## BULLETIN REPORTING FORM

County:	Warren County	Project No.:	LFM-R63(S)--7X-91
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	9/27/2019	Time of Letting:	02:00 PM
Bid Turn-In Location:	County Engineer	Type of Project:	Landslide Stabilization
Contact Phone No.:	515-961-1050	Contact FAX No.:	515-961-1053

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
0.6	ACRE	CLEARING AND GRUBBING
5878	CY	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED
5813	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
293.3	TON	MODIFIED SUBBASE
111.7	TON	GRANULAR SHOULDERS, TYPE B
731.6	SY	STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 8 IN.
1	LS	REMOVAL OF EXISTING STRUCTURES
237	CY	FLOODED BACKFILL
546	CY	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT
2	EACH	APRONS, CONCRETE, 48 IN. DIA.
104	LF	CULVERT, CONCRETE ROADWAY PIPE, 48 IN. DIA.
1314	LF	SUBDRAIN, STANDARD, PERFORATED, 6 IN., AS PER PLAN
4	EACH	SUBDRAIN OUTLET, DR-305
4	EACH	SUBDRAIN OUTLET, DR-306
175	SY	ENGINEERING FABRIC
165.4	TON	REVTMENT, CLASS E
731.6	SY	REMOVAL OF PAVEMENT
2	EACH	SAFETY CLOSURE
1	LS	CONSTRUCTION SURVEY
1	LS	TRAFFIC CONTROL
10	CDAY	PORTABLE DYNAMIC MESSAGE SIGN (PDMS)
1	LS	MOBILIZATION
1.1	ACRE	MULCHING
1.1	ACRE	SEEDING AND FERTILIZING (RURAL)
700	LF	SILT FENCE
700	LF	REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS
70	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
1880	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
1880	LF	REMOVAL OF PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE
2	EACH	MOBILIZATIONS, EROSION CONTROL

1	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL
---	------	--

Date: 8/29/2019 Local Agency Official: David Carroll, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



### BULLETIN REPORTING FORM

County: Cerro Gordo County Project No.: L-H35C17(20)-7X-17  
 Proposal Guarantee: \$12,500.00 DBE or TSB Goal: \_\_\_\_\_  
 Date of Letting: 10/1/2019 Time of Letting: 10:15 AM  
 Bid Turn-In Location: County Auditor Type of Project: RCB CULVERT REPLACEMENT - SINGLE BOX  
 Contact Phone No.: 641-424-9037 Contact FAX No.: 641-424-9058

Specific Description of Project:

REMOVE QUAD 6.5x6.5x32' LWB WITH 12' APRONS. PLACE TWIN 12x7x32 RCB WITH 12' APRONS WITH ASSOCIATED SHAPING AND EROSION CONTROL.

QUANTITY	UNIT	DESCRIPTION
1	ACRE	CLEARING AND GRUBBING
18	CY	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED
86	TON	GRANULAR SURFACING ON ROAD, CLASS B CRUSHED STONE
1	LS	REMOVAL OF EXISTING BRIDGE
392	CY	EXCAVATION, CLASS 20
125	TON	FOUNDATION TREATMENT MATERIAL
64	LF	PRECAST CONCRETE BOX CULVERT, 12 FT. X 7 FT.
4	EACH	PRECAST CONCRETE BOX CULVERT STRAIGHT END SECTION, 12 FT. X 7 FT.
1	EACH	TEMPORARY STREAM DIVERSION
13.7	CY	FLOWABLE MORTAR
164	SY	ENGINEERING FABRIC
216	TON	REVTMENT, CLASS E
2	EACH	SAFETY CLOSURE
1	LS	CONSTRUCTION SURVEY
1	LS	MOBILIZATION
0.3	ACRE	MULCHING
0.3	ACRE	SEEDING AND FERTILIZING (RURAL)
27	LF	FLOATING SILT CURTAIN (HANGING)
200	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.
1	EACH	MOBILIZATIONS, EROSION CONTROL

Date: 8/29/2019 Local Agency Official: Brandon Billings, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us