

**LOCAL AGENCY LETTING INFORMATION**

**CONTENTS**

<b>DATE ADDED</b>	<b>COUNTY/CITY</b>	<b>LETTING DATE</b>	<b>PAGE NUMBER</b>
April 13, 2021	Harrison	May 13, 2021	2
April 13, 2021	Harrison	May 13, 2021	3
April 13, 2021	Harrison	May 13, 2021	4
April 21, 2021	Buena Vista	May 13, 2021	5
April 23, 2021	Scott	May 14, 2021	7
May 5, 2021	Iowa	May 14, 2021	8
April 30, 2021	Scott	May 17, 2021	9
May 7, 2021	Linn	May 25, 2021	10
May 5, 2021	Adair	June 7, 2021	11
May 12, 2021	Bremer	June 7, 2021	14
May 11, 2021	Jones	June 8, 2021	15



**BULLETIN REPORTING FORM**

County:	<u>Harrison County</u>	Project No.:	<u>L-S8411e5--73-43</u>
Proposal Guarantee:	<u>\$7,000.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>5/13/2021</u>	Time of Letting:	<u>10:00 AM</u>
Bid Turn-In Location:	<u>County Auditor</u>	Type of Project:	<u>Otta Seal Coat</u>
Contact Phone No.:	<u>712-644-3140</u>	Contact FAX No.:	<u>712-644-3412</u>

Specific Description of Project:

Heavy duty bituminous seal coat using HFMS-2s binder and 3/4" limestone aggregate. Double Application.

Tied With: L-S8310e3--73-43, L-S8329e5--73-43

QUANTITY	UNIT	DESCRIPTION
15970.8	GAL	BINDER BITUMEN
1	LS	TRAFFIC CONTROL
6	EACH	FLAGGERS
1	LS	MOBILIZATION
399.2	TON	AGGREGATE, COVER 3/4" (APPLY ONLY) BASE LAYER
399.2	TON	AGGREGATE, COVER 3/4" (APPLY ONLY) SURFACE LAYER

Date: 4/13/2021 Local Agency Official: Steve Struble, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



**BULLETIN REPORTING FORM**

County:	<u>Harrison County</u>	Project No.:	<u>L-S8329e5--73-43</u>
Proposal Guarantee:	<u>\$3,000.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>5/13/2021</u>	Time of Letting:	<u>10:00 AM</u>
Bid Turn-In Location:	<u>County Auditor</u>	Type of Project:	<u>Otta Seal Coat</u>
Contact Phone No.:	<u>712-644-3140</u>	Contact FAX No.:	<u>712-644-3412</u>

Specific Description of Project:

Heavy duty bituminous seal coat using HFMS-2s binder and 3/4" limestone aggregate. Double Application.

Tied With: L-S8310e3--73-43, L-S8411e5--73-43

QUANTITY	UNIT	DESCRIPTION
7963.1	GAL	BINDER BITUMEN
1	LS	TRAFFIC CONTROL
4	EACH	FLAGGERS
1	LS	MOBILIZATION
196.5	TON	AGGREGATE, COVER 3/4" (APPLE ONLY) BASE LAYER
196.5	TON	AGGREGATE, COVER 3/4" (APPLY ONLY) SURFACE LAYER

Date: 4/13/2021 Local Agency Official: Steve Struble, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



**BULLETIN REPORTING FORM**

County:	<u>Harrison County</u>	Project No.:	<u>L-S8310e3--73-43</u>
Proposal Guarantee:	<u>\$2,500.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>5/13/2021</u>	Time of Letting:	<u>10:00 AM</u>
Bid Turn-In Location:	<u>County Auditor</u>	Type of Project:	<u>Otta Seal Coat</u>
Contact Phone No.:	<u>712-644-3140</u>	Contact FAX No.:	<u>712-644-3412</u>

Specific Description of Project:

Heavy duty bituminous seal coat using HFMS-2s binder and 3/4" limestone aggregate. Double Application.

Tied With: L-S8411e5--73-43, L-S8329e5--73-43

QUANTITY	UNIT	DESCRIPTION
6711.9	GAL	BINDER BITUMEN
1	LS	TRAFFIC CONTROL
4	EACH	FLAGGERS
1	LS	MOBILIZATION
163.6	TON	AGGREGATE, COVER 3/4 IN. (APPLY ONLY) BASE LAYER
163.6	TON	AGGREGATE, COVER 3/4 IN. (APPLY ONLY) SURFACE LAYER

Date: 4/13/2021 Local Agency Official: Steve Struble, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



## BULLETIN REPORTING FORM

County:	Buena Vista County	Project No.:	LFM-B-1703--7X-11
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	5/13/2021	Time of Letting:	03:00 PM
Bid Turn-In Location:	County Auditor	Type of Project:	Box Culverts
Contact Phone No.:	712-749-2540	Contact FAX No.:	712-749-2704

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
0.2	ACRE	CLEARING AND GRUBBING
32	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
20	CY	EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS
225	CY	EXCAVATION, CLASS 10, CHANNEL
28	TON	GRANULAR MATERIAL
544	SY	GRANULAR SUBBASE
4.45	STA	SHOULDER CONSTRUCTION, EARTH
37	TON	HOT MIX ASPHALT MIXTURE, WEDGE, LEVELING OR STRENGTHENING COURSE
2	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	REMOVAL OF EXISTING BRIDGE
160.7	CY	GRANULAR BACKFILL
212	CY	EXCAVATION, CLASS 20
56	LF	PRECAST CONCRETE BOX CULVERT,
2	EACH	PRECAST CONCRETE BOX CULVERT STRAIGHT END SECTION,
1	EACH	TEMPORARY STREAM DIVERSION
490	TON	REVETMENT, CLASS E
544	SY	REMOVAL OF PAVEMENT
1	LS	CONSTRUCTION SURVEY
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
0.6	ACRE	MULCHING
0.6	ACRE	SEEDING AND FERTILIZING (RURAL)
300	LF	SILT FENCE FOR DITCH CHECKS
300	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.
1	EACH	MOBILIZATIONS, EROSION CONTROL

Date: 4/21/2021 Local Agency Official: Bret Wilkinson, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at

DOT.Contracts@iowadot.us



### BULLETIN REPORTING FORM

County:	<u>Scott County</u>	Project No.:	<u>L-520--73-82</u>
Proposal Guarantee:	<u>\$25,000.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>5/14/2021</u>	Time of Letting:	<u>10:00 AM</u>
Bid Turn-In Location:	<u>950 E Blackhawk Trail, Eldridge, IA 52748</u>	Type of Project:	<u>Bridge or Culvert</u>
Contact Phone No.:	<u>563-326-8640</u>	Contact FAX No.:	<u></u>

Specific Description of Project:

Twin 12' x 7' x 58' RCB Culvert Replacement Project On 60th Avenue, Sec 7- T78N - R2E

QUANTITY	UNIT	DESCRIPTION
232	CY	Structural Concrete
34246	LB	Reinforcing Steel
820	CY	Excavation - Class 10
1055	CY	Excavation - Class 20
630	CY	EMBANKMENT-IN-PLACE
1650	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
400	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE

Date: 4/23/2021 Local Agency Official: Angela Kersten, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



**BULLETIN REPORTING FORM**

County: Iowa County Project No.: LFM-P4016--7X-48  
 Proposal Guarantee: \$1.00 DBE or TSB Goal: \_\_\_\_\_  
 Date of Letting: 5/14/2021 Time of Letting: 09:30 AM  
 Bid Turn-In Location: County Engineer Type of Project: Materials & Delivery Only of Precast Box Culvert  
 Contact Phone No.: 319-642-3721 Contact FAX No.: 319-642-7046

Specific Description of Project:

Materials and Delivery of a 14'x10'x36' precast concrete box culvert and end sections.

QUANTITY	UNIT	DESCRIPTION
2	EACH	Precast Concrete Box Culvert Straight End Section 14 ft. x 10 ft.
36	LF	Precast Box Culvert 14ft. x 10 ft.

Date: 5/4/2021 Local Agency Official: Nicholas Amelon, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us





**BULLETIN REPORTING FORM**

County:	<u>Scott County</u>	Project No.:	<u>2021 Crack Seal RFQ</u>
Proposal Guarantee:	<u>\$0.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>5/17/2021</u>	Time of Letting:	<u>09:00 AM</u>
Bid Turn-In Location:	<u>950 E. Blackhawk Trail, Eldridge, IA 52748</u>	Type of Project:	<u>Surfacing</u>
Contact Phone No.:	<u>563-326-8640</u>	Contact FAX No.:	<u>563-328-4173</u>

Specific Description of Project:

HMA Crack Sealing throughout Scott County

QUANTITY	UNIT	DESCRIPTION
30.43	MILE	CRACK AND JOINT CLEANING AND SEALING (HMA SURFACES)

Date: 4/30/2021 Local Agency Official: Angela Kersten, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



### BULLETIN REPORTING FORM

County:	<u>Linn County</u>	Project No.:	<u>M-PCC BRIDGE REHAB(21)</u>
Proposal Guarantee:	<u>\$12,500.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>5/25/2021</u>	Time of Letting:	<u>11:00 AM</u>
Bid Turn-In Location:	<u>County Auditor</u>	Type of Project:	<u>Bridge Repair</u>
Contact Phone No.:	<u>319-892-6400</u>	Contact FAX No.:	<u>319-892-6419</u>

Specific Description of Project:

Misc Bridge Repair on Bridge 641 on Mount Vernon Road and on Bridge 1699 on Springville Road.

QUANTITY	UNIT	DESCRIPTION
190	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
30	CY	EXCAVATION, CLASS 10, CHANNEL
105	CY	STRUCTURAL CONCRETE (MISCELLANEOUS)
6694	LB	REINFORCING STEEL, EPOXY COATED
1575	SF	CONCRETE REPAIR
8	CY	FLOWABLE MORTAR
370	TON	REVTMENT, CLASS D
1	LS	TRAFFIC CONTROL
10	EACH	FLAGGERS
1	LS	MOBILIZATION

Date: 5/7/2021 Local Agency Official: Brad Ketels, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



## BULLETIN REPORTING FORM

County:	Adair County	Project No.:	LFM-G61--7X-01/15
Proposal Guarantee:	\$50,000.00	DBE or TSB Goal:	
Date of Letting:	6/7/2021	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Grading
Contact Phone No.:	641-743-6111	Contact FAX No.:	

### Specific Description of Project:

This project includes the major grading of Adair / Cass County Highway G-61 from 0.2 miles west of the Adair / Cass County line to 0.2 miles east of the Adair / Cass County line. This project includes a 6' x 6' RCB Culvert Replacement, multiple roadway and entrance pipe culverts, longitudinal subdrains, side road and driveway regrading, temporary and permanent erosion control devices, and granular surfacing.

QUANTITY	UNIT	DESCRIPTION
0.1	ACRE	CLEARING AND GRUBBING
23065.5	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
5	CY	EXCAVATION, CLASS 10, WASTE
180	CY	EXCAVATION, CLASS 10, CHANNEL
6940	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
197	CY	GRANULAR MATERIAL FOR BLANKET AND SUBDRAIN
3833	SY	SUBGRADE STABILIZATION MATERIAL, POLYMER GRID
650	CY	MODIFIED SUBBASE
417	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
240	TON	SURFACING, DRIVEWAY, CLASS A CRUSHED STONE
0.75	LS	REMOVAL OF EXISTING STRUCTURES
321.4	CY	GRANULAR BACKFILL
905	CY	EXCAVATION, CLASS 20
71.5	CY	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT
186.5	CY	STRUCTURAL CONCRETE (RCB CULVERT)
26166	LB	REINFORCING STEEL
1	EACH	APRONS, CONCRETE, 18 IN. DIA.
1	EACH	APRONS, CONCRETE, 48 IN. DIA.
59	LF	CULVERT, CONCRETE ENTRANCE PIPE, 18 IN. DIA.
27	LF	CULVERT, CONCRETE ENTRANCE PIPE, 48 IN. DIA.
1	EACH	APRONS, METAL, 18 IN. DIA.
1	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
1	EACH	TEMPORARY STREAM DIVERSION
2600	LF	SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.
1	EACH	SUBDRAIN OUTLET, DR-305
10	EACH	SUBDRAIN OUTLET, DR-306

505	TON	REVETMENT, CLASS D
2940	LF	REMOVAL OF FENCE,
0.5	LS	CONSTRUCTION SURVEY
1	EACH	SAFETY CLOSURE
0.5	LS	TRAFFIC CONTROL
0.5	LS	MOBILIZATION
4.4	ACRE	MULCHING
1	ACRE	NATIVE GRASS SEEDING
4.4	ACRE	SEEDING AND FERTILIZING (RURAL)
4.4	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
119	SQ	TURF REINFORCEMENT MAT, TYPE 4
7115	LF	SILT FENCE
3557	LF	REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS
712	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
60	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.
60	LF	REMOVAL OF PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE
1	EACH	MOBILIZATIONS, EROSION CONTROL
1	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL
1	ACRE	CLEARING AND GRUBBING
23065.5	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
5	CY	EXCAVATION, CLASS 10, WASTE
1	CY	EXCAVATION, CLASS 10, CHANNEL
5937	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
1	CY	GRANULAR MATERIAL FOR BLANKET AND SUBDRAIN
3825	SY	SUBGRADE STABILIZATION MATERIAL, POLYMER GRID
648	CY	MODIFIED SUBBASE
70	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
340	TON	SURFACING, DRIVEWAY, CLASS A CRUSHED STONE
0.25	LS	REMOVAL OF EXISTING STRUCTURES
64.8	CY	GRANULAR BACKFILL
1	CY	EXCAVATION, CLASS 20
71.5	CY	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT
1	CY	STRUCTURAL CONCRETE (RCB CULVERT)
1	LB	REINFORCING STEEL
1	EACH	APRONS, CONCRETE, 18 IN. DIA.
1	EACH	APRONS, CONCRETE, 48 IN. DIA.
59	LF	CULVERT, CONCRETE ENTRANCE PIPE, 18 IN. DIA.
27	LF	CULVERT, CONCRETE ROADWAY PIPE, 48 IN. DIA.
4	EACH	APRONS, METAL, 18 IN. DIA.
120	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
1	EACH	TEMPORARY STREAM DIVERSION
2592	LF	SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.
1	EACH	SUBDRAIN OUTLET, DR-305
10	EACH	SUBDRAIN OUTLET, DR-306
651	TON	REVETMENT, CLASS D
306	LF	REMOVAL OF FENCE,

0.5	LS	CONSTRUCTION SURVEY
1	EACH	SAFETY CLOSURE
0.5	LS	TRAFFIC CONTROL
0.5	LS	MOBILIZATION
3.5	ACRE	MULCHING
3.5	ACRE	NATIVE GRASS SEEDING
0.1	ACRE	SEEDING AND FERTILIZING (RURAL)
3.5	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
0.1	SQ	TURF REINFORCEMENT MAT, TYPE 4
7046	LF	SILT FENCE
3523	LF	REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS
705	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
90	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.
90	LF	REMOVAL OF PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE
1	EACH	MOBILIZATIONS, EROSION CONTROL
1	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL

Date: 5/5/2021 Local Agency Official: Nick Kauffman, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



**BULLETIN REPORTING FORM**

County: Bremer County Project No.: L-L-10-122--73-09  
 Proposal Guarantee: \$37,500.00 DBE or TSB Goal: \_\_\_\_\_  
 Date of Letting: 6/7/2021 Time of Letting: 10:00 AM  
 Bid Turn-In Location: County Auditor Type of Project: Full depth reclamation and 2 inch mill and fill  
 Contact Phone No.: 319-352-4302 Contact FAX No.: 319-352-4326

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
22678.3	SY	FULL DEPTH RECLAMATION
456	TON	GRANULAR SHOULDERS, TYPE B
1.5	MILE	CLEANING AND PREPARATION OF BASE
4926	SY	PAVEMENT SCARIFICATION
3264.28	TON	HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX
3870.28	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
169.46	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	HOT MIX ASPHALT PAVEMENT SAMPLES
84	TON	ASPHALT STABILIZING AGENT (FOAMED ASPHALT)
1	LS	TRAFFIC CONTROL
6	EACH	FLAGGERS
1	LS	MOBILIZATION

Date: 5/12/2021 Local Agency Official: Landon Moore, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



**BULLETIN REPORTING FORM**

County:	<u>Jones County</u>	Project No.:	<u>M-0422</u>
Proposal Guarantee:	<u>\$25,000.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>6/8/2021</u>	Time of Letting:	<u>09:30 AM</u>
Bid Turn-In Location:	<u>County Auditor</u>	Type of Project:	<u>Full Depth PCC Patches</u>
Contact Phone No.:	<u>319-462-3785</u>	Contact FAX No.:	<u>319-462-3903</u>

Specific Description of Project:

Full depth PCC patches with subbase on two county routes: E17 from from state Hwy 38 to state Hwy136, E29 from state Hwy 38 to State Hwy 136.

QUANTITY	UNIT	DESCRIPTION
1	LS	TRAFFIC CONTROL
50	EACH	FLAGGERS
25	EACH	PILOT CARS
1923.5	SY	PATCHES, FULL-DEPTH FINISH, BY AREA
3455.9	SY	PATCHES, FULL-DEPTH FINISH, BY AREA (50 FEET OR GREATER IN LENGTH)
130	EACH	PATCHES, FULL-DEPTH FINISH, BY COUNT
5379	SY	SUBBASE (PATCHES)
1	LS	MOBILIZATION

Date: 5/11/2021 Local Agency Official: Derek Snead, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us