# STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, & CONCRETE BOX, ARCH & CIRCULAR CULVERTS

October 16, 2007 Supersedes April 17, 2007

Sections 2403, 2404, 2405, 2406, 2412, & 2415

Matls. IM 204 Appendix H (Metric) Units

MATERIAL OR CONSTRUCTION ITEM	TESTS		METHOD OF ACCEPTANCE &		(	QUALITY CONT	ROL			IN	DEPENDENT & VERIFIC <i>I</i>	ASSURANC	E		REMARKS					
II LIVI						.ivi	REI	ATED IMS	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPEC	TION									•										
Aggregate-Fine (4110)		AS	209																	
Aggregate-Coarse (4115)		AS	209																	
Granular Backfill (4133)		AS	209																	
Portland Cement (4101)	Quality	AS	401																	
Fly Ash (4108)	Quality	AS	491.17																	
Mixing Water (4102)	Quality									RCE	1/project	1 L	CTRL	731	Not required for potable water from Municipal Supply					
GGBFS (Ground Granulated Blast Furnace Slag)	Quality	AS	491.14																	
Air Entraining Admixture	Quality	AS	403																	
Retarding Admixture	Quality	AS	403																	
Water reducing Admixture	Quality	AS	403																	
Curing Compound, White (4105)	Lab Tested		405						V	DME	1/batch	1 qt	CTRL							
Curing Compound, Clear (4105)		AS	405.07																	
AS-Approved Sour ASD-Approved Sh	AS-Approved Source Cert A-Type A Certification ASD-Approved Shop Drawing Cert C-Type C Certification 6&T-Sampling & Testing Cert D-Type D Certification														dependent Assurance rification					

# STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, & CONCRETE BOX, ARCH & CIRCULAR CULVERTS

October 16, 2007 Supersedes April 17, 2007

Sections 2403, 2404, 2405, 2406, 2412, & 2415

Matls. IM 204 Appendix H (Metric) Units

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE &		QU	ALITY CONT	ROL			II		ENT ASSURAI			REMARKS
112.00		RELATED IMS	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPEC	CTION				•	•	•		•	•			'	
Preformed Joint Sealer (4136)	Lab- Tested	AS 436.02 436.05												
Reinforcing Steel Bars (4151)	Quality	AS 451												
Steel Pile (4167)	Quality	467												
Concrete Pile (4166)	Quality	AS 570												
Timber Pile (4165)	Quality	Cert A AS 462												
Timber (4162) & Lumber (4163)		Treated-Cert A 462												
Concrete Anchors	Quality	AS 453.09												
Epoxy Grout	Quality	AS 491.11												
Concrete Sealer	Quality	AS 491.12												
Subdrain Pipe (4143)	Quality	AS 443, 448												
Neoprene Bearing Pads (4195)		AS 495.03												
Bronze Bearing Plates (4190.03)		ASD/Cert A												
AS-Approved Sour ASD-Approved Sh S&T-Sampling & T	op Drawing	C	ert C-Type C Certification DME-D ert D-Type D Certification CTRL-0											dependent Assurance rification

# STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, & CONCRETE BOX, ARCH & CIRCULAR CULVERTS

October 16, 2007 Supersedes April 17, 2007

Sections 2403, 2404, 2405, 2406, 2412, & 2415

Matls. IM 204 Appendix H (Metric) Units

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE &		QU	ALITY CONTF	ROL					T ASSURANC ATION S&T	E		REMARKS
II EW		RELATED IMS	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPT.	
SOURCE INSPEC	CTION													
Steel Masonry Plate (4152)		ASD/Cert A												
Precast Units (2407)	Quality	AS 570												
Anchor Bolts (lighting, signing, handrail) (4153)	Lab Tested	ASD												
Structural Steel (4152)	Quality	Cert A												Monitor Sample According to plans or other instructions
Aluminum Bridge Rail & Anchor Assembly		ASD												
Conduit (Electrical) (4185.10) Steel)		AS												
Conduit (Plastic) (4185.10)	Lab Tested							V	DME	1/size	1 m with coupling	C TRL		
Bentonite		Visual												
Flowable Mortar	Lab Tested	Approved 525, 375 Trial Mix												Tested by DME
AS-Approved Sour ASD-Approved Sh S&T-Sampling & T	op Drawing esting	Ce Ce	rt C-Type C rt D-Type D	Certification Certification Certification	tification DME-District Materials Engineer						-Independent Assurance Verification			

# STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, & CONCRETE BOX, ARCH & CIRCULAR CULVERTS

October 16, 2007 Supersedes April 17, 2007

Sections 2403, 2404, 2405, 2406, 2412, & 2415

Matls. IM 204 Appendix H (Metric) Units

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE &	EPTANCE		Ql	JALITY CONT	ROL			REMARKS					
HEIVI		REL	α ATED IMs	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
PLANT INSPECT	TION														
Aggregate- Fine (4110)	Gradation Deck	302, 306 336	CONTR	IM 528	IM 301	CONTR	800240	IA V	DME RCE/ CONTR	1/750 m <sup>3</sup> Sample & Test 1/deck/wk	IM 301 IM 301	DME RCE		May use System App.	
	Gradation All other			CONTR	IM 528	IM 301	CONTR	V		DME RCE/ CONTR	1/750 m <sup>3</sup> Sample 1/wk Test 1st day +20%	IM 301 IM 301	DME RCE		May use System App.
	Moisture		308, 528	CONTR	1/lot	1000 gm	CONTR								See IM 528 if Moisture Probe is used
	Sp. Gr.		307	CONTR	IM 528	1000 gm	CONTR								1 1000 10 4004
	Quality	AS	209					- -							
Aggregate- Coarse (4115)	Gradation Deck		302, 306 336	CONTR	IM 528	IM 301	CONTR	_	IA V	DME RCE/ CONTR	1/750 m <sup>3</sup> Sample & Test 1/deck/wk	IM 301 IM 301	DME RCE		May use System App.
	Gradation All other			CONTR	IM 528	IM 301	CONTR		IA V	DME RCE/ CONTR	1/750 m <sup>3</sup> Sample 1/wk Test 1 <sup>st</sup> day +20%k	IM 301 IM 301	DME RCE		May use System App.
	Moisture		308, 528	CONTR	1/lot	2000gm	CONTR	1			1207010				
	Sp. Gr.		307	CONTR	IM 528	2000gm	CONTR	1							
	Quality	AS	209						V	DME	1/750 m <sup>3</sup>	22 kg	CTRL		(1)
Portland Cement	w/c ratio		528	CONTR	1/pour		CONTR								
	Quality	AS	Cert D						V	DME	1/750 m <sup>3</sup>	7 kg	CTRL		(1)
AS-Approved Sou ASD-Approved Sh S&T-Sampling &	nop Drawing			Cert C-Type	A Certificati C Certificati D Certificati	on		RCE-Resider DME-District CTRL-Centra CONTR-Con	Materials E al Materials	Engineer	er/Project Engi	neer		IA-Indep V-Verific	endent Assurance ation

(1) These verification samples for concrete materials not required when mix quantity is less than 40 m<sup>3</sup>.

# STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, & CONCRETE BOX, ARCH & CIRCULAR CULVERTS

October 16, 2007 Supersedes April 17, 2007

Sections 2403, 2404, 2405, 2406, 2412, & 2415

Matls. IM 204 Appendix H (Metric) Units

MATERIAL OR CONSTRUCTION ITEM	TESTS		METHOD OF ACCEPTANCE &		QUA	ALITY CONTR	OL				INDEPENDENT & VERIFICA		E		REMARKS
II LIVI		RELATED IMS	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT		
PLANT INSPECT	ION														
Fly Ash	Quality	AS	Cert D		Ea Load			800240							
GGBFS(Ground Granulated Blast Furnace Slag)	Quality	AS	Cert D		Ea Load				V	DME	1/750 m <sup>3</sup>	7 kg	CTRL		
Air Entraining Admixture (4103)		AS	403						V	RCE	1/batch	0.5 L	CTRL		(1) Sample lots not
Retarding Admixture		AS	403						V	RCE	1/batch	0.5 L	CTRL		previously reported or as required by DME
Water Reducing Admixture (4103)		AS	403						V	RCE	1/batch	0.5 L	CTRL		
GRADE INSPECTION															
Plastic Concrete	Air Content		316, 327					M145*	IA V	DME RCE	1/750 m <sup>3</sup> 1/25 m <sup>3</sup>		DME RCE		DME may adjust
	Slump		317, 327						IA V	DME RCE	1/750m <sup>3</sup> 1/25 m <sup>3</sup>		Witness Only RCE		DME may adjust
	Beams		316, 327, 328							RCE	2/placement		RCE		If required per 2403.18 & 2403.19
	Cylinders									DME	3/project		DME		Primary Projects Only (Information only)
AS-Approved Sou ASD-Approved Sh S&T-Sampling & T	op Drawing		С	ert C-Type	A Certification C Certification D Certification	n	•	RCE-Reside DME-Distric CTRL-Centro CONTR-Co	ct Materials ral Material	Engineer	eer/Project Er	ngineer	•	IA-Indep V-Verific	endent Assurance ation

(1) These verification samples for concrete materials not required when mix quantity is less than 40 m<sup>3</sup>.

<sup>\*</sup>Available from the Office of Construction.

# STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, & CONCRETE BOX, ARCH & CIRCULAR CULVERTS

October 16, 2007 Supersedes April 17, 2007

Sections 2403, 2404, 2405, 2406, 2412, & 2415

Matls. IM 204 Appendix H (Metric) Units

MATERIAL OR CONSTRUCTION ITEM	TESTS		HOD OF EPTANCE &	==::=:::==					REMARKS									
TI E.W.					RELA	ATED IMs	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
GRADE INSPECTION														-				
Reinforcing Steel (4151)	Quality	AS	Cert A		Each Shipment			Field Book	V	DME	IM 451	2 m	CTRL					
Reinforcing Steel Epoxy Coated (4151)	Quality	AS	Cert A		Each Shipment			Field Book	V	DME	1 bar	2 m	CTRL		Will be acceptance tested for coating			
Steel Pile (4167)	Quality	AS	Cert A		Each Heat			Field Book	V	DME	IM 467		CTRL					
Timber Pile (4165)	Quality	AS	462 Cert A						V	DME	IM 462		CRTL		No grade requirement Charge numbers on butt end.			
Anchor Bolts (lighting, signing, handrail)	Lab Tested	ASD							V	DME	1/project	1 bolt w/nut & washer	CTRL		Sample only if not source inspected			
Steel Masonry Plates (4152)		ASD	Cert A		Each Shipment			Field Book							Approved by Materials Department			
Bronze Bearing Plates (4190.03)	Lab Tested								V	DME	1/project	1 only	CTRL		Sample only if not source inspected			
Neoprene Bearing Pads (4195)		AS	495.03		Each Shipment			820905										
Alum. Bridge Rail & Anchor Assembly		ASD			Each Shipment			Field Book							Approved By Materials Dept.			
Drains (Std Steel Pipe)(as per plan)	Dimensions Galvanized	ASD	Visual 332						V	DME	1/project		DME	Test Report				
AS-Approved Sou ASD-Approved Sh S&T-Sampling & 1	(	Cert C-Type C Certification I Cert D-Type D Certification (				RCE-Resident Construction Engineer/Project Engineer IA-Indep DME-District Materials Engineer V-Verific CTRL-Central Materials Office CONTR-Contractor							endent Assurance ation					

# STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, & CONCRETE BOX, ARCH & CIRCULAR CULVERTS

October 16, 2007 Supersedes April 17, 2007

Sections 2403, 2404, 2405, 2406, 2412, & 2415

Matls. IM 204 Appendix H (Metric) Units

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE		QUALITY CONTROL						INDEPENDENT ASSURANCE & VERIFICATION S&T						
		RELATED IMS	<b>I</b> Is	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT		
GRADE INSPEC	TION														-	
Timber (4162) & Lumber (4163)	Quality	AS Treated-Cert A	462		Each Shipment											
Subdrain Pipe (4143)	Quality	AS Cert D 443	3, 448		Each Shipment											
Flowable Mortar (2506) ▼	Flow Test		375	RCE	As needed for Project Control		RCE	830211							Mix Design approval by DME	
Bentonite	Flow Test	Visual	375				RCE									
Smoothness (2317)	Profilometer	Cert. Test Rpt.	341	CONTR	Each Project	Each Wheelpath	CONTR	821301	V		10%		DME			
AS-Approved Sou ASD-Approved Sh S&T-Sampling & T	on on on		RCE-Resident Construction Engineer/Project Engineer  DME-District Materials Engineer  CTRL-Central Materials Office  CONTR-Contractor							endent Assurance eation						