Sampling and Testing Guide-Minimum Frequency

April 15, 2008 Supersedes October 16, 2007

CONCRETE BRIDGE FLOOR REPAIR & OVERLAY & SURFACING Section 2413

Matls. IM 204 Appendix M

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF TESTS ACCEPTANCE & RELATED IMS	QUALITY CONTROL						REMARKS					
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTIO	Ň									•	•			
Aggregates-Fine (4110)		AS 209												
Aggregates-Coarse (4115)		AS 209												
Portland Cement (4101)	Quality	AS 401												
Mixing Water (4102)	Quality	Lab Tested						V	RCE	1/source	1 qt.	CTRL		Not needed for potable Municipal Water
Air Entraining Admixture (4103)	Quality	AS 403												
Water Reducing Admixture (4103)	Quality	AS 403												
Retarding Admixture (4103)		AS 403												
Curing Compound (4105)	Lab Tested	405						V	DME	1/batch	1 pt	CTRL		Sample lots not previously reported
PLANT INSPECTION														
Aggregate-Fine (4110)		AS Cert A												
Aggregate-Coarse (4115)	Quality	AS Cert A						V	DME	1/project	50 lb	CTRL		DME may adjust frequency
Portland Cement (4101)	Quality	AS Cert D						V	DME	1/project	15 lb	CTRL		
Air Entraining Admixture (4103)		AS 403						V	RCE	Each batch	1 pt	CTRL		Sample if not previously reported
Water Reducing Admixture (4103)		AS 403						V	RCE	Each batch	1 pt	CTRL		Sample if not previously reported
Retarding Admixture (4103)		AS 403						V	RCE	Each batch	1 pt	CTRL		Sample if not previously reported
AS-Approved Source Cert A-Type A Certifica ASD-Approved Shop Drawing Cert C-Type C Certifica S&T-Sampling & Testing Cert D-Type D Certifica					cation									dependent Assurance rification

Sampling and Testing Guide-Minimum Frequency

CONCRETE BRIDGE FLOOR REPAIR & OVERLAY & SURFACING Section 2413

April 15, 2008 Supersedes October 16, 2007 Matls. IM 204 Appendix M

MATERIAL OR CONSTRUCTION	TESTS	METHOD OF ACCEPTANCE	QUALITY CONTROL						INDEPENDENT ASSURANCE & VERIFICATION S&T						
ITEM		RE	& RELATED IMs	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
GRADE INSPECTION															
Plastic Concrete (2413)	Air	318, 327						V	RCE	1/100 sy		RCE		Freq. 1/load for ready mix	
	Slump	317, 327						V	RCE	1/100 sy		RCE		Freq. 1/load for ready mix	
	Density	358						V	RCE	See Note		RCE		For Class O PCC only.(1)	
	Thickness								RCE	3/50 sy		RCE			
	Cylinders							V	DME	3/project		DME		Primary Projects only (Information Only)	
Concrete Sealer (2413.09)	Quality	AS 491.12												(
AS-Approved Source ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert C-Type C Certification DME-District					t Materials Engineer V-Verifi al Materials Office						pendent Assurance cation	

(1) Nuclear density testing frequency for each placement shall be one test within 5 feet (1500 mm) of the beginning and end of the placement and additional tests shall be equally spaced a maximum of 100 feet (30 000 mm) throughout the length of the placement. Each placement shall have a minimum of three nuclear density tests.