



**NOTES:**

PLACE CLAY WATERSTOP IN TRENCH AS SHOWN TO PREVENT WATER FLOW THROUGH GRANULAR TRENCH BACKFILL. COMPACT CLAY WATERSTOP TO MINIMUM 95% DENSITY.

IF STABILIZATION (FOUNDATION) MATERIAL IS REQUIRED, EXTEND WATERSTOP THROUGH STABILIZATION MATERIAL TO BOTTOM OF TRENCH.

BACKFILL REQUIREMENTS ABOVE WATERSTOP (FINAL TRENCH BACKFILL) SHALL BE IN ACCORDANCE WITH FIGURE 3010.1.

WATERSTOPS ARE REQUIRED ONLY WHEN SPECIFIED IN THE CONTRACT DOCUMENTS. WHEN REQUIRED, WATERSTOPS SHALL BE PLACED AT A NOMINAL SPACING OF 800' OR AT LOCATIONS SHOWN ON THE PLANS.

WHEN SUITABLE CLAY MATERIAL IS AVAILABLE ON-SITE, INSTALLATION OF WATERSTOPS SHALL BE CONSIDERED INCIDENTAL.

REV.	DATE	BY	WATERSTOP FOR TRENCHES	FIGURE: 3010.10
DATE: 10/18/05				SHEET 1 OF 1