


- 1 Provide two #4 hoop bars at all pipe openings.
- 2 Cast-in-place base shown. If base is precast integral with walls, the footprint of the base is not required to extend beyond the outer edge of the
- 3 12 inch minimum wall height above all pipes.
- If required by casting manufacturer, provide support beam under all frame joints. Modify structure walls as required to provide pocket for beam.



- 1 Provide two #4 hoop bars at all pipe openings.
- 2 Cast-in-place base shown. If base is precast integral with walls, the footprint of the base is not required to extend beyond the outer edge of the
- 3 12 inch minimum wall height above all pipes.
- If required by casting manufacturer, provide support beam under all frame joints. Modify structure walls as required to provide pocket for beam.

SE		

MAXIMUM PIPE DIAMETERS					
Pipe	Precast	Cast-in-place			
Location	Structure	Structure			
Short Wall	18"	21"			
Long Wall	36"	42"			

	REINFORCING BAR LIST							
Mark	Size	Location	Shape	Count	Length	Spacing		
4b1	4	Base		6	3'-6"	12"		
4b2	4	Base		4	5'-8"	12"		
4w1	4	Walls		20	Wall Height minus 4"	12"		
4w2	4	Short Wall		Varies	3'-0"	12"		
4w3	4	Long Wall		Varies	5'-2"	12"		

