



## **LOCAL AGENCY LETTING INFORMATION**

### **CONTENTS**

<b>DATE ADDED</b>	<b>COUNTY/CITY</b>	<b>LETTING DATE</b>	<b>PAGE NUMBER</b>
April 21, 2025	Dubuque	May 5, 2025	2
April 21, 2025	Dubuque	May 5, 2025	4
April 9, 2025	Webster	May 6, 2025	5
April 9, 2025	Webster	May 6, 2025	6
April 11, 2025	Marion	May 6, 2025	7
April 1, 2025	Bremer	May 13, 2025	8
April 29, 2025	Linn	May 13, 2025	9
April 23, 2025	Sioux	May 20, 2025	10
April 24, 2025	Jones	May 27, 2025	11
April 24, 2025	Jones	May 27, 2025	12
April 29, 2025	Linn	May 27, 2025	13
April 29, 2025	Howard	May 29, 2025	14

## BULLETIN REPORTING FORM

County:	Dubuque County	Project No.:	LM-C25(01)-31
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	5/5/2025	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Culvert Replacements
Contact Phone No.:	563-557-7283	Contact FAX No.:	563-557-1973

**Specific Description of Project:**

Culvert Repl (7) Wulfekuhle Rd, Ridge Rd, New Melleray Rd, Feeney Rd, Bethany Rd, Dyersville East Rd, N Bankston Rd

QUANTITY	UNIT	DESCRIPTION
0.2	ACRE	CLEARING AND GRUBBING
946	CY	EMBANKMENT-IN-PLACE
518	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
383	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
338	SY	SUBGRADE STABILIZATION MATERIAL, POLYMER GRID
48	TON	GRANULAR SHOULDERS, TYPE B
71	TON	CHOKE STONE BASE
142	TON	MACADAM STONE BASE
91	TON	HOT MIX ASPHALT SURFACE PATCHES
274	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
1	LS	REMOVAL OF EXISTING BRIDGE
1	LS	REMOVAL OF EXISTING STRUCTURES
1060	TON	GRANULAR BACKFILL
479	CY	FLOODED BACKFILL
2279	CY	EXCAVATION, CLASS 23, FOR ROADWAY PIPE CULVERT
37.6	CY	STRUCTURAL CONCRETE (MISCELLANEOUS)
2702	LB	REINFORCING STEEL
2	EACH	APRONS, CONCRETE, 66 IN. DIA.
1	EACH	REMOVE AND REINSTALL CONCRETE PIPE APRONS GREATER THAN 36 IN.
56	LF	CULVERT, CONCRETE ROADWAY PIPE, 66 IN. DIA.
32	LF	REMOVE AND REINSTALL RIGID PIPE CULVERT GREATER THAN 36 IN.
18	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 15 IN. DIA.
120	LF	CULVERT, CORRUGATED METAL ROADWAY PIPE, 42 IN. DIA.
144	LF	CULVERT, CORRUGATED METAL ROADWAY PIPE, 48 IN. DIA.
116	LF	CULVERT, CORRUGATED METAL ROADWAY PIPE, 60 IN. DIA.
78	LF	CULVERT, CORRUGATED METAL ROADWAY PIPE, 66 IN. DIA.
26.5	CY	FLOWABLE MORTAR
338	SY	ENGINEERING FABRIC
158	TON	REVTMENT, CLASS E

20	CY	REVETMENT, REMOVE AND REPLACE
262.21	SY	REMOVAL OF PAVEMENT
4	EACH	OBJECT MARKER, TYPE 3
26	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
1	EACH	PIPE CULVERT CONNECTION, TYPE 'C' (DR-122)
1	LS	INSTALL RAILROAD TANK CARS
0.71	ACRE	MULCHING
0.71	ACRE	SEEDING AND FERTILIZING (RURAL)
0.71	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
450	LF	SILT FENCE
1175	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.

Date: 4/21/2025 Local Agency Official: Russell Weber, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

## BULLETIN REPORTING FORM

County:	Dubuque County	Project No.:	2025 Maintenance Culvert Lining
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	5/5/2025	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Culvert Lining
Contact Phone No.:	563-557-7283	Contact FAX No.:	563-557-1973

Specific Description of Project:

Cured-In-Place Culvert Linings (10) on Sundown Rd from US 151 to Monastery Rd and (2) on Higginsport Rd

QUANTITY	UNIT	DESCRIPTION
10	CY	FLOWABLE MORTAR
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
8	LF	CURED-IN-PLACE CULVERT LINING
790	LF	CURED-IN-PLACE CULVERT LINING
97	LF	CURED-IN-PLACE CULVERT LINING

Date: 4/21/2025      Local Agency Official: Russell Weber, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired.  
E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

## BULLETIN REPORTING FORM

County:	Webster County	Project No.:	L-973002--73-94
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	5/6/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	RCB Culvert Replacement - Single Box
Contact Phone No.:	515-576-3281	Contact FAX No.:	

**Specific Description of Project:**

The Existing 17' x 23' Single Span Steel Stringer Bridge with a Concrete Deck and Timber High Abutments will be replaced with a Single 12' x 11' x 37' Precast Concrete Box Culvert with 15 Deg R.A Skewed End Sections on Samson Ave., Approx 970' South of the Northwest Corner Section 30, Colfax Twp, Over D.D. 57

Tied With: L-891560--73-94

QUANTITY	UNIT	DESCRIPTION
182	CY	EMBANKMENT-IN-PLACE
220	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
1	LS	REMOVAL OF EXISTING BRIDGE
85	TON	GRANULAR BACKFILL, PLACE ONLY
427	CY	EXCAVATION, CLASS 20
37	LF	PRECAST CONCRETE BOX CULVERT, 12 FT. X 11 FT.
2	EACH	PRECAST CONCRETE BOX CULVERT STRAIGHT END SECTION, 12 FT. X 11 FT.
260	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
1	EACH	TEMPORARY STREAM DIVERSION
150	SY	ENGINEERING FABRIC
165	TON	REVTMENT, CLASS E
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
300	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.

Date: 4/9/2025 Local Agency Official: Jamie Johll, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at [DOT.Contracts@iowadot.us](mailto:DOT.Contracts@iowadot.us)

## BULLETIN REPORTING FORM

County:	Webster County	Project No.:	L-891560--73-94
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	5/6/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	RCB Culvert Replacement - Single Box
Contact Phone No.:	515-576-3281	Contact FAX No.:	

**Specific Description of Project:**

The Existing 25 'x 26' Single Span Concrete Channel Beam Bridge with a Concrete Deck and Concrete High Abutments will be replace with a Single 10' x 10' x 60' Precast Concrete Box Culvert with 30 Deg R.A Skewed End Sections on 240th St, Approx 2950' East of the Northwest Corner Section 15, Elkhorn Twp, Over D.D. 96

Tied With: L-973002--73-94

QUANTITY	UNIT	DESCRIPTION
482	CY	EMBANKMENT-IN-PLACE
278	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
1	LS	REMOVAL OF EXISTING BRIDGE
30	TON	GRANULAR BACKFILL, PLACE ONLY
539	CY	EXCAVATION, CLASS 20
60	LF	PRECAST CONCRETE BOX CULVERT, 10 FT. X 10 FT.
2	EACH	PRECAST CONCRETE BOX CULVERT STRAIGHT END SECTION, 10 FT. X 10 FT.
180	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
1	EACH	TEMPORARY STREAM DIVERSION
40	LF	SUBDRAIN, CORRUGATED METAL PIPE, 12 IN. DIA.
220	SY	ENGINEERING FABRIC
210	TON	REVTMENT, CLASS E
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
300	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.

Date: 4/9/2025 Local Agency Official: Jamie Jhll, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

## BULLETIN REPORTING FORM

County:	Marion County	Project No.:	M-DOLLAR26-4
Proposal Guarantee:	\$37,500.00	DBE or TSB Goal:	
Date of Letting:	5/6/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Bridge Removal
Contact Phone No.:	641-828-2225	Contact FAX No.:	641-828-7349

**Specific Description of Project:**

Emergency removal and disposal of the Wabash Bridge (Dollar Bridge) on 216th Place over the Des Moines River. The bridge is 561' in total length with three 155' truss spans plus two approach spans. The removal includes all spans and two steel caisson piers and one pile pier.

QUANTITY	UNIT	DESCRIPTION
1	LS	REMOVAL OF EXISTING BRIDGE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION

Date: 4/11/2025 Local Agency Official: Tyler Christian, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

## BULLETIN REPORTING FORM

County:	Bremer County	Project No.:	L-L-1-127--73-09 (B)
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	5/13/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Bridge Replacement
Contact Phone No.:	319-352-4302	Contact FAX No.:	319-352-4326

Specific Description of Project:

Providing Precast Deck Panels and Setting of the Deck Panels

QUANTITY	UNIT	DESCRIPTION
1	LS	MOBILIZATION
4	EACH	Deck Unit, Ext. Oden Precast Panel, 50'-0
14	EACH	Deck Unit, Int. Oden Precast Panel, 50'-0

Date: 4/1/2025 Local Agency Official: Landon Moore, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

## BULLETIN REPORTING FORM

County:	Linn County	Project No.:	M-CULVERT LINING(25)
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	5/13/2025	Time of Letting:	11:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Culvert Lining and Deep Soil Injections
Contact Phone No.:	319-892-6400	Contact FAX No.:	319-892-6419

Specific Description of Project:

Culvert lining and Deep Soil Injections at Various Locations in Linn County

QUANTITY	UNIT	DESCRIPTION
1	LS	TRAFFIC CONTROL
8	EACH	FLAGGERS
1	LS	MOBILIZATION
216	LB	DEEP SOIL INJECTION
432	LF	CIP CULVERT LINING

Date: 4/28/2025 Local Agency Official: Brad Ketels, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at [DOT.Contracts@iowadot.us](mailto:DOT.Contracts@iowadot.us)

## BULLETIN REPORTING FORM

County:	Sioux County	Project No.:	LFM-811--7X-84
Proposal Guarantee:	\$100,000.00	DBE or TSB Goal:	
Date of Letting:	5/20/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	Sioux County Engineer's Office	Type of Project:	Grading
Contact Phone No.:	712-737-2248	Contact FAX No.:	712-737-2757

Specific Description of Project:

Shoulder widening and ditch improvement

QUANTITY	UNIT	DESCRIPTION
1042.85	UNIT	CLEARING AND GRUBBING
72985.71	CY	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED
49494.53	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
20	CY	EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS
4005.47	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
70	EACH	APRONS, SAFETY SLOPE, 18 IN. DIA.
14	EACH	APRONS, SAFETY SLOPE, 24 IN. DIA.
2	EACH	APRONS, SAFETY SLOPE, 30 IN. DIA.
2	EACH	APRONS, SAFETY SLOPE, 48 IN. DIA.
2718	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
324	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.
66	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 30 IN. DIA.
72	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 48 IN. DIA.
48.14	SY	REMOVAL OF PAVEMENT
1	LS	TRAFFIC CONTROL
10	EACH	FLAGGERS
1	LS	MOBILIZATION
75.76	ACRE	MULCHING
70.31	ACRE	SEEDING AND FERTILIZING (RURAL)
5.45	ACRE	SEEDING AND FERTILIZING (URBAN)
3691	LF	SILT FENCE
4443	LF	SILT FENCE FOR DITCH CHECKS
14518	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.

Date: 4/23/2025 Local Agency Official: Joel Sikkema, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

## BULLETIN REPORTING FORM

County:	Jones County	Project No.:	M-0826
Proposal Guarantee:	\$2,000.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	09:30 AM
Bid Turn-In Location:	County Auditor	Type of Project:	HMA Overlay
Contact Phone No.:	319-462-3785	Contact FAX No.:	319-462-3903

Specific Description of Project:

**TIED WITH JONES COUNTY PROJECT M-0726, HMA OVERLAY ON RIVER ROAD**

HMA Overlay on Shaw Road in Section 13 of Fairview Township, SE of the city of Anamosa.

Tied With: Jones County Project M-0726

QUANTITY	UNIT	DESCRIPTION
0.1	MILE	CLEANING AND PREPARATION OF BASE
500	TON	PAVEMENT SCARIFICATION
359	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
22	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	TRAFFIC CONTROL
1	EACH	FLAGGERS
1	LS	MOBILIZATION

Date: 4/24/2025 Local Agency Official: Derek Snead, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

## BULLETIN REPORTING FORM

County:	Jones County	Project No.:	M-0626
Proposal Guarantee:	\$2,000.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	09:30 AM
Bid Turn-In Location:	County Auditor	Type of Project:	HMA Overlay
Contact Phone No.:	319-462-3785	Contact FAX No.:	319-462-3903

**Specific Description of Project:**

THIS DESIGN IS FOR AN HMA OVERLAY ON RIVERVIEW ROAD FROM BUCHANAN ST SW, EAST ONE MILE TO THE INTERSECTION OF RIVERVIEW RD. DIVISION 1, JONES COUNTY

QUANTITY	UNIT	DESCRIPTION
365	TON	GRANULAR SHOULDERS, TYPE B
1	MILE	CLEANING AND PREPARATION OF BASE
307	SY	PAVEMENT SCARIFICATION
1628	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
98	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	TRAFFIC CONTROL
10	EACH	FLAGGERS
5	EACH	PILOT CARS
1	LS	MOBILIZATION

Date: 4/24/2025 Local Agency Official: Derek Snead, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

## BULLETIN REPORTING FORM

County:	Linn County	Project No.:	L-ABBOTSFORD RD(25)
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	11:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Asphalt Overlay
Contact Phone No.:	319-892-6400	Contact FAX No.:	319-892-6419

Specific Description of Project:

Asphalt Paving on Abbotsford Road from Dows Road to Lakeside Road and all of Innes Way.

QUANTITY	UNIT	DESCRIPTION
94	STA	SHOULDER CONSTRUCTION, EARTH
465.9	SY	PAVEMENT SCARIFICATION
1611	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
97.56	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
151.2	SY	HOT MIX ASPHALT, DRIVEWAY
251.6	SY	DRIVEWAY, P.C. CONCRETE, 5 IN.
264.2	SY	REMOVAL OF PAVED DRIVEWAY
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
6	EACH	FLAGGERS
1	LS	MOBILIZATION
69	MGAL	WATER, HYDRAULIC SEEDING
0.9	ACRE	MULCHING, BONDED FIBER MATRIX
0.9	ACRE	HYDRAULIC SEEDING

Date: 4/28/2025 Local Agency Official: Brad Ketels, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

## BULLETIN REPORTING FORM

County:	Howard County	Project No.:	L-(C-9)--73-45
Proposal Guarantee:	\$62,500.00	DBE or TSB Goal:	
Date of Letting:	5/29/2025	Time of Letting:	01:00 PM
Bid Turn-In Location:	County Engineer	Type of Project:	Bridge Replacement - CCS & Grading
Contact Phone No.:	563-547-2620	Contact FAX No.:	563-547-2576

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
1500	CY	EXCAVATION, CLASS 10, CHANNEL
1	LS	REMOVAL OF EXISTING BRIDGE
105	CY	EXCAVATION, CLASS 20
77	CY	EXCAVATION, CLASS 21
436.9	CY	STRUCTURAL CONCRETE (BRIDGE)
81748	LB	REINFORCING STEEL
322	LF	CONCRETE OPEN RAILING, TL-4
390	LF	PILES, STEEL, HP 10 X 42
720	LF	PILES, STEEL, HP 14 X 73
110	LF	PREBORED HOLES
1145	TON	REVTMENT, CLASS E
20	CY	REVTMENT, REMOVE AND REPLACE
1	LS	MOBILIZATION
28	LF	ROCK CORING, 6 @ 4'-8
0.9	ACRE	CLEARING AND GRUBBING
585	CY	EMBANKMENT-IN-PLACE
1405	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
1550	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
450	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
50	CY	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT
78	LF	CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.
94	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
50	LF	STEEL BEAM GUARDRAIL
4	EACH	STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-221
4	EACH	STEEL BEAM GUARDRAIL END ANCHOR, BOLTED
4	EACH	STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-225
1	LS	CONSTRUCTION SURVEY
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
6616	CY	EXCAVATION, OXBOW
3.8	ACRE	MULCHING
1.9	ACRE	SEEDING AND FERTILIZING (RURAL)
1.9	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
565	LF	SILT FENCE
570	LF	SILT FENCE FOR DITCH CHECKS
1135	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
470	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
1	EACH	MOBILIZATIONS, EROSION CONTROL
1	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL

5390	CY	OXBOW, EXCAVATION
998	CY	OXBOW, STRIPPING
2711	CY	SHALLOW WATER, EXCAVATION
487	CY	SHALLOW WATER, STRIPPING
1.06	ACRE	ROUTE SEED MIX
1.3	ACRE	EPHEMERAL POND MIX
1	LS	MOBILIZATION, CRAY OXBOW RESTORATION

Date: 4/29/2025 Local Agency Official: Nick Rissman, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at [DOT.Contracts@iowadot.us](mailto:DOT.Contracts@iowadot.us)