

LOCAL AGENCY LETTING INFORMATION

CONTENTS

DATE ADDED	COUNTY/CITY	LETTING DATE	PAGE NUMBER
April 23, 2025	Sioux	May 20, 2025	2
May 7, 2025	Jasper	May 22, 2025	3
April 24, 2025	Jones	May 27, 2025	4
April 24, 2025	Jones	May 27, 2025	5
April 29, 2025	Linn	May 27, 2025	6
May 6, 2025	Linn	May 27, 2025	7
May 9, 2025	Kossuth	May 27, 2025	8
May 13, 2025	Pottawattamie	May 27, 2025	9
May 13, 2025	Pottawattamie	May 27, 2025	10
May 13, 2025	Pottawattamie	May 27, 2025	11
May 13, 2025	Pottawattamie	May 27, 2025	12
April 29, 2025	Howard	May 29, 2025	13
May 6, 2025	Muscatine	June 2, 2025	15
May 2, 2025	Johnson	June 3, 2025	17
May 6, 2025	Cedar	June 3, 2025	18
May 8, 2025	Story	June 3, 2025	20
May 6, 2025	Muscatine	June 23, 2025	21
May 14, 2025	Montgomery	July 15, 2025	23



County:	Sioux County	Project No.:	LFM-8117X-84
Proposal Guarantee:	\$100,000.00	DBE or TSB Goal:	
Date of Letting:	5/20/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	Sioux County Engineer's Office	Type of Project:	Grading
Contact Phone No.:	712-737-2248	Contact FAX No.:	712-737-2757

Specific Description of Project:

Shoulder widening and ditch improvement

QUANTITY	UNIT	DESCRIPTION
1042.85	UNIT	CLEARING AND GRUBBING
72985.71	CY	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED
49494.53	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
20	CY	EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS
4005.47	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
70	EACH	APRONS, SAFETY SLOPE, 18 IN. DIA.
14	EACH	APRONS, SAFETY SLOPE, 24 IN. DIA.
2	EACH	APRONS, SAFETY SLOPE, 30 IN. DIA.
2	EACH	APRONS, SAFETY SLOPE, 48 IN. DIA.
2718	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
324	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.
66	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 30 IN. DIA.
72	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 48 IN. DIA.
48.14	SY	REMOVAL OF PAVEMENT
1	LS	TRAFFIC CONTROL
10	EACH	FLAGGERS
1	LS	MOBILIZATION
75.76	ACRE	MULCHING
70.31	ACRE	SEEDING AND FERTILIZING (RURAL)
5.45	ACRE	SEEDING AND FERTILIZING (URBAN)
3691	LF	SILT FENCE
4443	LF	SILT FENCE FOR DITCH CHECKS
14518	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.

Date: 4/23/2025 Local Agency Official: Joel Sikkema, County Engineer



County:	Jasper County	Project No.:	L-C050(DO5BRPCC)73-50
Proposal Guarantee:	\$0.00	DBE or TSB Goal:	
Date of Letting:	5/22/2025	Time of Letting:	02:00 PM
Bid Turn-In Location:	County Engineer	Type of Project:	Bridge Deck PCC
Contact Phone No.:	641-792-5862	Contact FAX No.:	641-791-7740

Specific Description of Project:

This bid is for MATERIAL AND HAULING TO SITE.

Site is located on N 107th Ave W, East of W 100th St N 1.2 Miles.

Mix should meet the requirements in Section 2403 of the Standard Specifications for Highway and Bridge Construction manual.

Class 3i Durability Coarse Aggregate, C Mix. May use fly ash as per Spec Section 2403.

QUANTITY	UNIT	DESCRIPTION
90	CY	STRUCTURAL CONCRETE (BRIDGE)

Date: 5/7/2025 Local Agency Official: Michael Frietsch, County Engineer



County:	Jones County	Project No.:	M-0826
Proposal Guarantee:	\$2,000.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	09:30 AM
Bid Turn-In Location:	County Auditor	Type of Project:	HMA Overlay
Contact Phone No.:	319-462-3785	Contact FAX No.:	319-462-3903

Specific Description of Project:

TIED WITH JONES COUNTY PROJECT M-0726, HMA OVERLAY ON RIVER ROAD

HMA Overlay on Shaw Road in Section 13 of Fairview Township, SE of the city of Anamosa.

Tied With: Jones County Project M-0726

QUANTITY	UNIT	DESCRIPTION
0.1	MILE	CLEANING AND PREPARATION OF BASE
500	TON	PAVEMENT SCARIFICATION
359	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
22	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	TRAFFIC CONTROL
1	EACH	FLAGGERS
1	LS	MOBILIZATION

Date: 4/24/2025 Local Agency Official: Derek Snead, County Engineer



County:	Jones County	Project No.:	M-0626
Proposal Guarantee:	\$2,000.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	09:30 AM
Bid Turn-In Location:	County Auditor	Type of Project:	HMA Overlay
Contact Phone No.:	319-462-3785	Contact FAX No.:	319-462-3903

Specific Description of Project:

THIS DESIGN IS FOR AN HMA OVERLAY ON RIVERVIEW ROAD FROM BUCHANAN ST SW, EAST ONE MILE TO THE INTERSECTION OF RIVERVIEW RD. DIVISION 1, JONES COUNTY

QUANTITY	UNIT	DESCRIPTION
365	TON	GRANULAR SHOULDERS, TYPE B
1	MILE	CLEANING AND PREPARATION OF BASE
307	SY	PAVEMENT SCARIFICATION
1628	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
98	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	TRAFFIC CONTROL
10	EACH	FLAGGERS
5	EACH	PILOT CARS
1	LS	MOBILIZATION

Date: 4/24/2025 Local Agency Official: Derek Snead, County Engineer



County:	Linn County	Project No.:	L-ABBOTSFORD RD(25)
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	11:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Asphalt Overlay
Contact Phone No.:	319-892-6400	Contact FAX No.:	319-892-6419

Specific Description of Project:

Asphalt Paving on Abbotsford Road from Dows Road to Lakeside Road and all of Innes Way.

QUANTITY	UNIT	DESCRIPTION
94	STA	SHOULDER CONSTRUCTION, EARTH
465.9	SY	PAVEMENT SCARIFICATION
1611	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
97.56	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
151.2	SY	HOT MIX ASPHALT, DRIVEWAY
251.6	SY	DRIVEWAY, P.C. CONCRETE, 5 IN.
264.2	SY	REMOVAL OF PAVED DRIVEWAY
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
6	EACH	FLAGGERS
1	LS	MOBILIZATION
69	MGAL	WATER, HYDRAULIC SEEDING
0.9	ACRE	MULCHING, BONDED FIBER MATRIX
0.9	ACRE	HYDRAULIC SEEDING

Date: 4/28/2025 Local Agency Official: Brad Ketels, County Engineer



County:	Linn County	Project No.:	M-HMA PATCHING(25)
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	11:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Asphalt Repair
Contact Phone No.:	319-892-6400	Contact FAX No.:	319-892-6419

Specific Description of Project:

HMA Patching and Leveling at various locations in Linn County

QUANTITY	UNIT	DESCRIPTION
145	SY	PATCHES, PARTIAL-DEPTH REPAIR, HOT MIX ASPHALT
4	EACH	PATCHES BY COUNT (REPAIR)
2610	SY	PAVEMENT SCARIFICATION
55	TON	HOT MIX ASPHALT MIXTURE, WEDGE, LEVELING OR STRENGTHENING COURSE
468	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
31.38	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
2.84	STA	PAINTED PAVEMENT MARKINGS, HIGH-BUILD WATERBORNE
1	LS	TRAFFIC CONTROL
20	EACH	FLAGGERS
1	LS	MOBILIZATION

Date: 5/6/2025 Local Agency Official: Brad Ketels, County Engineer



County:	Kossuth County	Project No.:	MSC-1-25 thru MSC-4-25 1
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	08:40 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Seal Coat
Contact Phone No.:	515-295-3320	Contact FAX No.:	515-295-4973

Specific Description of Project:

MSC-1-25, Maintenance Seal Coat on Kossuth County Route P44 from B19 north 3 miles to B14.

MSC-2-25, Maintenance Seal Coat on Kossuth County Route P20 from A42 north 6 miles to IA 9.

MSC-3-25, Maintenance Seal Coat on Kossuth County Route P16 from IA 9 north 3 miles to A21.

MSC-4-25, Maintenance Seal Coat on Kossuth County Route A38 from West County Line east 1 mile to P16.

QUANTITY	UNIT	DESCRIPTION	
522	TON	Cover Aggregate	
12300	GAL	MC-3000 Bitumen Binder	
1044	TON	Cover Aggregate	
24600	GAL	MC-3000 Bitumen Binder	
522	TON	Cover Aggregate	
12300	GAL	MC-3000 Bitumen Binder	
174	TON	Cover Aggregate	
4100	GAL	MC-3000 Bitumen Binder	

Date: 5/8/2025 Local Agency Official: Doug Miller, County Engineer



County:	Pottawattamie County	Project No.:	L-2025(WS42BEAMS)78-73
Proposal Guarantee:	\$1,500.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Furnish Materials - Beams
Contact Phone No.:	712-328-5608	Contact FAX No.:	712-328-4751

Specific Description of Project:

Furnish beams for bridge construction.

QUANTITY	UNIT	DESCRIPTION	
5	EACH	Steel Beam - W30 x 211x80' - Weathering Steel - 1/2" Camber	
10	EACH	Steel Beam - W30x90x40' - Weathering Steel - 1/2" Camber	

Date: 5/13/2025 Local Agency Official: John Rasmussen, County Engineer



County:	Pottawattamie County	Project No.:	L-2025(WS42PILING)78-73
Proposal Guarantee:	\$1,500.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Furnish Materials - Piling
Contact Phone No.:	712-328-5608	Contact FAX No.:	712-328-4751

Specific Description of Project:

Furnish piling materials for bridge construction project.

QUANTITY	UNIT	DESCRIPTION
320	LF	PILES, STEEL, HP 8 X 36
600	LF	PILES, STEEL, HP 10 X 42
104	LF	PILES, STEEL, HP 12 X 53
700	LF	PILES, STEEL, HP 14 X 73
1980	SF	PILES, STEEL SHEET
120	SF	PILES, STEEL SHEET, 120 degree corner

Date: 5/13/2025 Local Agency Official: John Rasmussen, County Engineer



County:	Pottawattamie County	Project No.:	L-2025(WS42DECK)78-73
Proposal Guarantee:	\$1,500.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Furnish Materials - Timber Deck Panels
Contact Phone No.:	712-328-5608	Contact FAX No.:	712-328-4751

Specific Description of Project:

Furnish 6" nail laminated deck panels for 160' steel beam bridge.

QUANTITY	UNIT	DESCRIPTION
160	LF	4' x 6" Nail Laminated Treated Timber Transverse Deck Panels

Date: 5/13/2025 Local Agency Official: John Rasmussen, County Engineer



County:	Pottawattamie County	Project No.:	L-2025(WS42MISC)78-73
Proposal Guarantee:	\$1,500.00	DBE or TSB Goal:	
Date of Letting:	5/27/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Furnish Materials - Misc Materials
Contact Phone No.:	712-328-5608	Contact FAX No.:	712-328-4751

Specific Description of Project:

Furnish miscellaneous steel materials for bridge construction.

QUANTITY	UNIT	DESCRIPTION
4	EACH	Flared End Terminal - Thrie Beam Guardrail
132	LF	C12x25 C Channel
283	LF	C15 x 33.9 C Channel
52	LF	L6x3.5x3/8 Angle Iron
52	LF	Steel Plate - 1/2"x18"x26'
325	LF	Thrie Beam Guardrail
379	LF	W6x15 Steel Beam

Date: 5/13/2025 Local Agency Official: John Rasmussen, County Engineer



County:	Howard County	Project No.:	L-(C-9)73-45
Proposal Guarantee:	\$62,500.00	DBE or TSB Goal:	
Date of Letting:	5/29/2025	Time of Letting:	01:00 PM
Bid Turn-In Location:	County Engineer	Type of Project:	Bridge Replacement - CCS & Grading
Contact Phone No.:	563-547-2620	Contact FAX No.:	563-547-2576

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION	
1500	CY	EXCAVATION, CLASS 10, CHANNEL	
1	LS	REMOVAL OF EXISTING BRIDGE	
105	CY	EXCAVATION, CLASS 20	
77	CY	EXCAVATION, CLASS 21	
436.9	CY	STRUCTURAL CONCRETE (BRIDGE)	
81748	LB	REINFORCING STEEL	
322	LF	CONCRETE OPEN RAILING, TL-4	
390	LF	PILES, STEEL, HP 10 X 42	
720	LF	PILES, STEEL, HP 14 X 73	
110	LF	PREBORED HOLES	
1145	TON	REVETMENT, CLASS E	
20	CY	REVETMENT, REMOVE AND REPLACE	
1	LS	MOBILIZATION	
28	LF	ROCK CORING, 6 @ 4'-8	
0.9	ACRE	CLEARING AND GRUBBING	
585	CY	EMBANKMENT-IN-PLACE	
1405	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW	
1550	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD	
450	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	
50	CY	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	
78	LF	CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.	
94	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.	
50	LF	STEEL BEAM GUARDRAIL	
4	EACH	STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-221	
4	EACH	STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	
4	EACH	STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-225	
1	LS	CONSTRUCTION SURVEY	
2	EACH	SAFETY CLOSURE	
1	LS	TRAFFIC CONTROL	
6616	CY	EXCAVATION, OXBOW	
3.8	ACRE	MULCHING	
1.9	ACRE	SEEDING AND FERTILIZING (RURAL)	
1.9	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING	
565	LF	SILT FENCE	
570	LF	SILT FENCE FOR DITCH CHECKS	
1135	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	
470	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	
1	EACH	MOBILIZATIONS, EROSION CONTROL	
1	EACH	MOBILIZATIONS, EMERGENSY EROSION CONTROL	

5390	CY	OXBOW, EXCAVATION
998	CY	OXBOW, STRIPPING
2711	CY	SHALLOW WATER, EXCAVATION
487	CY	SHALLOW WATER, STRIPPING
1.06	ACRE	ROUTE SEED MIX
1.3	ACRE	EPHEMERAL POND MIX
1	LS	MOBILIZATION, CRAY OXBOW RESTORATION

Date: 4/29	/2025	Local Agency	Official:	Nick Rissman,	County	Engineer	
------------	-------	--------------	-----------	---------------	--------	----------	--



County:	Muscatine County	Project No.:	L-(GO-4)73-70
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	6/2/2025	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Box Culverts
Contact Phone No.:	563-263-6351	Contact FAX No.:	563-263-6358

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
1.1	ACRE	CLEARING AND GRUBBING
2619	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
427	CY	EXCAVATION, CLASS 10, CHANNEL
665	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
7	STA	SHOULDER CONSTRUCTION, EARTH
60	TON	CHOKE STONE BASE
160	TON	MACADAM STONE BASE
272	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
80	TON	SURFACING, DRIVEWAY, CLASS A CRUSHED STONE
1	LS	REMOVAL OF EXISTING BRIDGE
1356	CY	EXCAVATION, CLASS 20
261	CY	STRUCTURAL CONCRETE (RCB CULVERT)
38582	LB	REINFORCING STEEL
2	EACH	APRONS, METAL, 18 IN. DIA.
56	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.
1	EACH	TEMPORARY STREAM DIVERSION
327	SY	ENGINEERING FABRIC
350	TON	REVETMENT, CLASS E
195	LF	FENCE, CHANNEL CROSSING, TYPE A
503	LF	FENCE, FIELD
31	EACH	FIELD FENCE BRACE PANELS
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
2	ACRE	MULCHING
1	ACRE	SEEDING AND FERTILIZING (RURAL)
2	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
3	EACH	SILT BASINS
870	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
3	EACH	MOBILIZATIONS, EROSION CONTROL
2	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL

Date: 5/6/2025 Local Agency Official: Bryan Horesowsky, County Engineer



County:	Johnson County	Project No.:	L-R-19-273-52
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	6/3/2025	Time of Letting:	09:00 AM
Bid Turn-In Location:	Johnson County Administration Building at 913 S. Dubuque Street, Iowa City, IA 52240	Type of Project:	Bridge or Culvert
Contact Phone No.:	319-356-6046	Contact FAX No.:	319-339-6133

Specific Description of Project:

Bridge Replacement (44'-0" x 24'-6" Two Span Laminated Timber Bridge with Full Timber Abutments) on Maier Avenue SW in Section 19, T78N, R6W, of the 5th P.M., Liberty Township, Johnson County, Iowa.

QUANTITY	UNIT	DESCRIPTION	
235	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW	
780	CY	EXCAVATION, CLASS 13, CHANNEL	
1	LS	REMOVAL OF EXISTING BRIDGE	
460	CY	EXCAVATION, CLASS 20	
414	LB	STRUCTURAL STEEL	
792	LB	MISCELLANEOUS HARDWARE	
9.588	MFBM	TREATED TIMBER AND LUMBER	
1065	LF	PILES, WOOD (TREATED TIMBER TRESTLE PILES)	
226	LF	STEEL BEAM GUARDRAIL	
401	TON	REVETMENT, CLASS E	
1	LS	TRAFFIC CONTROL	
1	LS	MOBILIZATION	
1	LS	TIMBER PANEL-LAM BRIDGE DECK	

Date: 5/2/2025 Local Agency Official: Paul Wittau, County Engineer



County:	Cedar County	Project No.:	L-20230373-16 (Division 1) and LFM-2025077X-16 (Division 2)
Proposal Guarantee:	\$37,500.00	DBE or TSB Goal:	
Date of Letting:	6/3/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	Box Culverts
Contact Phone No.:	563-886-6102	Contact FAX No.:	

Specific Description of Project:

L-202303--73-16 (Spicer Avenue) is a 10'x7'x44' 15 degree skew RCB Replacement.

LFM-202507--7X-16 (190th Street) is a 10'x8'x44' 15 degree skew RCB Replacement.

QUANTITY	UNIT	DESCRIPTION		
1541	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW		
14	CY	EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS		
2	STA	LOCATING TILE LINES		
128	CY	EXCAVATION, CLASS 10, CHANNEL		
465.4	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD		
168.1	TON	GRANULAR MATERIAL		
592.2	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE		
16	TON	SURFACING, DRIVEWAY, CLASS A CRUSHED STONE		
1	LS	REMOVAL OF EXISTING BRIDGE		
168.8	CY	FLOODED BACKFILL		
516	CY	EXCAVATION, CLASS 20		
102.1	CY	STRUCTURAL CONCRETE (RCB CULVERT)		
14235	LB	REINFORCING STEEL		
2	EACH	APRONS, METAL, 18 IN. DIA.		
48	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.		
1	EACH	TEMPORARY STREAM DIVERSION		
1	EACH	INTAKE, STANDPIPE, 8 IN., AS PER PLAN		
20	LF	SUBDRAIN, PLASTIC PIPE, 12 IN.		
166	LF	SUBDRAIN, PERFORATED PLASTIC PIPE, 4 IN. DIA.		
1	EACH	SUBDRAIN OUTLET, DR-305		
291.3	TON	REVETMENT, CLASS E		
2	EACH	SAFETY CLOSURE		
1	LS	TRAFFIC CONTROL		
1	LS	MOBILIZATION		
621	TON	TONS' ITEM - MODIFIED SUBBASE		
2.6	ACRE	MULCHING		
1.3	ACRE	SEEDING AND FERTILIZING (RURAL)		
1.3	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING		
4	EACH	SILT BASINS		
4	EACH	REMOVAL OF SILT BASINS		
920	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.		
400	LF	REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE		
3	EACH	MOBILIZATIONS, EROSION CONTROL		
1	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL		
0.1	ACRE	CLEARING AND GRUBBING		
2055	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW		
408	CY	EXCAVATION, CLASS 10, CHANNEL		
808	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD		
212	TON	GRANULAR MATERIAL		
779	CY	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE		
32	TON	SURFACING, DRIVEWAY, CLASS A CRUSHED STONE		
1	LS	REMOVAL OF EXISTING BRIDGE		
251	CY	FLOODED BACKFILL		
327	CY	EXCAVATION, CLASS 20		
113.4	CY	STRUCTURAL CONCRETE (RCB CULVERT)		
15980	LB	REINFORCING STEEL		
4	EACH	APRONS, METAL, 18 IN. DIA.		
96	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.		
1	EACH	TEMPORARY STREAM DIVERSION 18		
96	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.		

144	LF	SUBDRAIN, PLASTIC PIPE, 4 IN.
467.2	TON	REVETMENT, CLASS E
60	LF	REMOVAL OF FENCE, FIELD
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
0.1	ACRE	ACRES ITEM - SPECIAL SEEDING
862.4	TON	TONS ITEM - MODIFIED SUBBASE
1	ACRE	MULCHING
0.5	ACRE	SEEDING AND FERTILIZING (RURAL)
0.5	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
4	EACH	SILT BASINS
4	EACH	REMOVAL OF SILT BASINS
1560	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
400	LF	REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE
2	EACH	MOBILIZATIONS, EROSION CONTROL
1	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL

Date: 5/6/2025 Local Agency Official: Robert Fangmann, County Engineer



County:	Story County	Project No.:	L-F1773-85
Proposal Guarantee:	\$6,250.00	DBE or TSB Goal:	
Date of Letting:	6/3/2025	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	HMA Paving
Contact Phone No.:	515-382-7355	Contact FAX No.:	515-382-7369

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
57.4	CY	EXCAVATION, CLASS 10, WASTE
134.6	TON	GRANULAR SHOULDERS, TYPE B
416.1	TON	HOT MIX ASPHALT STANDARD TRAFFIC, BASE COURSE, 1/2 IN. MIX
208.1	TON	HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX
208.1	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
49.9	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	TRAFFIC CONTROL
12	EACH	FLAGGERS
1	LS	MOBILIZATION

Date: 5/8/2025 Local Agency Official: Darren Moon, County Engineer



County:	Muscatine County	Project No.:	LFM-(FR-6)7X-70
Proposal Guarantee:	\$250,000.00	DBE or TSB Goal:	
Date of Letting:	6/23/2025	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	PCC Paving
Contact Phone No.:	563-263-6351	Contact FAX No.:	563-263-6358

Specific Description of Project:

PCC Reconstruction from Fruitland Road to Muscatine City limits.

QUANTITY	UNIT	DESCRIPTION
0.7	ACRE	CLEARING AND GRUBBING
5825	CY	EMBANKMENT-IN-PLACE
17902	CY	EXCAVATION, CLASS 13, WASTE
335	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
55370	SY	SUBGRADE STABILIZATION MATERIAL, POLYMER GRID
7132	CY	MODIFIED SUBBASE
8860	CY	MODIFIED SUBBASE, PLACE ONLY
3138	TON	GRANULAR SHOULDERS, TYPE B
32	EACH	RELOCATION OF MAIL BOXES
1363	SY	STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 7 IN.
49360	SY	STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 9 IN.
1	LS	PORTLAND CEMENT CONCRETE PAVEMENT SAMPLES
90	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
960	TON	SURFACING, DRIVEWAY, CLASS A CRUSHED STONE
36550	EACH	PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT SMOOTHNESS (BY SCHEDULE)
31584	LF	SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.
112	EACH	SUBDRAIN OUTLET, DR-306
5470	LF	REMOVAL OF CABLE GUARDRAIL
4910	LF	HIGH TENSION CABLE GUARDRAIL
8	EACH	HIGH TENSION CABLE GUARDRAIL, END ANCHOR
1	EACH	HIGH TENSION CABLE GUARDRAIL, SPARE PARTS KIT
4602	SY	ENGINEERING FABRIC
4969.6	TON	EROSION STONE
2274	SY	REMOVAL OF PAVEMENT
39870.5	SY	REMOVAL AND CRUSHING OF PAVEMENT
106	SF	DETECTABLE WARNINGS
1680	SY	DRIVEWAY, P.C. CONCRETE, 6 IN.
2268	SY	REMOVAL OF PAVED DRIVEWAY

63	SY	RAILROAD APPROACH SECTION, HMA
1	LS	CONSTRUCTION SURVEY
6	EACH	PAINTED SYMBOLS AND LEGENDS, DURABLE
349.97	STA	PAINTED PAVEMENT MARKINGS, DURABLE
30	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
1	LS	RAILROAD PROTECTIVE LIABILITY INSURANCE FOR DAKOTA, MINNESOTA, AND EASTERN RAILROAD CORP.
7.8	ACRE	MULCHING
3.4	ACRE	SEEDING AND FERTILIZING (RURAL)
1	ACRE	SEEDING AND FERTILIZING (URBAN)
3.4	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
8570	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.
8570	LF	REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE
24	EACH	MOBILIZATIONS, EROSION CONTROL
2	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL

Date: 5/5/2025 Local Agency Official: Bryan Horesowsky, County Engineer



County:	Montgomery County	Project No.:	L-RO1702-69
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	7/15/2025	Time of Letting:	09:15 AM
Bid Turn-In Location:	County Auditor	Type of Project:	Corrugated Metal Pipe Culvert
Contact Phone No.:	712-623-5197	Contact FAX No.:	712-623-9477

Specific Description of Project:

Remove existing Steel I-Beam bridge with concrete deck and install 120" x 84'-0 Corrugated Metal Pipe (CMP) roadway culvert. CMP culvert provided by Montgomery County and stockpiled on site. Project includes all work and material necessary to remove bridge superstructure and install new provided CMP, all associated earthwork, construction of reinforced concrete slope collars and revetment.

QUANTITY	UNIT	DESCRIPTION
1	UNIT	CLEARING AND GRUBBING
644	CY	EMBANKMENT-IN-PLACE
191	CY	EXCAVATION, CLASS 10, CHANNEL
96	CY	COMPACTING BACKFILL ADJACENT TO BRIDGES, CULVERTS OR STRUCTURES
1	LS	REMOVAL OF EXISTING BRIDGE
42	TON	GRANULAR BACKFILL
529	CY	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT
365	CY	EXCAVATION, CLASS 21
76	TON	FOUNDATION TREATMENT MATERIAL
24	CY	STRUCTURAL CONCRETE (MISCELLANEOUS)
2067	LB	REINFORCING STEEL
1	EACH	TEMPORARY STREAM DIVERSION
324	SF	PILES, STEEL SHEET
315	TON	REVETMENT, SPECIAL
69	CY	REVETMENT, REMOVE AND REPLACE
1	LS	CONSTRUCTION SURVEY
1	LS	MOBILIZATION
1	LS	REMOVAL OF ASBESTOS
84	LF	120" CMP, PLACE ONLY, CULVERT PROVIDED BY COUNTY

Date: 5/14/2025 Local Agency Official: Karen Albert, County Engineer