



**SPECIAL PROVISIONS
FOR
SITE REMOVALS**

**Des Moines County
EDP-0977(650)--7Y-29**

**Effective Date
October 20, 2020**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

155047.01 DESCRIPTION.

This work consists of general site removals to allow for replacement and/or installation of new infrastructure improvements. This section includes the furnishing of all labor, materials, permits, tools, equipment, and equipment of all work and services necessary or incidental to the removal of existing miscellaneous items and materials located within the project area not covered under other project line items.

155047.02 MATERIALS.

None.

155047.03 CONSTRUCTION.

- A.** Contractor shall be responsible for reviewing site prior to bid and construction to determine which existing items are included for removal under this section and the extent of the removals.
- B.** Items included for removal under this item may include removal and disposal of benches, plant pots and contents, miscellaneous metal or wood posts, trash and recycling receptacles, tree grates, and other items not listed.
- C.** The Jurisdiction maintains salvage rights to all material, as indicated by Engineer.
- D.** Removal of all items shall follow approved recycling and/or disposal methods for respective materials and items. Contractor shall be responsible for obtaining all permits and paying all fees associated with disposal of items and materials under this section.

155047.04 METHOD OF MEASUREMENT.

Lump sum item; no measurement will be made.

155047.05 BASIS OF PAYMENT.

- A.** Payment will be at the lump sum price for Site Removals. All labor, materials, permits, and equipment necessary for the proper removal and disposal of miscellaneous items within project area approved for removal by the engineer.
- B.** Removal of all items and materials not covered under other project line items shall be included under this item.