



**SPECIAL PROVISIONS
FOR
WOOD FENCE**

**Johnson County
BROS-3715(664)--8J-52**

**Effective Date
September 21, 2021**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

156194.01 DESCRIPTION.

A. General.

Furnish all material, set posts, and erect the fence according to the contract documents.

B. Submittals.

Upon request, submit certification that products supplied comply with identified specifications.

156194.02 MATERIALS.

Fence materials, layout, and appearance shall match the existing fence at the property. General product requirements are listed below, but the Contractor is responsible for evaluating the existing fence to ensure uniformity when the proposed fence ties in the existing fence.

A. Pickets: Use cedar wood, 6 foot height, 5.5 inch average width, dog ear cut on top.

B. Posts: Use cedar wood, 9 foot height, 3 feet of which is buried underground

C. Backer Rails: Use cedar wood, 2 inch height.

156194.03 CONSTRUCTION.

Fence materials, layout, and appearance shall match the existing fence at the property. General installation requirements are listed below, but the Contractor is responsible for evaluating the existing fence to ensure uniformity when the proposed fence ties into the existing fence.

A. Pickets: Place pickets on the outside of the fence, facing south towards the trail and creek.

B. Posts: Install posts with uniform spacing on the inside of the fence. There shall be approximately 17 pickets between each post.

C. Backer Rails: Install three rails along the inside of the fence with 2 foot vertical spacing between rails.

156194.04 METHOD OF MEASUREMENT.

Wood Fence per linear feet constructed, of the height and type specified, measured along the fence at the bottom.

156194.05 BASIS OF PAYMENT.

- A. Per linear foot.
- B. Payment is full compensation for furnishing all material and for construction of Wood Fence as provided herein, including clean up after the work is complete.