



**SPECIAL PROVISIONS
FOR
FOOTINGS FOR CONCRETE PIPE APRONS**

**Linn County
TAP-U-1187(799)--8I-57**

**Effective Date
September 21, 2021**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

157175.01 DESCRIPTION.

This section covers the furnishing of all labor, materials, tools, equipment and performances of all work and services necessary or incidental for the construction of footings for concrete pipe aprons as indicated on the drawings or as specified herein.

157175.02 MATERIALS.

A. Concrete.

- 1. Precast:** Comply with Section 2419 of the Standard Specifications and ASTM C 478.
- 2. Cast-in-place:** Use Class C concrete. Apply Section 2403 of the Standard Specifications.

B. Reinforcement: Apply Section 2404 of the Standard Specifications.

157175.03 CONSTRUCTION.

Comply with the detail included in the plans.

157175.04 METHOD OF MEASUREMENT.

Each footing of a particular diameter installed at a concrete pipe apron will be counted.

157175.06 BASIS OF PAYMENT.

Payment will be made at the unit price for each footing of a particular diameter. Unit price shall include, but is not limited to, excavation; dewatering; reinforcing steel; concrete; furnishing and installing apron; furnishing, placing and compacting bedding and backfill material.