



**SPECIAL PROVISIONS
FOR
WAYFINDING KIOSK**

**Scott County
STP-U-4252(604)--70-82**

**Effective Date
February 18, 2025**

THE STANDARD SPECIFICATIONS, SERIES 2023, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

236036.01 DESCRIPTION.

- A.** Wayfinding Kiosk for the project includes Kiosk to match existing kiosk in Phase 1.
- B.** Kiosk location is found on plans. Concrete foundation shall be constructed per vendor's specifications.
- C. Submittals.**
 - 1.** Shop Drawings: Submit complete shop drawings for the kiosk from Cornerstone Kiosk. Shop drawings shall consist of plans showing all sides of kiosk. Plans to cover mounting, footings, and all fasteners.
 - 2.** Submit fabrication and installation schedule that includes lead times.
 - 3.** Maintenance instructions and product specifications for all components including finishes, shall be provided to Contracting Authority upon completion of accepted work.
- D. Design Criteria.**

Utilize Kiosk configuration that matches the existing kiosk in phase 1 located approximately 130 feet south of the intersection of Dodge Street and S Cody Road on the east side of S Cody Road.
- E. Warranty.**

Cabinet warranted for 3 years.

236036.02 MATERIALS.

- A.** Provide materials submittal per Cornerstone Kiosk, 8227 Marina Pacific Drive, N. Long Beach, California.

- B. All necessary electrical conduit, wire, and lighting within the kiosk shall be per manufacturer's specifications.

236036.04 CONSTRUCTION.

A. Examination.

Examine the conditions under which site signage is to be installed and notify the Engineer of conditions detrimental to the proper and timely completion of the work. Do not proceed with the work until unsatisfactory conditions have been corrected in a manner acceptable to the Engineer.

B. Installation.

1. Verify and stake the exact sign locations on site walk-thru with Engineer for all kiosk locations.
2. Install kiosk plumb, level, square and true to line.
3. Securely anchor signage in proper location using foundations, anchors, anchorages, fasteners, or other methods approved on shop drawings. All anchors and fasteners shall be appropriate to the anchorage condition and per kiosk supplier.
4. Coordinate work, access to site, staging and traffic control with the Engineer.

236036.05 METHOD OF MEASUREMENT.

Items will be measured per each as documented.

236036.06 BASIS OF PAYMENT.

- A. Payment will be for the measured quantity at the contract unit price for the type and size of each bid item. This payment shall be full compensation for, fabrication, delivery to site, furnishing material, labor, tools necessary, and installation of items.
- B. Payment for kiosks shall be per each installation. Includes final design, engineering, fabrication, reinforced concrete foundation, electrical, and installation of kiosk. Graphic content to be provided by City of LeClaire.